

RFQ NO:0002718- Renovations to NHLS Queenstown Laboratory at the Queenstown Hospital,5319.

Compulsory Site Briefing
Venue: NHLS Queenstown Laboratory
Date: 06 February 2025

Time: 09h30 - 10h00 Contact: Pumla Prusent -: 045 389 4483

ISSUED BY:

SUPPLY CHAIN MANAGEMENT NATIONAL HEALTH LABORATORY SERVICE 1 MODDERFONTEIN ROAD SANDRINGHAM 2092 PREPARED BY:

SUPPLY CHAIN MANAGEMENT NATIONAL HEALTH LABORATORY SERVICE NO.1 MODDERFONTEIN ROAD SANDRINGHAM 2092

Quotation Queries:	Technical Queries:	
CONTACT NAME: Ziphozihle Ceza	CONTACT NAME: Cornelius Swarts	
TELEPHONE:041 395 6165	TELEPHONE: 011 386 6021/ 082 809 5978	

	TENDEDED.		
VAIVIE UE	I ENDERER:	 	

CLOSING DATE: 14 FEBRUARY 2025

Site Briefing: Compulsory

Venue: NHLS Queenstown Laboratory

Date : 06 February 2025 Time : 09h30 - 10h00

Contents

PART A.	Error! Book	kmark not defined.
THE QUO	TATION PROCEDURES	4
A 1.1 NOT	ICE AND INVITATION TO SUBMIT	3
	FOR QUOTATION	
TERMS AN	ND CONDITIONS FOR BIDDING	4
	FERENTIAL PROCUREMENT REGULATIONS, 2022 (OBJECTIVE CRITERIA)	
	MISSION DATA	
	RETURNABLE DOCUMENTS AND SCHEDULES	
B 2.1	LIST OF RETURNABLE DOCUMENTS	17
B. 2.2	RETURNABLE SCHEDULES Bookmark not defined17	Error!
FORM A:	CERTIFICATE OF TENDERER'S ATTENDANCE OF BRIEFING SESSION, if applic	cableError! Bookmark not def
FORM B:	VENDOR NUMBER REGISTRATION WITH CENTRAL SUPPLIER DATABASE	17
FORM C:	TAX COMPLIANCE	18
FORM D:	PREFERENCE SCHEDULE	19
FORM E:	PROOF OF REGISTRATION WITH CIDB	29
FORM F:	DECLARATION OF INTEREST	27
FORM G:	DECLARATION OF BIDDER'S PAST SUPPLY CHAIN MANAGEMENT PRACTICE	S32
FORM H:	OHS ACT DECLARATION AND SUBMISSION	34
FORM I:	COID CERTIFICATE ISSUED BY DEPARTMENT OF LABOUR	31
FORM J:	SCHEDULE OF BIDDER'S EXPERIENCE IN PROJECTS	33
	DATA	
PART C1:	PRICING DATA AND BILL OF QUANTITIES	38
C2.1	PRICING INSTRUCTIONS	
PART C3:	SCOPE OF WORK	41
C3.1 DESC	CRIPTION OF WORKS	
C3 3 VVIVI	TYLIDES	

PART A

REQUEST FOR QUOTATION PROCEDURES

1.1 NOTICE AND INVITATION TO SUBMIT QUOTATIONS

National health Laboratory Service (NHLS) invites quotations for the request, Renovations for Queenstown LAB

Preferences are offered to tenderers for Broad-Based Black Economic Empowerment (B-BBEE) Status Level of Contribution in terms of the Preferential Procurement Regulations, 2022. Exempted Micro Enterprises (EME) or Qualifying Small Enterprises (QSE) the specific goals will be applicable.

Only tenderers who are already registered in terms of the Construction Industry Development Regulations in CIDB grading designation **2GB or HIGHER** are eligible to submit Quotation.

COMPULSORY BRIEFING AND SITE INSPECTION

A compulsory clarification meeting will take place at NHLS QUEENSTOWN HOSPITAL, On 06 FEBRUARY 2024 At 09:30am.

The tenderer shall inspect and examine the Site and its surroundings and shall satisfy himself/herself before submitting his/her quotation. The tenderer must be represented at the site inspection by a person who is suitably qualified and experiences to comprehend the implications of the work involved. Attendance of the site inspection is compulsory, and a tender will be disqualified if the site inspection is not attended by a representative of the tenderer.

The NHLS will evaluate tenders received during the First stage in terms of the method of evaluation stated in the submission data and award the contract in terms of these conditions of tender.

Technical quotation will be evaluated on Administrative / Mandatory Requirements and on Functionality.

Bidders who fail to obtain a minimum of 80% for technical evaluation will not be considered further.

Financial quotation will be evaluated on price and B-BBEE as outlined in this document.

The Closing Date and Time for receipt of Quotation is 14 February 2025 at 11h00am

Only Quotation complying with the following requirements will be considered:

- i) The request for quotations for contractors who have a CIDB contractor grading as outlined above
- ii) Quotation submitted on the prescribed NHLS RFQ
- iii) Quotation should be hand delivered to: NHLS LAB, Cnr of Eastbourne & Buckingham Road, Mount Croix at Reception

Requirements for sealing, addressing, delivery, opening and assessment of quotation are stated in the Submission Data.

REQUEST FOR QUOTATION

PART A REQUEST FOR QUOTATION

YOU ARE HEREBY INVITED TO SUBMIT AN RFQ FOR RENOVATIONS AT NHLS QUEENSTOWN LABORATORY					
RFQ NUMBER:	0002718	CLOSING DATE:	14 FEBRUARY 2025	CLOSING TIME:	11h00am
DESCRIPTION	DESCRIPTION Renovations at NHLS Queenstown Laboratory, Corner Kingsway and Livingstone St, Komani, 5320			gstone St,	
THE SUCCESSFUL BIDDER WILL BE REQUIRED TO FILL IN AND SIGN A WRITTEN CONTRACT FORM (MBD7.1) OR AGRREMENT OF FORM OF OFFER AND ACCEPTANCE.					

SUPPLIER INFORMATION				
NAME OF BIDDER				
POSTAL ADDRESS				
STREET ADDRESS				
TELEPHONE NUMBER	CODE		NUMBER	
CELLPHONE NUMBER				
FACSIMILE NUMBER	CODE		NUMBER	
E-MAIL ADDRESS				
VAT REGISTRATION NUMBER				
TAX COMPLIANCE STATUS	TCS PIN:	OR	CSD No:	
B-BBEE STATUS LEVEL VERIFICATION CERTIFICATE [TICK APPLICABLE BOX]	☐ Yes ☐ No	B-BBEE S' SWORN A	TATUS LEVEL FFIDAVIT	☐ Yes ☐ No

[A B-BBEE STATUS LEVEL VERIFICATION CERTIFICATE/ SWORN AFFIDAVIT (FOR EMES & QSEs) MUST BE SUBMITTED IN ORDER TO QUALIFY FOR PREFERENCE POINTS FOR B-BBEE]

1. ARE YOU THE ACCREDITED REPRESENTATIVE IN SOUTH AFRICA FOR THE GOODS /SERVICES /WORKS OFFERED?	☐ Yes ☐ No [IF YES ENCLOSE PROOF]	ARE YOU A FOREIGN BASED SUPPLIER FOR THE GOODS /SERVICES /WORKS OFFERED?	☐ Yes ☐ No [IF YES, ANSWER PART B:3]
2. TOTAL NUMBER OF ITEMS OFFERED			
3. SIGNATURE OF BIDDER		4. DATE	
5. CAPACITY UNDER WHICH THIS BID IS SIGNED			
BIDDING PROCEDURE ENQUIRE	ES MAY BE DIRECTED TO:	TECHNICAL INFOI	RMATION MAY BE DIRECTED
BIDDING PROCEDURE ENQUIRED DEPARTMENT/ORGANIZATION	ES MAY BE DIRECTED TO:		Cornelius Swart
		TO: CONTACT	
DEPARTMENT/ORGANIZATION	NHLS	TO: CONTACT PERSON TELEPHONE	Cornelius Swart
DEPARTMENT/ORGANIZATION CONTACT PERSON	NHLS Ziphozihle Ceza	TO: CONTACT PERSON TELEPHONE NUMBER FACSIMILE	Cornelius Swart 011 386 6548 / 082 809 5978

PART B

1.	BID SUBMISSION:
1.1.	BIDS MUST BE DELIVERED BY THE STIPULATED TIME TO THE CORRECT ADDRESS. LATE BIDS WILL NOT BE ACCEPTED FOR CONSIDERATION.
1.2.	ALL BIDS MUST BE SUBMITTED ON THE OFFICIAL FORMS PROVIDED-(NOT TO BE RE-TYPED)
1.3.	THIS BID IS SUBJECT TO THE PREFERENTIAL PROCUREMENT POLICY FRAMEWORK ACT AND THE PREFERENTIAL PROCUREMENT REGULATIONS, 2017
2.	TAX COMPLIANCE REQUIREMENTS
2.1.	BIDDERS MUST ENSURE COMPLIANCE WITH THEIR TAX OBLIGATIONS.
2.2.	BIDDERS ARE REQUIRED TO SUBMIT THEIR UNIQUE PERSONAL IDENTIFICATION NUMBER (PIN) ISSUED BY SARS TO ENABLE THE ORGAN OF STATE TO VIEW THE TAXPAYER'S PROFILE AND TAX STATUS.
2.3.	APPLICATION FOR THE TAX COMPLIANCE STATUS (TCS) CERTIFICATE OR PIN MAY ALSO BE MADE VIA E-FILING. IN ORDER TO USE THIS PROVISION, TAXPAYERS WILL NEED TO REGISTER WITH SARS AS E-FILERS THROUGH THE WEBSITE WWW.SARS.GOV.ZA.
2.4.	FOREIGN SUPPLIERS MUST COMPLETE THE PRE-AWARD QUESTIONNAIRE IN PART B: 3.
2.5.	BIDDERS MAY ALSO SUBMIT A PRINTED TCC CERTIFICATE TOGETHER WITH THE BID.
2.6.	IN BIDS WHERE CONSORTIA / JOINT VENTURES / SUB-CONTRACTORS ARE INVOLVED, EACH PARTY MUST SUBMIT A SEPARATE TCC CERTIFICATE / PIN / CSD NUMBER.
2.7.	WHERE NO TCC IS AVAILABLE BUT THE BIDDER IS REGISTERED ON THE CENTRAL SUPPLIER DATABASE (CSD), A CSD NUMBER MUST BE PROVIDED.
3.	QUESTIONNAIRE TO BIDDING FOREIGN SUPPLIERS
3.1.	IS THE ENTITY A RESIDENT OF THE REPUBLIC OF SOUTH AFRICA (RSA)? YES NO
3.2.	DOES THE ENTITY HAVE A BRANCH IN THE RSA? ☐ YES ☐ NO
3.3.	DOES THE ENTITY HAVE A PERMANENT ESTABLISHMENT IN THE RSA? YES NO
3.4.	DOES THE ENTITY HAVE ANY SOURCE OF INCOME IN THE RSA?
3.5.	IS THE ENTITY LIABLE IN THE RSA FOR ANY FORM OF TAXATION?
A T	HE ANSWER IS "NO" TO ALL OF THE ABOVE, THEN IT IS NOT A REQUIREMENT TO REGISTER FOR AX COMPLIANCE STATUS SYSTEM PIN CODE FROM THE SOUTH AFRICAN REVENUE SERVICE RS) AND IF NOT REGISTER AS PER 2.3 ABOVE.

NB: FAILURE TO PROVIDE ANY OF THE ABOVE PARTICULARS MAY RENDER THE BID INVALID. NO BIDS WILL BE CONSIDERED FROM PERSONS IN THE SERVICE OF THE STATE.

SIGNATURE OF BIDDER:	
CAPACITY UNDER WHICH THIS BID IS SIGNED:	
DATE:	

IMPORTANT NOTICE

Bidders should ensure that request for quotation are hand delivered to NHLS RECEPTION, RFQ BOX, NO.1 MODDERFONTEIN ROAD, SANDRINGHAM, JHB. If the bid is late, it will not be accepted for consideration.

Quotation must be submitted on the official forms – (not to be re-typed)

The contractor will be responsible for final measurements.

Writing must be in block letters and black ink.

This bid is subject to the Preferential Procurement Policy Framework Act and the Preferential Procurement Regulations, 2017, National health Laboratory Services (NHLS)

PREFERENTIAL PROCUREMENT REGULATIONS, 2022 (OBJECTIVE CRITERIA)

According to the Preferential Procurement Policy Framework Act (PPPFA), 2000: Preferential Procurement Regulations, 2022

The tender will be awarded subject to section 2(1)(f) of the Preferential Procurement Policy Framework Act, 2000 (Act No. 5 of 2000). Section 2 (1)(f) of the Act states that "the contract must be awarded to the tenderer who scores the highest points, unless objective criteria in addition to those contemplated in paragraph (d) and (e) justify the award to another tenderer".

Section (d) of the PPPFA state that "the specific goals may include – contracting with persons, or categories of persons, historically disadvantaged by unfair discrimination on the basis of race, gender or disability; and implementing the programmes of the Reconstruction and Development Programme as published in Government Gazette No. 16805 dated 23 November 1994. Section (e) of the PPPFA states that "any specific goal for which a point must be awarded, must be clearly specified in the invitation to submit a tender".

The NHLS will evaluate the **past performance** of the bidder by assessing the completed project awarded in the past within the NHLS as an **OBJECTIVE CRITERIA**

SCHEDULE OF WORK CARRIED OUT BY THE BIDDER

The bidder must indicate in the table below a complete list of contracts awarded by the NHLS, including the current contracts, if any. This information shall be deemed to be material to the award of this bid. If the bidder has three (3) or more projects that are not completed within the NHLS, the NHLS will justify the award to another tenderer. NB: Failure to disclose the information required will lead to disqualification.

SUBMISSION DATA

Clause number	er Submission Data	
	This Request for quotations intended to allow the successful bidder to specify and present their skills and expertise for the above mentioned services to CIDB. Final acceptance of any quotation is not guaranteed, this being the exclusive right of CIDB.	
	Terms and conditions of expression of interest (Annex D as published/ amended by CIDB in August 2019) contained in Annex D of the CIDB Standard for Uniformity in National Health Laboratory Services (August 2019) as published in Government Gazette No 42622, Board Notice 423 of 2019 of 08 August 2019. (See www.cidb.org.za).	
	The standard conditions of expression of interest for procurements make several references to the submission data for details that apply specifically to this quotation. The submission data shall have precedence in the interpretation of any ambiguity or inconsistency between it and the standard conditions of tender.	
	Each item of submission data given below is cross-referenced to the clause in the standard conditions of tender to which it mainly applies.	
A.1.1	The employer is the NHLS	
B.1.2	For this contract, the following documents will be adopted:	
	The single volume procurement document issued by the employer comprises of the following:	
	The Request for quotation	
	Part A 1: Tendering procedures	
	A 1.1 - Notice and invitation to Submit Proposal	
	B 1.2 - Submission data	
	Part B.2: Returnable documents B.2.1 - List of returnable documents	
	B.2.2 – Mandatory documents and	
	Technical	
	Part C2 - Pricing Data	
	C2.1 – Bill of Quantity (BOQ)	
C.1.4	The Employer's agent for the purpose of this quotation is deemed to be the authorised and designated representative of the Employer: Name: Procurement Office	
	E-mail Address: procurement.EC@nhls.ac.za	
C1.5	Cancellation and Re-Invitation of Tenders	
C.1.5.1	An employer may, prior to the award of the RFQ, cancel a RFQ if-	
	a) due to changed circumstances, there is no longer a need for the NHLS Standard spec	
	b) funds are no longer available to cover the total envisaged expenditure; or	
	c) no acceptable tenders are received.	
	d) there is a material irregularity in the tender process.	

C.1.5.2	The decision to cancel request for quotation must be published in the same manner in which the original request for quotation was advertised		
C.1.5.3	An employer may only with the prior approval of the relevant treasury cancel request for quotation invitation for the second time.		
D.1.6	Procurement procedures		
D.1.6.1	Unless otherwise stated in the submission data, a contract will, subject to E.3.13, be concluded with the tenderer who in terms of E.3.11 is the highest ranked or the bidder scoring the highest number of RFQ evaluation points, as relevant, based on the RFQ submissions that are received at the closing time for RFQ.		
D.2.	Competitive negotiation procedure		
D.2.1	highest ranked in tern enter into competitive	ers or at least a minimum of not less than as of the evaluation criteria stated in the negotiations based on the principle of each associated information.	submission data shall be invited to
Notwithstanding the provisions of E.2.17, the employer may request that tenders be a specified and fine-tuned in order to improve a tenderer's competitive position provided the clarification, specification, fine-tuning or additional information does not alter any fund aspects of the offers or impose substantial new requirements which restrict or distort competative a discriminatory effect.			petitive position provided that such
D.2.3	At the conclusion of each round of negotiations, tenderers shall be invited by the employer to revise their tender offer based on the same evaluation criteria, with or without adjusted weightings. Tenderers shall be advised when they are to submit their best and final offer.		
D.2.4	The contract shall be awarded in accordance with the provisions of E.3.11 and E.3.13 after tenderers have been requested to submit their best and final offer.		
E.2	Tenderer's obligation	ns	
E.2.1	Eligibility		
	g		
		who satisfy the following criteria are eligible	e to submit tenders:
		who satisfy the following criteria are eligible	e to submit tenders:
	Only those tenderers van CIDB registration Only tenderers who	who satisfy the following criteria are eligible are already registered in terms of the 0 db grading designation 2GB or higher are	Construction Industry Development
	Only those tenderers van CIDB registration Only tenderers who a Regulations 25(2) in ci For the sake of clarity specified at the tender	are already registered in terms of the order and subject to satisfactory proof of a term of the cared value, the Employer lists in the table in the event that the sum tendered excellence.	Construction Industry Development e eligible to submit quotation. Inderer's ability to perform the work ble below the margins it considers
	Only those tenderers van a) CIDB registration Only tenderers who a Regulations 25(2) in ci For the sake of clarity specified at the tenderers on able. However,	are already registered in terms of the order and subject to satisfactory proof of a term of the cared value, the Employer lists in the table in the event that the sum tendered excellence.	Construction Industry Development e eligible to submit quotation. Inderer's ability to perform the work ble below the margins it considers

	2	R1.0 m	discretion in terms of CIDB
	3	R3.0 m	 Practice Note 3 on allowable margins to be accepted
	4	R6.0 m	
	5	R10.0 m	
	6	R20.0 m	
	7	R60.0 m	
	8	R200.0 m	
E.2.2	(a) Availability of re(b) Availability of sk(c) Previous experience	ills to manage and perform the contract ence on contracts of a similar value and nat ompanies' letterhead stating that the contra lect	ture
E.2.	Cost of Tendering		
E.2.1	The Employer will not compensate the tenderer for any costs incurred in attending interviews or making any submissions in the office of the Employer		
E.2. 3	The cost of the tender documents charged by the employer shall be limited to the actual cost incurred by the employer for printing the documents. Employers must attempt to make available the tender documents on its website so as not to incur any costs pertaining to the printing of the RFQ documents.		
F.3.1	Check documents Check the tender documents on receipt for completeness and notify the employer of any discrepancy or omission.		
F.4.1.	Confidentiality and copyright of documents Treat as confidential all matters arising in connection with the RFQ, Use and copy the documents issued by the employer only for the purpose of preparing and submitting a RFQ response to the invitation.		
F.4.2	Acknowledge addenda Acknowledge receipt of addenda to the tender documents, which the employer may issue, and if necessary apply for an extension to the closing time stated in the RFQ submission data, in order to take the addenda into account.		
F.4.3	Clarification meeting A compulsory clarification meeting with representatives of the Employer will take place at NHLS QUEENSTOWN HOSPITAL ON 06 FEBRUARY 2025 @09H30 Bidder must sign the attendance list in the name of the bidding entity. Addendam will be issued to		

	the bidders only from those bidding entities appearing on the attendance list.
F.4.4	Seek clarification
	Request clarification of the tender documents, if necessary, by notifying the employer at least five (3) working days before the closing time stated in the NHLS RFQ, (COIDA)
F.4.5	Insurance
	Be aware that the extent of insurance to be provided by the employer (if any) might not be for the full cover required in terms of the conditions of contract identified in the contract data. The tenderer is advised to seek qualified advice regarding insurance.
F.5.1.	Pricing the RFQ BOQ
F.5.2.	This contract shall not be subject to Contract Price Adjustments, foreign fluctuations, etc and all rates and prices shall remain FIXED, final and binding for the full duration of this contract.
F.6.1	Alterations to documents
	Do not make any alterations or additions to the tender documents, except to comply with instructions issued by the employer, or necessary to correct errors made by the tenderer. All signatories to the tender offer shall initial all such alterations.
F.6.2	Alternative RFQ offers
	No alternative tender offers will be considered
F.7.	Submitting a RFQ Responses
F.1.1	Submit one tender offer only as a single tendering entity to provide the whole of the works identified in the contract data and described in the scope of works, unless stated otherwise in the RFQ document
F.1.2	Return all returnable documents to the employer after completing them in their entirety, either electronically (if they were issued in electronic format) or by writing legibly in non-erasable ink.
F.1.3	Submit the parts of the RFQ offer communicated on paper as an original the RFQ Document with an English translation of any documentation in a language other than English, and the parts communicated electronically in the same format as they were issued by the employer.
F.1.4	Sign the original of the RFQ Document where required in terms of the RFQ document. The employer will hold all authorized signatories liable on behalf of the RFQ
F.1.5	Bidders are requested to deliver the submission in one envelope. The Employer's address for delivery of RFQ and identification details to be shown on each tender offer package are:
	Title to appear on envelope or attachment one(1):
	1. RFQ:0002718- RENOVATIONS TO QUEENSTOWN NHLS LABORATORY.
	This envelope must contain the Returnables, SCM Documentation and Relevant Annexures. This envelope must contain printed copies of all the pages in this document, duly completed and signed,
	Title to appear on envelope or attachment two (2):
	2. RFQ NO.: (FINANCIAL QUOTATIONS)
	RFQ NO: 0002718 - RENOVATIONS TO QUEENSTOWN HOSPITAL

	This envelope will contain the Pricing Schedules (Bills of Quantities) and RFQ document as published.
	For identification purposes, bidders are requested to ensure that the envelopes containing the company's bids are clearly marked and are easily identifiable by the company's logo or name.
	Location of tender box: NHLS Port Elizabeth Building RFQ BOX
	Physical address: BUCKINGHAM ROAD, PORT ELIZABETH 6390
	Identification details: RFQ BOX
F.1.6.1	Accept that the employer will not assume any responsibility for the misplacement or premature opening of the tender offer if the outer package is not sealed and marked as stated.
F.1.6.2	Closing time
	The closing time for submission of Quotation is 14 FEBRUARY 2025 at 11h00am.
	CIDB is not obliged to accept the lowest or any tender and reserves the right to accept any tender in whole or in part.
F.1.6.3	The RFQ validity 90 days period is from the closing date.
F.2.	Clarification of tender offer after submission Provide clarification of request for quotation in response to a request to do so from the employer during the evaluation of tender offers. This may include providing a breakdown of rates or prices and correction of arithmetical errors by the adjustment of certain rates or item prices (or both). No change in the competitive position of tenderers or substance of the tender offer is sought, offered, or permitted.
F.2.1	The Tenderer shall, when requested by the Employer to do so, submit the names of all management and supervisory staff that will be employed to supervise the labour-intensive portion of the works together with satisfactory evidence that such staff members satisfy the eligibility requirements.
F.2.2	Inspections, tests and analysis
	Provide access during working hours to premises for inspections, tests and analysis as provided for in the submission data.
F.2.3	Submit securities, bonds and policies
	If requested, submit for the employer's acceptance before formation of the contract, all securities, bonds, guarantees, policies and certificates of insurance required in terms of the conditions of contract identified in the contract data.
F.2.3.1	Provide access during working hours to premises for inspections, tests and analysis as provided for in the submission data.
F.2.3.2	The Tenderer is required to submit with his/her tender all documents and schedules listed under E2.1 and E2.2.
F.2.3.3	Canvassing and obtaining of additional information by tenderers
	The Tenderer shall not make any attempt to obtain particulars of any relevant information, other than that disclosed at the opening of tenders.
E.2.4.3	Prohibitions on awards to persons in service of the state
	The Employer is prohibited to award a quotation to a person -

	<u> </u>				
	a) who is in the service of the state; or				
	b) if that person is not a natural person, of which any director, manager, principal shareholder or stakeholder is a person in the service of the state; or				
	c) a person who is an advisor or consultant contracted with the Department.				
	In the service of the state means to be -				
	a) a member of:-				
	any municipal council;				
	any provincial legislature; or				
	the National Assembly or the National Council of Provinces;				
	b) a member of the board of directors of any municipal entity;				
	c) an official of any municipality or municipal entity;				
	d) an employee of any national or provincial department;				
	e) provincial public entity or constitutional institution within the meaning of the Public Finance Management Act, 1999 (Act No.1 of 1999);				
	f) a member of the accounting authority of any national or provincial public entity; or				
	g) An employee of Parliament or a provincial legislature.				
	In order to give effect to the above, the questionnaire for the declaration of interests in the tender of persons in service of state in part E2 of this procurement document must be completed.				
0.0	•				
G.3.	The employer's undertakings				
Add the following new clause G.3.1	Respond to requests from the tenderer The Employer will respond to requests for clarification received up to five (3) working days before the tender closing time.				
Add the following new clause G.3.2	Issue Addenda Addenda will be issued until five (3) working days before the tender closing time.				
	A sistematical arrang aminaiana and disagrapsing				
H.4	Arithmetical errors, omissions and discrepancies				
H.4.1	Check the highest ranked tenders or tenderers with the highest number of tender				
	evaluation points after the evaluation of tender offers in accordance with E.3.11 for:				
	a) the gross misplacement of the decimal point in any unit rate;				
	b) omissions made in completing the pricing schedule or bills of quantities; or				
	c) arithmetic errors in:				
	line item totals resulting from the product of a unit rate and a quantity in bills of quantities of schedules of prices; or the summation of the prices.				
H.4.2	The arithmetical errors shall be corrected in the following manner:				
	a) Where there is a discrepancy between the amounts in words and amounts in figures, the amount in words shall govern.				
	b) If bills of quantities or pricing schedules apply and there is an error in the line item total				

resulting from the product of the unit rate and the quantity, the line item total shall govern and the rate shall be corrected. Where there is an obviously gross misplacement of the decimal point in the unit rate, the line item total as quoted shall govern, and the unit rate shall be corrected.

c) Where there is an error in the total of the prices either as a result of other Corrections required by this checking process or in the tenderer's addition of prices, the total of the prices shall govern and the tenderer will be asked to revise selected item prices (and their rates if bills of quantities apply) to achieve the tendered total of the prices.

The Tender Offer will be rejected if the tenderer does not correct or accept the Correction of the arithmetical error in the manner described above.

H.4.3 Functionality, Price and Preference

The purpose of the evaluation is to ensure and promote compliance with the Constitution, specifically Section 217, which provides that when organs of state contract for goods or services, they must do so in accordance with a system which is fair, equitable, transparent, competitive and cost-effective. The evaluation of bids will be undertaken in 3 stages.

H.4.4 Technical Quotation

Administrative. / Mandatory Requirements

The Technical quotation will be evaluated on Administrative. / Mandatory Requirements and Functionality.

Bidders who fail to meet the minimum requirements for the Technical quotation will not be considered further.

Financial Quotation will be evaluated on price and B-BBEE specific goals as outlined in this document.

During this phase bid documents will be reviewed to determine the compliance with Standard Bidding Documents (SBD), SCM returnable, tax matters and contractor had registered on Central Data Base (CSD) and Construction Industry Development Board (CIDB). All returnable documents must be submitted with the bid documents at the closing date and time of the bid. Bids which do not satisfy the compliance criteria will be disqualified and will not be evaluated further on prequalification criteria.

The bid quotation will be screened for compliance with administrative requirements as indicated below and bidders must circle the correct answer

Item No.	Administrative Requirements	Check/Complianc e	Non- submission shall result in disqualificat ion
1	Master Bid Document	provided and bound	*YES
Included in the Bid Document			
3	SCM - SBD 1 -	Completed and	*YES

	Invitation to Bid	signed	
4	SCM - SBD 2 - Tax Clearance Certificate Requirements	Attached CSD registration number/SARS PIN and CSD summary report	*YES
5	SCM - SBD 4 - Declaration of Interest	Completed and signed	*YES
6	SCM - SBD 6.1 - Preference Points Claim Form in terms of the Preferential Procurement Regulations 2017	Completed and signed	*YES
7	SCM - SBD 8 — Declaration of Bidder's Past Supply Chain Management Practices	Completed and signed	*YES
8	SCM - SBD 9 - Certificate of Independent Bid Determination	Completed and signed(If applicable)	*YES
9	In case of bids where Consortia / Joint Ventures, Consortia/Joint Venture agreement signed by both parties must be submitted with bid quotation	JV agreement completed and signed, if applicable	*YES

*YES – NHLS reserves the right to reject quotations that are not submitted in the prescribed format or where information presented is illegible or incomplete and will not be further evaluated for Mandatory Requirements (Phase 2)

**NO – NHLS reserves the right to request such information during the evaluation process of the quotation and such information must be presented within short notice.

H.4.5 Request for quotation will only be accepted on condition that:

- a) the tenderer is registered with the Construction Industry Development Board in an appropriate contractor grading designation;
- b) the bidder or any of its directors is not listed in the Register of Bid Defaulters in terms of the Prevention and Combating of Corrupt Activities Act of 2004 as a person prohibited from doing business with the public sector;
- c) the bidder has not:

H.5.	The number of paper copies of the signed contract to be provided by the employer is TWO letter of award for any request above 200k, and PO.
	i) Has submitted the documentation listed in E2.21 and E2.22
	d) Has completed the Compulsory Enterprise Questionnaire, SBD4, 6.1, 7.1, 8,9 and there are no conflicts of interest which may impact on the tenderer's ability to perform the contract in the best interests of the employer or potentially compromise the tender process
	ii. failed to perform on any previous contract and has been given a written notice to this effect.
	i. abused the Employer's Supply Chain Management System; or

PART 2: RETURNABLE DOCUMENTS AND SCHEDULES

2.1 LIST OF RETURNABLE DOCUMENTS

2.1.1 These Schedules are required for pre-qualification and eligibility purposes:

2.2.01 Stage one as per CIDB: Eligibility Criteria Schedule-CIDB Registration 2 GB

OR Higher

- 2.1.2 Stage Two as per CIDB: these schedules will be used for evaluation purposes:
 - Technical returnable if applicable

The following documents must be returned by the Bidder for evaluation purposes in addition to the Schedule listed in previous paragraphs.

	THE FOLLOWING DOCUMENTS MUST BE FURNISHED (FAILURE TO SUBMIT COMPULSORY DOCUMENTATION WILL RESULT IN YOUR BID BEING DISQUALIFIED)	YES	NO
1	Tax Compliance (Provide PIN)	Yes 🗌	No 🗆
2	B-BEE Certificate issued by SANAS accredited verification agent/ OR AFFIDAVIT FOR EME/QSE ON DTI FORMAT	Yes 🗌	No 🗆
3	Proof of valid registration with CIDB	Yes 🗌	No 🗌
4	Signed Declaration of Interest	Yes 🗌	No 🗌
5	Certificate of Independent Bidder determination	Yes 🗌	No 🗌
6	Valid COID certificate issued by the Department of Labour	Yes 🗌	No 🗌
7	Submit an original Briefing session certificate of attendance	Yes 🗌	No 🗌
8	Fully Completed and Signed all other SBD forms	Yes 🗌	No 🗌

2.2.01: Eligibility Criteria Schedule-CIDB Grading Designation

Note to bidders:

Bidders are to indicate their CIDB Grading by filling in the table below. Attach a copy of the CIDB Grading Designation or Evidence of being capable of being so registered.

CRS Number	Status	Grading	Expiry Date

ORM B: VENDOR NUMBER REGISTRATION WITH CENTRAL SUPPLIER DATABASE

Bidders must submit Vendor Number Registration with Central Supplier Database

2.	Failure to submit the bidder being disquali		Registration	with Cen	tral Supplier	Database n	nay result	with the
	ENTITY NAME							
	CSD							
	REGISTRATION No	:					•••••	
	NAME							
	SIGNATURE OF BIDDER							
	DATE							
	CAPACITY UNDER	WHICH						

CONDITIONS PERTAINING TO TAX

BID IS SIGNED

TAX CLEARANCE CERTFICATE REQUIREMENTS

FORM C: TAX COMPLIANCE

It is a condition of bid that the taxes of the successful bidder <u>must</u> be in order, or that satisfactory arrangements have been made with South African Revenue Service (SARS) to meet the bidder's tax obligations.

- Any person who requires his or her tax compliance status to be disclosed to a Government institution
 or department, for purposes of submitting a bid or to confirm its good standing after the phasing out
 of paper based TCCs must request a unique security personal identification number (PIN) from
 SARS.
- Very important to note is that the disclosure of a bidder's tax compliance status is an express condition for all acceptable Government bids. Failure to make the relevant disclosures will invalidate your bid and your response will be null and void.
- 3. The Government institution or department must use the PIN referred to above to verify a person's tax compliance status with SARS.

4. Bidders to complete the table below and provide a unique s (PIN) from SARS which will enable the MW to access online compliance status with the electronic Tax Compliance Status PIN may result in the bid being disqualified.	real-time veri	fication of a person's tax				
Full name of bidder:	Electronic Ta Status Systen	x Compliance n PIN No:				
NAME:						
SIGNATURE OF BIDDER						
DATE						
CAPACITY UNDER WHICH BID IS SIGNED						
MANDATORY REQUIREMENTS:						
The bidder who fails to comply with the Mandatory Requirements	will be disqu	alified.				
Technical Suitability: Mandatory Requirements – Renovations						
1 Technical Suitability: Mandatory Requirement						
Bidders must provide details and registration confirmation with CIDB in terms of the CIDB Act 38 of 2000. Provide proof of grading level 2 GB or higher	CIDB in terms of the CIDB Act 38 of 2000.					
Substantiation: The bidder must provide a proof of CIDB information will lead to disqualification.	grading leve	el. Failure to provide				
2 Technical Suitability: Mandatory Requirement						
Bidders must provide at least 2 references for a similar project (no older than 7 years. Bidder must provide proof:	Comply	Do Not Comply				
Substantiation: The bidder must provide proof of at least 2 references letters each accompanied by a completion certificate and Final account certificate of the same projects indicating amongst others the value of the project, time it took to complete the project. Reference letters template (details of the company letterhead, physical address, contactable person name, company contact number and email address) Template checklist for reference letter is attached and must be complied with. Failure to provide information will lead to disqualification.						

3 Technical Suitability: Mandatory Requirement

Provide a trade test certificate for Plumber in your organization or	Comply	Do Not Comply
subcontractor.		
Substantiation: The bidder must provide a proof of Plumber	certificate (T	rade Test Certificate).
Failure to provide information will lead to disqualification		

4 Technical Suitability: Mandatory Requirement

Provide copy of CV and Certificate of experienced project manager to manage the project	Comply	Do Not Comply
Substantiation: The bidder must provide CV and Certificate manage the project	of experience	ed project manager to

5 Technical Suitability: Mandatory Requirement

Provide Air conditioners trade test certificate	Comply	Do Not Comply	
Substantiation: The bidder must provide Air conditioner Trade c			

6. Technical Suitability: Mandatory Requirement

Provide a wiremen's licence certificate of the Electrician in your	Comply	Do Not Comply			
organization or subcontractor to issue an electrical COC (certification of compliance) .					
Substantiation: The bidder must provide a proof of wiremen's licence certificate. Failure to provide					
information will lead to disqualification.					

7. Technical Suitability: Mandatory Requirement

	comply	Do not comply
Specify air conditioner brand		

Reference letter Checklist

	SUBJECT		
1	STANDARD LETTER LAYOUT	Comply	Do not Comply
1.1	Company letterhead		
1.2	Physical Address		

1.3	Contactable Person Full Names: Engineer/Project Manager who signed off the work done:	
1.4	Contact number: Work number and Cellphone number	
1.5	Email address	
2	PROJECT DETAILS	
2.1	Description of the Project	
2.2	Value of the Project	
2.3	Project Duration	
2.4	Date of Completion	
3	RECOMMENDATION	
3.1	Attach Final Account Certificate	

FORM D: PREFERENCE SCHEDULE

PREFERENCE POINTS CLAIM FORM IN TERMS OF THE PREFERENTIAL PROCUREMENT REGULATIONS 2017

This preference form must form part of all bids invited. It contains general information and serves as a claim form for preference points for Broad-Based Black Economic Empowerment (B-BBEE) Status Level of Contribution

NB: BEFORE COMPLETING THIS FORM, BIDDERS MUST STUDY THE GENERAL CONDITIONS, DEFINITIONS AND DIRECTIVES APPLICABLE IN RESPECT OF B-BBEE, AS PRESCRIBED IN THE PREFERENTIAL PROCUREMENT REGULATIONS, 2017.

1. GENERAL CONDITIONS

- 1.1 The following preference point systems are applicable to all bids:
 - the 80/20 system for requirements with a Rand value of up to R50 000 000 (all applicable taxes included); and

1.2

- a) The value of this bid is estimated to be below R50 000 000 (all applicable taxes included) and therefore the 80/20 preference point system shall be applicable;
- 1.3 Points for this bid shall be awarded for:
 - (a) Price; and
 - (b) B-BBEE Status Level of Contributor.
- 1.4 The maximum points for this bid are allocated as follows:

	POINTS
PRICE	80
Specific Goals	20
Total points for Price and Specific Goals must not exceed	100

- 1.5 Failure on the part of a bidder to submit proof of B-BBEE Status level of contributor together with the bid, will be interpreted to mean that preference points for B-BBEE status level of contribution are not claimed.
- 1.6 The purchaser reserves the right to require of a bidder, either before a bid is adjudicated or at any time subsequently, to substantiate any claim in regard to preferences, in any manner required by the purchaser.

2. **DEFINITIONS**

- (a) "B-BBEE" means broad-based black economic empowerment as defined in section 1 of the Broad-Based Black Economic Empowerment Act;
- (b) "B-BBEE status level of contributor" means the B-BBEE status of an entity in terms of a code of good practice on black economic empowerment, issued in terms of section 9(1) of the Broad-Based Black Economic Empowerment Act;
- (c) "bid" means a written offer in a prescribed or stipulated form in response to an invitation by an organ of state for the provision of goods or services, through price quotation, advertised competitive bidding processes or quotations;
- (d) "Broad-Based Black Economic Empowerment Act" means the Broad-Based Black Economic Empowerment Act, 2003 (Act No. 53 of 2003);
- (e) "EME" means an Exempted Micro Enterprise in terms of a code of good practice on black economic empowerment issued in terms of section 9 (1) of the Broad-Based Black Economic Empowerment Act;
- (f) "functionality" means the ability of a tenderer to provide goods or services in accordance with specifications as set out in the tender documents.
- (g) "prices" includes all applicable taxes less all unconditional discounts;
- (h) "proof of B-BBEE status level of contributor" means:
 - 1) B-BBEE Status level certificate issued by an authorized body or person;
 - 2) A sworn affidavit as prescribed by the B-BBEE Codes of Good Practice;
 - 3) Any other requirement prescribed in terms of the B-BBEE Act;
- "QSE" means a qualifying small business enterprise in terms of a code of good practice on black economic empowerment issued in terms of section 9 (1) of the Broad-Based Black Economic Empowerment Act;
- (j) "rand value" means the total estimated value of a contract in Rand, calculated at the time of bid invitation, and includes all applicable taxes;

POINTS AWARDED FOR SPECIFIC GOALS

- 4.1.In terms of Regulation 4(2); 5(2); 6(2) and 7(2) of the Preferential Procurement Regulations, preference points must be awarded for specific goals stated in the tender. For the purposes of this tender the tenderer will be allocated points based on the goals stated in table 1 below as may be supported by proof/documentation stated in the conditions of this tender:
- 4.2.In cases where organs of state intend to use Regulation 3(2) of the Regulations, which states that, if it is unclear whether the 80/20 or 90/10 preference point system applies, an organ of state must, in the tender documents, stipulate in the case of—
- (a) an invitation for tender for income-generating contracts, that either the 80/20 or 90/10 preference point system will apply and that the highest acceptable tender will be used to determine the applicable preference point system; or
- (b) any other invitation for tender, that either the 80/20 or 90/10 preference point system will apply and that the lowest acceptable tender will be used to determine the applicable preference point system,

then the organ of state must indicate the points allocated for specific goals for both the 90/10 and 80/20 preference point system.

Points awarded for historically disadvantaged individuals

Preference points for HDI's are calculated on their percentage shareholding in a business, provided that they are actively involved in and exercise control over the enterprise. The following formula is prescribed

Where:

NEP = Points awarded for equity ownership by an HDI

NOP = The maximum number of points awarded for equity by an HDI in that specific category

EP = The percentage of equity ownership by an HDI within the enterprise or business, determined in accordance with the definition of HDI's.

A consortium or joint venture (including unincorporated consortia and joint ventures) must submit a consolidated B-BBEE Status Level Verification certificate for every separate tender

Table 1: Specific goals for the tender and points claimed are indicated per the table below.

(Note to organs of state: Where either the 90/10 or 80/20 preference point system is applicable, corresponding points must also be indicated as such.

Note to tenderers: The tenderer must indicate how they claim points for each preference point system.POINTS AWARDED FOR B-BBEE STATUS LEVEL OF CONTRIBUTOR

1.7 In terms of Regulation 6 (2) and 7 (2) of the Preferential Procurement Regulations, preference points must be awarded to a bidder for attaining the Specific Goals status level of contribution in accordance with the table below:

The specific goals allocated points in terms of this tender	Number of points allocated (80/20 system) (To be completed by the organ of state)	Percentage owned (To be completed by the tenderer)	Number of points claimed (80/20 system) (To be completed by the tenderer)
HDI	6	%	
WOMAN	4	%	
DISABLED	1	%	
YOUTH	4	%	
Locality	5		
• Eastern Cape Province = 5			
• National = 0			
TOTAL POINTS	20		

BID DECLARATION

1.8 Bidders who claim points in respect of Specific Goals Status Level of Contribution must complete the following:

2. SPECIFIC GOALS STATUS LEVEL OF CONTRIBUTOR CLAIMED IN TERMS OF PARAGRAPHS 1.4 AND 4.1

2.1 Specific Goals = (maximum of 10 or 20 points) (Points claimed in respect of paragraph 7.1 must be in accordance with the table reflected in paragraph 4.1 and must be substantiated by relevant proof of Specific Goals status level of contributor.

3. SUB-CONTRACTING

3.1 Will any portion of the contract be sub-contracted?

(Tick applicable box)				
YES		NO		

3.1.1 If yes, indicate:

i)	What percentage of the contract will be subcontracted		%'
ii)	The name of the sub-contractor		
iii)	The B-BBEE status level of the sub-contractor		
iv)	Whether the sub-contractor is an EME or QSE		
	(Tick applicable box)		
	YES NO		
v)	Specify, by ticking the appropriate box, if subcontracting with Preferential Procurement Regulations, 2017:	h an enterp	rise in term
	- Telefolitari Tocarement (Negalations,2017).	LEVAL	005
Designa	ated Group: An EME or QSE which is at last 51% owned by:	EME √	QSE √
Black p	eople		
·	eople who are youth		
	eople who are women		
	eople with disabilities		
	eople living in rural or underdeveloped areas or townships ative owned by black people		
· ·	eople who are military veterans		
Black p	OR		
Any EM	 JE		
Any QS			
.1 Name	of company/firm: egistration number:		
.4 TYPE	pany registration number		
	oany registration number OF COMPANY/ FIRM		
	······································		
	OF COMPANY/ FIRM		
	OF COMPANY/ FIRM Partnership/Joint Venture / Consortium		
	Partnership/Joint Venture / Consortium One person business/sole propriety Close corporation Company		
	OF COMPANY/ FIRM Partnership/Joint Venture / Consortium One person business/sole propriety Close corporation		
	Partnership/Joint Venture / Consortium One person business/sole propriety Close corporation Company		
 - - Tic	Partnership/Joint Venture / Consortium One person business/sole propriety Close corporation Company (Pty) Limited		
 - - Tic	Partnership/Joint Venture / Consortium One person business/sole propriety Close corporation Company (Pty) Limited KAPPLICABLE BOX]		
 - - Tic	Partnership/Joint Venture / Consortium One person business/sole propriety Close corporation Company (Pty) Limited KAPPLICABLE BOX]		
 - - Tic	Partnership/Joint Venture / Consortium One person business/sole propriety Close corporation Company (Pty) Limited KAPPLICABLE BOX]		

4.

4.	.6 C	AMPAI	NY CLASSIFICATION				
	[_ N	Manufacturer				
	[_	Supplier				
	[□ F	Professional service provider				
	[Other service providers, e.g. tr	ansporte	er, etc.		
	[TICKAI	PPLICABLE BOX]				
4.	.7 To	otal nur	nber of years the company/fire	m has be	een in business:		
4.8 I/we, the undersigned, who is / are duly authorised to do so on behalf certify that the points claimed, based on the Specific Goals status level of in paragraphs 1.4 and 6.1 of the foregoing certificate, qualifies the copreference(s) shown and I / we acknowledge that:				Specific Goals status level of contributor indicated certificate, qualifies the company/ firm for the			
	i) Th	e information furnished is true	and co	rrect;		
	i	•	e preference points claimed licated in paragraph 1 of this t		n accordance with the General Conditions as		
	i	pa					
	i	ba	If the B-BBEE status level of contributor has been claimed or obtained on a fraudule basis or any of the conditions of contract have not been fulfilled, the purchaser may, addition to any other remedy it may have —				
		(a)	disqualify the person from t	he biddi	ng process;		
		(b)	recover costs, losses or dathat person's conduct;	amages	it has incurred or suffered as a result of		
		(c)		-	damages which it has suffered as a result arrangements due to such cancellation;		
		(d)	only the shareholders and restricted by the National T	I director Freasury Acceding	tractor, its shareholders and directors, or rs who acted on a fraudulent basis, be from obtaining business from any organ 10 years, after the audi alteram partem applied; and		
		(e)	forward the matter for crimi	nal pros	ecution.		
WITNES	SSES						
1.	<i>-</i>				SIGNATURE(S) OF BIDDERS(S) DATE		
2.	<i></i>				ADDRESS		

FORM E: PROOF OF REGISTRATION WITH CIDB

1. Attach proof of CIDB registration to this page.

	Firm	CRS Number	CIDB Grading	Lead Partner (Indicate with X)
Com	bined CIDB Grading for Jo	int Venture / Consortium:		
alculator is av	ailable at https://registers.cid	db.org.za/common/jvcalc.asp	<u>o</u>)	1

Full name (in BLOCK letters):

Signature:

Date:

Page 28

FORM F: DECLARATION OF INTEREST

- 1. No bid will be accepted from persons in the service of the state¹.
- 2. Any person, having a kinship with persons in the service of the state, including a blood relationship, may make an offer or offers in terms of this invitation to bid. In view of possible allegations of favouritism, should the resulting bid, or part thereof, be awarded to persons connected with or related to persons in service of the state, it is required that the bidder or their authorised representative declare their position in relation to the evaluating/adjudicating authority.
- 3. In order to give effect to the above, the following questionnaire must be completed and submitted with the bid.
- 3.1 Full Name of bidder or his or her representative:
- 3.2 Identity Number:
- 3.3 Position occupied in the Company (director, trustee, shareholder²):
- 3.4 Company Registration Number:
- 3.5 Tax Reference Number:

¹SCM Regulations: "in the service of the state" means to be –

(a) a member of -

3.6

NO

(i) any municipal council;

VAT Registration Number

- (ii) any provincial legislature; or
- (iii) the national Assembly or the national Council of provinces;
- (b) a member of the board of directors of any municipal entity;
- (c) an official of any municipality or municipal entity;
- (d) an employee of any national or provincial department, national or provincial public entity or constitutional institution within the meaning of the Public Finance Management Act, 1999 (Act No.1 of 1999):
- (e) a member of the accounting authority of any national or provincial public entity; or
- (f) an employee of Parliament or a provincial legislature.
 - ² Shareholder" means a person who owns shares in the company and is actively involved in the management of the company or business and exercises control over the company.

3.7	The names of all directors / trustees / shareholders members, their individual identity numbers an state employee numbers must be indicated in paragraph 4 below.
3.8	Are you presently in the service of the state? YES /

3.8.1 If yes, furnish particulars_____

3.9	Have you been in the service of the s	state for the past twelve mo	onths?	YES/
3.9.1	If yes, furnish particulars			
3.10	Do you have any relationship (family may be involved with the evaluation a NO			
3.10.1	If yes, furnish particulars			
3.11	Are you, aware of any relationship (fain the service of the state who may b	· · · · · · · · · · · · · · · · · · ·	tion and or adjudication of t	•
3.11.1				
3.12	Are any of the company's directors, t service of the state?	rustees, managers, princip	ole shareholders or stakeho	lders in
3.12.1	If yes, furnish particulars			
3.13	Are any spouse, child or parent of the shareholders or stakeholders in serv		• , ,	YES/
3.13.1	If yes, furnish particulars			
3.14	Do you or any of the directors, truste company have any interest in any oth bidding for this contract.	es, managers, principle sh her related companies or b	areholders, or stakeholders	y are
3.14.1	If yes, furnish particulars			
4. Fu	ull details of directors / trustees / meml			
	Full Name	Identity Number	State Employee Number	er
				

Signature		Date	
 C:		 Data	
			

FORM G: DECLARATION OF BIDDER'S PAST SUPPLY CHAIN MANAGEMENT PRACTICES

- 1 This Standard Bidding Document must form part of all bids invited.
- It serves as a declaration to be used by institutions in ensuring that when goods and services are being procured, all reasonable steps are taken to combat the abuse of the supply chain management system.
- 3 The bid of any bidder may be disregarded if that bidder, or any of its directors have
 - a. Abused the institution's supply chain management system;
 - b. committed fraud or any other improper conduct in relation to such system; or
 - c. failed to perform on any previous contract.
- In order to give effect to the above, the following questionnaire must be completed and submitted with the bid.

Item	Question	Ye s No	0
4.1	Is the bidder or any of its directors listed on the National Treasury's Database of Restricted Suppliers as companies or persons prohibited from doing business with the public sector?	Yes	No
	(Companies or persons who are listed on this Database were informed in writing of this restriction by the Accounting Officer/Authority of the institution that imposed the restriction after the audi alteram partem rule was applied).		
	The Database of Restricted Suppliers now resides on the National Treasury's website (www.treasury.gov.za) and can be accessed by clicking on its link at the bottom of the home pg		
4.1.1	If so, furnish particulars:		
4.2	Is the bidder or any of its directors listed on the Register for Tender Defaulters in terms of section 29 of the Prevention and Combating of Corrupt Activities Act (No 12 of 2004)?	Yes	No
	The Register for Tender Defaulters can be accessed on the National Treasury's website (www.treasury.gov.za) by clicking on its link at the bottom of the home page.		
4.2.1	If so, furnish particulars:		
4.3	Was the bidder or any of its directors convicted by a court of law (including a court outside of the Republic of South Africa) for fraud or corruption during the past five years?	Yes	<u>2</u> 0□
4.3.1	If so, furnish particulars:		
4.4	Was any contract between the bidder and any organ of state terminated during the past five years on account of failure to perform on or comply with the contract?	Yes	No
4.4.1	If so, furnish particulars:		

CERTIFICATION

POSITION	NAME	OF	:	BIDDER
SIGNATURE	DA	ΛTE		
I ACCEPT THAT, IN ADDITION TO CANCELL AGAINST ME SHOULD THIS DECLARATION PR		T, ACTION	MAY BE	TAKEN
I, THE UNDERSIGNED (FULL NAME) INFORMATION FURNISHED ON THIS DECLARA		CERTIFY AND CORR		THE

FORM H: OHS ACT DECLARATION AND SUBMISSION

The Bidder declares him/herself/herself to be conversant with the following:

- 1. All the requirements, regulations and standards of the Occupational Health and Safety Act (Act 85 of 1993), hereinafter referred to as "The Act", together with its amendments and with special reference to the following Sections of the Act:
 - i) Section 8: General duties of Employers to their employees
 - ii) Section 9: General duties of Employers and self-employed persons to persons other than employees.
 - iii) Section 13: Duty to Inform
 - iv) Section 37: Acts or omissions by employees or mandatories
 - v) Sub-section 37(2) relating to the purpose and meaning of this Agreement
- 2. Construction Regulations, 2014 (Government Notice R.84) pertaining to the Contractor and to all his Subcontractors, or any amendments thereto.
- 3. Bid document Volume 3: Project Specification PD: Supplement to Volume 5: Specification for Occupational Health and Safety.
- 4. Bid document Volume 3: C1.7 Agreement in terms of Occupational Health and Safety Act.

The Bidder declares that he has or will obtain the necessary knowledge, competence and resources to comply fully with all OHS requirements should he be awarded the contract.

The Bidder confirms that he has included with his bid a written quotation describing how he will comply with OHS requirements

Signature	Date	
Name	 Capacity	
Bidder		

FORM J: SCHEDULE OF BIDDER'S EXPERIENCE IN SERVICE, FOR RENOVATIONS FOR DINING ROOM AND TOILETS FACILITIES TO THE OFFICE OF THE CEO MAIN BUILDING AT NHLS SANDRINGHAM CAMPUS

NHLS shall not be held responsible for incorrect judgement misled by unclear written letters/words on the forms below, to be completed by the Bidder(s). Attachment shall strictly be made where specified and at the correct location, any attachment other than what has been requested by cidb, shall be completely ignored, and scored zero, where points allocation is required.

When completing Forms, Bidder(s) may make copies of the original Forms, should the provided forms be inadequate for their completion of the information required. Forms must be hand completed in black ink, no computer regenerated forms will be accepted. Forms must be completed in full, forms not completed in full shall be rejected by scoring zero.

C.1.1 CONTRACT DATA

PART 1: DATA PROVIDED BY THE EMPLOYER

3.1.3	The Contractor shall obtain the specific approval of the Employer before executing any of his functions or duties according to the following Clauses of the General Conditions of Contract: GCC 2015 3rd Edition			
	1. Clause 5.8.1 Non-working times			
	2. Clause 5.11.1 Suspension of the Works			
	3. Clause 5.12.1 Approval of any extension of time for completion			
	4. Clause 5.12.4 Acceleration of progress instead of extension of time			
	5. Clause 5.13.2 Reduction of a penalty for delay			
	6. Clause 6.3.2 The issuing of variation orders			
	7. Clause 6.8.4 The determination of additional or reduced cost arising from changes			
	in the legislation			
	8. Clause 6.11 The agreeing of the adjustment of the sums for general items			
	9. Clause 10.1.5 The giving of a ruling on a Contractor's claim			
5.3.1	Clause 5.3.1: Commencement of the Works			
	The documentation required before commencement with Works execution are:			
	a) Health and Safety Plan			
	b) Initial programme			
	c) Security			
	d) Insurance			
5.3.2	Clause 5.3.2: Timeframe to deliver documentation The time to submit the documentation required before commencement with Works execution			
	is fourteen (14) days.			
5.4.4	"The Contractor shall bear all costs and charges for special and temporary rights of way required by him/her in connection with access to the Site. The Contractor shall also provide at his own cost any additional facilities outside the Site required by him/her for the purposes of the Works."			
5.8.1	Clause 5.8.1: Non-Working Times			
	The non-working days are Saturdays and Sundays.			
	The special non-working days are:			
	All gazetted public holidays falling outside the year end break.			

	The year-end break commencing on 14 December and ending on 7 January (Provisional).
5.13.1	Clause 5.13.1: Penalty for Delay
	The penalty for failing to complete the Works will be charges per day based on the loss suffered due to delays up to a limit of 30 normal working day, upon which automatic termination will be effected by the Employer.
5.16.3	Clause 5.16.3: Latent defect liability
	The latent defect period is ten (10) years for civil engineering works.
6.8.2	Clause 6.8.2: Contract Price Adjustment
	The Contract Price Adjustment is not applicable in this contract.
6.8.3	Clause 6.8.3: Variation in Cost of Special Materials
	Price adjustments for variations in the costs of special materials are not allowed
6.10.1.5	Clause 6.10.1.5: Interim Payments - Materials on Site
	No percentage advance on materials on site but not yet built into the Permanent Works is allowed for, or will be paid.
6.10.4	Clause 6.10.4: Delivery, dissatisfaction with and payment of payment certificate
	Add the following to clause 6.10.4:
	Notwithstanding the above, the Engineer shall be empowered to withhold the delivery of the payment certificate until the Contractor has complied with his obligations to report in terms of Clause 4.10.2 and as described in the Scope of Work.
8.6.1.1.2	Clause 8.6.1.1.2: Insurance
	The value of the materials supplied by the Employer to be included in the insurance sum is - Nil.
8.6.1.1.3	Clause 8.6.1.1.3: Insurance
	The amount to cover professional fees for repairing damage and loss to be included in the insurance sum is Nil.
8.6.1.3	Clause 8.6.1.3: Insurance
	The limit of indemnity for liability insurance is R5 million for any single claim – the number of claims to be unlimited during the construction.
9.2.1.3.8	The Contractor has furnished inaccurate information in the returnable documents completed at tender stage and forming part of the Contract.
9.2.1.3.9	An official or other role player committed any corrupt or fraudulent act during the procurement process or in the execution of the contract that benefited the Contractor.

10	Clause 10: Dispute Resolution
	"Dispute resolution shall initially be by means of ad-hoc adjudication as per Clause 10.5.2. Should adjudication not be successful, then the dispute shall be referred to Arbitration under the provisions of Clause 10.7.1."
10.4.1	The parties may at time agree to settle disputes with the help of an impartial third party
10.5.3	The number of Adjudication Board Members to be appointed is five (5).
11	Clause 12: Confidentiality The Contractor shall treat the details of the Works comprised in this Contract as private and confidential (save in so far as may be necessary for the purposes hereof) and shall not publish or disclose the same or any particulars thereof in any trade or technical paper elsewhere without prior written consent of the Engineer.
12	Clause 13: Amendments in writing No amendments of this Contract or of any provisions or terms hereof and no waiver or relaxation or suspension of any of the provisions or terms of this Contract shall be of any force or effect unless reduced to writing and signed by both the parties hereto.

PART 2: DATA PROVIDED BY THE CONTRACTOR

The contractor is advised to read the *general conditions of contract for construction works, third edition, 2015* published by the South African institution of civil engineering, private bag x200, halfway house, 1685, in order to understand the implications of this data which is required to be completed. Copies of these conditions of contract may be obtained from www.saice.org.za.

Each item of data given below is cross-referenced to the clause in the Conditions of Contract to which it mainly applies.

Clause	Data
1.1.1.9	The name of the Contractor is:
1.2.1.2	The address of the Contractor is:
	Address (physical):
	Address (postal):
	Telephone:
	e-mail:

C2: PRICING DATA

C2.1PRICING INSTRUCTIONS

1. Measurement and payment clauses of the COLTO (1998)/SANS 1200 Standardised Specifications, as well as the Particular Specifications, shall be deemed to form part of and included in the pricing instructions.

2. The units of measurement described in the Bill of Quantities are metric units. Abbreviations used in the Bill of Quantities are as follows:

% m².pass square metre-pass percent h m^3 cubic metre hour = m³.km cubic metre-kilometre ha = hectare kg kilogram MN meganewton kilolitre MN.m meganewton-metre kΙ km kilometre MPa = megapascal number km-pass kilometre-pass No. = kPa = kilopascal Prov sum = Provisional sum P C sum kW = kilowatt = Prime Cost sum litre sum lump sum metre ton (1 000 kg) m t = = millimetre W/day Work day mm = m^2 square metre

- 3. Unless otherwise stated, items are measured net in accordance with the drawings, and no allowance is made for waste.
- 4. The prices and rates to be inserted in the Bill of Quantities are to be the full inclusive prices for the work described under the items. Such prices and rates shall cover all costs and expenses that may be required in accordance with the provisions of the Scope of Work, and shall cover the cost of all general risks, liabilities, and obligations set forth or implied in the Contract Data, as well as overhead charges and profit. These prices shall be used as a basis for assessment of payment for additional work that may have to be carried out.
- 5. It will be assumed that prices included in the Bill of Quantities are based on Acts, Ordinances, Regulations, By-laws, International Standards and National Standards that were published 28 days before the closing date for tenders. (Refer to www.sabs.co.za or www.iso.org for information on standards).
- 6. Where the Scope of Work requires detailed drawings and designs or other information to be provided, all costs associated therewith are deemed to have been provided for and included in the unit rates and sum amount tendered for such items.
- 7. An item against which no price is entered will be considered to be covered by the other price s or rates in the Bill of Quantities. A single lump sum will apply should a number of items be grouped together for pricing purposes.
- 8. The quantities set out in the Bill of Quantities are approximate and do not necessarily represent the actual amount of work to be done. The quantities of work accepted and certified for payment will be used for determining payments due and not the quantities given in the Bills of Quantities.
- 9. Reasonable compensation will be received where no pay item appears in respect of work required in the Bills of Quantities in terms of the Contract and which is not covered in any other pay item.
- 10. The short descriptions of the items of payment given in the Bill of Quantities are only for the purposes of identifying the items. More details regarding the extent of the work entailed under each item appear in the Scope of Work.
- 11. The Bill of Quantities has been drawn up in accordance with the latest issue of the COLTO (1998)/SABS1200 Standardised Specifications. Descriptions in the Bill of Quantities are abbreviated and must be read in conjunction with the measurement and payment clauses of the applicable specification

SCHEDULE OF QUANTITIES PREAMBLE TO THE SCHEDULE OF QUANTITIES AND RATES

• The standard commercial terms and conditions, special terms and conditions, and specifications (including the project specification.

- The proposer is at liberty to insert a rate of his own choosing for each item in the schedule, and any
 item against which no quantity (where applicable) or rate is entered will be considered to be covered
 by other items in the schedule.
- The quantities and rates inserted in the schedule are to be inclusive prices to the employer for the
 work described under the several items. Such prices shall cover all costs and expenses that may be
 required in and for the works and shall cover the cost of all general risks, liabilities, and obligations
 set forth or implied in the documents on which the tender is based.
- All rates and amounts shall be net, exclusive of value-added tax (vat) and shall be carried to the summary page in their net form. Vat will then be calculated on the total of the nett amounts.
- All quantities and rates as set forth and inserted in the schedule and extended to the totals for each
 portion of the schedule shall be considered as being totally inclusive for the whole of the works as
 stipulated or as can reasonably be inferred from these documents.
- All product guarantees are deemed to be included in the rates, and installation and application rates will consist of all necessary inspections and approvals to maintain guarantees.
- "Complete" as it is used in the schedule means the complete system or unit as specified in the particular documents. Each item in the schedule that is priced shall be filled in black ink.
- All quantities shall be considered as final and sufficient for the work described. The proposer shall satisfy himself as to the sufficiency of quantities but may not change quantities. Quantities shall be re-measured, and payment shall be made according to the adjusted total only

C.2.2 Bill of Quantities



RFQ NO: 0002718

INVITATION TO QUOTE ON

DESCRIPTION: RENOVATIONS TO QUEENSTOWN LABORATORY

COMPULSORY SITE MEETING: 06 FEBRUARY 2025 @ 09H30 TILL 10H00

ADDRESS. QUEENSTOWN HOSPITAL, MEET AT NHLS RECEPTION

CLOSING DATE. 14 FEBRUARY 2025 @ 11H00 ADDRESS; NHLS Lab , cnr Buckingham & Eastborne rd, mount croix, Port Elizabeth

FORM OF QUOTATION

SUPPLIER:

RFQ NO: 0002718

DESCRIPTION: RENOVATIONS TO QUEENSTOWN LABORATORY

	Description	Unit	Quantity	Rate	Cost excl vat
No	Virology:				
1	Remove existing benches, cupboards, sinks and basins and make good		Item		
2	Supply and install 30 ^{mm} x 30 ^{mm} steel square tubing frame, 800 ^{mm} wide and 880 ^{mm} high, on adjustable inserts, must be powder coated as per specification	m	9		
3	Supply and fit 15 ^{mm} x 900 ^{mm} wide, top shall be off approved Phenolic Resin. Top shall be impervious core that is chemical and heat resistant fixed to steel frames, height 895 ^{mm} high similar to Fundermax tops	m	9		
4	Supply and install 30 ^{mm} x 30 ^{mm} steel square tubing frame, 800 ^{mm} wide and 880 ^{mm} high, on adjustable inserts, must be powder coated as per specification. Centre bench	m	1.6		
5	Supply and fit 15 ^{mm} x 900 ^{mm} wide, top shall be off approved Phenolic Resin. Top shall be impervious core that is chemical and heat resistant fixed to steel frames, height 895 ^{mm} high similar to Fundermax tops. Centre bench	m	1.6		
6	Supply and fit steel wall powder coated cupboards with doors, 750 ^{mm} high x 900 ^{mm} wide x 330 ^{mm} deep with shelve as per specification	No	2		
7	Supply and deliver steel powder coated under bench cupboards	No	2		

			1	T	ı	
	800 ^{mm} high x 900 ^{mm} with doors and shelve on lockable castor wheels					
	as per specification					
8	Supply and fit porcelain hand wash basin with hospital elbow taps,	No	1			
	connect to hot and cold water supply and waste, fit splash back tiles above basin					
9	Supply and fit, steel, 2 Compartment type, allow for bends and end	m	14			
9	caps, power skirting from wire ways for power and data reticulation	111	14			
	and will be able to accommodate future expansion					
10	Supply and fit 15 amp standard power skirting plug points, wire	No	11			
	from distribution board to prevent overloading, allow for circuit	- 1.4				
	breakers					
11	Remove vinyl sheeting on wall, prepare and rhinolite to smooth	m^2	15			
	finish before painting commence					
12	Prepare and paint walls 2 coats Plascon Double Velvet as per	m^2	42			
	specification					
13	Remove existing vinyl sheeting and skirting, prepare floor to smooth	m^2	20			
	finish using self-levelling screed, supply and install 2 ^{mm} Eclipse PUR					
	or Classic Mystique PUR vinyl sheeting with welded joints, vinyl					
	must go up the wall 120 ^{mm} high include cove fillet and capping as per					
	specification					
	IT Office:					
1	Supply and install 12 000 BTU Midwall Split unit, heating and	No	1			
	cooling air conditioner, must be inverter type using R410A					
	refrigerant, install as per specification, air con type must be: LG,					
	Carrier, York, Samsung, or Daiken or similar					
2	Supply and install 30 amp single phase isolator at each air con wired	No	1			
	from distribution board including 1 x 20 amp single phase circuit					
	breakers, allow for cabling, trunking, bends and end caps					
	Store Room:					
1	Supply and fit Krost shelving in store room, 915 ^{mm} wide x 2000 ^{mm}	No	18			
	high x 350 ^{mm} deep, shelves must be 350 ^{mm} apart					
2	Supply and fit 5ft double LED tube light fitting complete with tubes	No	1			
	and clip on cover, wire from light next door					
	Waste Room:					
1	Remove existing vinyl sheeting and skirting, prepare floor to smooth	m^2	6			
	finish using self-levelling screed, supply and install 2 ^{mm} Eclipse PUR					
	or Classic Mystique PUR vinyl sheeting with welded joints, vinyl					
	must go up the wall 120 ^{mm} high include cove fillet and capping as per					
	specification					
	Tea Room:					
1	Remove existing cupboards, sink and taps and make good		Item			
2	Supply and fit 20 ^{mm} x 600 ^{mm} Rustenburg Granite top	m	3.4	1		
3	Supply and fit 750 ^{mm} wide wall cupboards including shelve, hinges	No	2	1		
	and chrome door handles, mahogany	= . =	_			
4	Supply and fit 900 ^{mm} wide floor standing cupboards including shelve,	No	2			
	hinges and chrome door handles on 100 ^{mm} x 50 ^{mm} chrome legs,					
L	mahogany			<u> </u>		
•	· · · · · · · · · · · · · · · · · · ·		•		•	

hinges and chrome door handles on 100mm x 50mm chrome legs, mahogany 6 Supply and install 401. 542mm x 319mm x 465mm cupboard for dustbin to match new cupboards including dustbin 7 Supply and fit double bowl stainless steel sink to granite top, 1600mm No 1 x 500mm wide, supply and fit 600mm x 200mm wall tiles above sink 8 Supply and fit Goose neck sink mixer tap, connect to hot and cold water supply, supply drainage for sink and connect on the stage of the supply supply drainage for sink and connect on the supply supply drainage for sink and connect on the supply supply drainage for sink and connect on the supply supply drainage for sink and connect on the supply supply and fit for sink and connect on the supply supply and fit of supply drainage for sink and connect on the supply supply and fit for supply supply supply supply and fit for supply sup	Ininges and chrome door handles on 100 mm x 50 mm chrome legs, mahogany Supply and install 40L 542 mm x 319 mm x 465 mm cupboard for dustbin to match new cupboards including dustbin Supply and fit double bowl stainless steel sink to granite top, 1600 mm x 500 mm wide, supply and fit double bowl stainless steel sink to granite top, 1600 mm x 500 mm wide, supply and fit footone neck sink mixer tap, connect to hot and cold No 1 x 500 mm wide, supply and fit footone x 200 mm wall tiles above sink Supply and fit fit Goose neck sink mixer tap, connect to hot and cold No 1 supply and fit microwave shelve, mahogany, 650 mm wide x 400 mm high x 400 mm high x 400 mm deep Supply and fit 15 amp Crabtree double surface mounted plugs wired from Distribution board, allow for cabling and 25 amp circuit breaker Supply and fit 30 amp isolator next to Hydroboil, wired from distribution board, including ducting, wiring and 25 amp single pole circuit breaker Supply and fit 5ft double LED tube light fitting complete with tubes and clip on cover Remove existing vinyl sheeting and skirting, prepare floor to smooth finish using self-levelling screed, supply and install 2 mm Eclipse PUR or Classic Mystique PUR vinyl sheeting with welded joints, vinyl must go up the wall 120 mm high include cove fillet and capping as per specification Remove all loose and peeling paint from walls, where necessary rhinolite walls to smooth finish, Prepare and paint walls, 2 coats, Plascon Double Velvet, as per specification Supply and fit new Yale Puch Button door lock No 1 Toilets: Remove existing toilets, basins, and make good Item Supply and fit porcelain hand bash basin on pedestal including hot and cold goose neck tap mixers, connect to existing hot and cold goose neck tap mixers, connect to existing hot and cold goose neck tap mixers, connect to existing hot and cold goose neck tap mixers, connect to existing hot and cold goose neck tap mixers, connect to existing hot and cold goose neck tap mixers, connect to existing hot and cold g	hinges and chrome door handles on 100 ^{min} x 50 ^{min} chrome legs, mahogany 6 Supply and install 40L 542 ^{min} x 319 ^{min} x 465 ^{min} cupboard for dustbin to match new cupboards including dustbin 7 Supply and fit double bowl stainless steel sink to granite top, 1600 ^{min} No 1 x 500 ^{min} wide, supply and fit 600 ^{min} x 200 ^{min} wall tiles above sink 8 Supply and fit Goose neck sink mixer tap, connect to hot and cold water supply, supply drainage for sink and connect 9 Supply and fit microwave shelve, mahogany, 650 ^{min} wide x 400 ^{min} high x 400 ^{min} deep 10 Supply and fit 15 amp Crabtree double surface mounted plugs wired from Distribution board, allow for cabling and 25 amp circuit breaker 11 Supply and fit 30 mp isolator next to Hydroboli, wired from distribution board, including ducting, wiring and 25 amp single pole circuit breaker 12 Supply and fit 5ft double LED tube light fitting complete with tubes and clip on cover 13 Remove existing vinyl sheeting and skirting, prepare floor to smooth finish using self-levelling screed, supply and install 2 ^{min} Eclipse PUR or Classic Mystique PUR vinyl sheeting with welded joints, vinyl must go up the wall 120 ^{min} bip include cove filled and capping as per specification 14 Remove all loose and peeling paint from walls, where necessary rhinolite walls to smooth finish, Prepare and paint walls, 2 coats, Plascon Double Velvet, as per specification 15 Remove all soos and peeling paint from ceiling, where necessary rhinolite ceiling to smooth finish, Prepare and paint ceiling, 2 coats, Plascon Double Velvet, as per specification 16 Supply and fit new Yale Puch Button door lock No 1 Remove existing toilets, basins, and make good 16 Remove all toose and peeling paint from ceiling, where necessary rhinolite ceiling to smooth finish, Prepare and paint ceiling, 2 coats, Plascon Double Velvet, as per specification Remove existing toilets, basins, and make good 10 Remove existing toilets, basins, and make good 11 Remove existing toilets, basins, and make good 12					T		
6 Supply and install 401.542*** x 319*** x 465**** upboard for dustbin to match new cupboards including dustbin 7 Supply and fit double bowl stainless steel sink to granite top, 1600*** No 1 x x 500*** wide, supply and fit 600*** x 200*** wall tiles above sink 8 Supply and fit floose neck sink mixer tap, connect to hot and cold water supply, supply drainage for sink and connect water supply, supply and fit incrowave shelve, mahogany, 650*** with the supply and fit 15 amp Crabtree double surface mounted plugs wired from Distribution board, allow for cabling and 25 amp circuit breaker from Distribution board, allow for cabling and 25 amp circuit breaker supply and fit 50 amp isolator next to Hydroboil, wired from distribution board, including ducting, wiring and 25 amp single pole circuit breaker supply and fit 51 double LED tube light fitting complete with tubes and clip on cover and clip on cover and clip on cover or classic Mystique PUR vinyl sheeting and skirting, prepare floor to smooth finish using self-levelling screed, supply and install 2*** Eclipse PUR or Classic Mystique PUR vinyl sheeting with welded joints, vinyl must go up the wall 120*** high include cove fillet and capping as per specification supply and supply and fit new valle to smooth finish, Prepare and paint walls, 2 coats, Plascon Double Velvet, as per specification 15 Remove all loose and peeling paint from walls, where necessary thinolite walls to smooth finish, Prepare and paint walls, 2 coats, Plascon Double Velvet, as per specification 16 Supply and fit new Yale Puch Button door lock No 1 Toilets: 1 Remove existing toilets, basins, and make good Item Toilets: 1 Remove existing toilets, basins, and make good Remove existing flooring, supply and fit 600** x 200** grade "A" Porcelain floor tiles including grouting Remove existing wall tiles, supply and fit 600** x 200** x 200** migrade	Supply and fit double bowl stainless steel sink to granite top, 1600mm kg, 200mm wide, supply and fit double bowl stainless steel sink to granite top, 1600mm kg, 200mm wide, supply and fit 6000mm x 200mm wall tiles above sink supply and fit 60ose neck sink mixer tap, connect to hot and cold water supply, supply drainage for sink and connect Supply and fit floose neck sink mixer tap, connect to hot and cold water supply, supply drainage for sink and connect Supply and fit microwave shelve, mahogany, 650mm wide x 400mm kg, x 400mm deep Supply and fit flooren granite double surface mounted plugs wired from Distribution board, allow for cabling and 25 amp circuit breaker Supply and fit 30 amp isolator next to Hydroboil, wired from distribution board, including ducting, wiring and 25 amp single pole circuit breaker Supply and fit 51 double LED tube light fitting complete with tubes and clip on cover Remove existing vinyl sheeting and skirting, prepare floor to smooth finish using self-levelling screed, supply and install 2mm Eclipse PUR or Classic Mystique PUR winyl sheeting with welded joints, vinyl must go up the wall 120mm high include cove fillet and capping as per specification Remove all loose and peeling paint from walls, where necessary rhinolite walls to smooth finish, Prepare and paint walls, 2 coats, Plascon Double Velvet, as per specification Remove all loose and peeling paint from ceiling, where necessary rhinolite ceiling to smooth finish, Prepare and paint ceiling, 2 coats, Plascon Double Velvet, as per specification Supply and fit new Yale Puch Button door lock Toilets: Remove existing toilets, basins, and make good Item Supply and fit porcelain hand bash basin on pedestal including hot and cold goose neck tap mixers, connect to existing hot and cold goose neck tap mixers, connect to existing hot and cold goose neck tap mixers, connect to existing hot and cold goose neck tap mixers, connect to existing hot and cold goose neck tap mixers, connect to existing hot and cold goose neck tap mixers,	mahogany to match new cupboards including distabilin Supply and fit double both stainless steed sink to grantie top, 1600** Supply and fit double both stainless steed sink to grantie top, 1600** Supply and fit double both stainless steed sink to grantie top, 1600** Supply and fit Googne fock sink mister 1pt, connect to hot and cold water supply, supply drainage for sink and connect Supply and fit fit of more sheet shew, mahogany, 650** Supply and fit fit of more sheet shew, mahogany, 650** Supply and fit fit of more sheet shew, mahogany, 650** Supply and fit 15 amp Crabtree double surface mounted plags wired from Distribution board, allow for cabiling and 25 amp circuit breaker from Distribution board, including ducting, wiring and 25 amp single pole circuit breaker from the sheet	5	Supply and fit 450 ^{mm} wide floor standing cupboards with drawers,	No	1			
Supply and install 40L 542** x 319** x 465*** cupboard for dustbin to match new cupboards including dustbin Supply and fit double bowl stainless steel sink to granite top, 1600*** x 300*** wide, supply and fit 600*** x 200*** wall tiles above sink Supply and fit Goose neck sink mixer tap, connect to hot and cold water supply, supply drainage for sink and connect Supply and fit foose neck sink mixer tap, connect to hot and cold water supply, supply drainage for sink and connect Supply and fit microwave shelve, mahogany, 650*** wide x 400**** and to limit microwave shelve, mahogany, 650*** wide x 400*** and to limit microwave shelve, mahogany, 650** wide x 400*** and to limit microwave shelve, mahogany, 650** wide x 400*** and to limit microwave shelve, mahogany, 650** wide x 400** and to limit microwave shelve, mahogany, 650** wide x 400** and 1 limit microwave shelve, mahogany, 650** wide x 400** and 1 limit microwave shelve, mahogany, 650** wide x 400** and 1 limit microwave shelve, mahogany, 650** wide x 400** and 1 limit microwave shelve, mahogany, 650** wide x 400**	Supply and install 40L 542mm x 31gmm x 465mm cupboard for dustbin to match new cupboards including dustbin Supply and fit double bowl stainless steel sink to granite top, 1600mm kg 500mm wide, supply and fit 600mm x 200mm wall tiles above sink Supply and fit Goose neck sink mixer tap, connect to hot and cold No 1 water supply, supply drainage for sink and connect Supply and fit fit from water supply, supply drainage for sink and connect Supply and fit fit from water supply and fit microwave shelve, mahogany, 650mm wide x 400mm high x 400mm deep Supply and fit 15 amp Crabtree double surface mounted plugs wired from Distribution board, allow for cabling and 25 amp circuit breaker Supply and fit 30 amp isolator next to Hydroboil, wired from distribution board, including ducting, writing and 25 amp single pole circuit breaker Supply and fit 51 double LED tube light fitting complete with tubes and clip on cover Remove existing vinyl sheeting and skirting, prepare floor to smooth finish using self-levelling screed, supply and install 2mm Eclipse PUR or Classic Mystique PUR vinyl sheeting with welded joints, vinyl must go up the wall 120mm high include cove fillet and capping as per specification Remove all loose and peeling paint from walls, where necessary thinolite walls to smooth finish, Prepare and paint walls, 2 coats, Plascon Double Velvet, as per specification Remove all loose and peeling paint from ceiling, where necessary m² 13 missing to smooth finish, Prepare and paint ceiling, 2 coats, Plascon Double Velvet, as per specification Remove all loose and peeling paint from ceiling, where necessary m² 13 missing to smooth finish prepare and paint ceiling, 2 coats, Plascon Double Velvet, as per specification Remove all fit new Yale Puch Button door lock No 1 Toilets: Remove existing toilets, basins, and make good Supply and fit porcelain hand bash basin on pedestal including hot and cold goose neck tap mixers, connect to existing hot and cold water and waste, fit shut off valves to each water outlet Suppl	5 Supply and install 40f. 542 m² x 119 m² x 465 m² cupharts including dustini to match new cuphoarts including dustini in 1600 m² x 200 m² wide, supply and fit 6000 m² x 200 m² wide, supply and fit 6000 m² x 200 m² wide, supply and fit 600 m² x 200 m² wide, supply and fit 600 m² x 200 m² wide, supply and fit fit 600 m² x 200 m² wide subsessink 8 Supply and fit fit fit 600 m² x 200 m² wide subsessink 8 Supply and fit fit 600 m² x 200 m² wide subsessink 8 Supply and fit fit 600 m² x 200 m² wide x 400 m² 1 9 Supply and fit 190 m² biath x 400 m² cupharts wide fit 600 m² x 200 m² x		-					
to match new cupboards including dustbin 7 Supply and fit double bowl stainless steel sink to granite top, 1600mm No 1 x 500mm wide, supply and fit 600mm x 200mm wall tiles above sink 8 Supply and fit Goose neck sink mixer tap, connect to hot and cold water supply, supply drainage for sink and connect 9 Supply and fit microwave shelve, mahogany, 650mm wide x 400mm No 1 high x 400mm deep	lo match new cupboards including dustbin Supply and fit double bowl stainless steel sink to granite top, 1600mm x 500mm wide, supply and fit 600mm x 200mm wall tiles above sink Supply and fit Goose neck sink mixer tap, connect to hot and cold water supply, supply drainage for sink and connect Supply and fit microwave shelve, mahogany, 650mm wide x 400mm No ligh x 400mm deep Supply and fit 15 amp Crabtree double surface mounted plugs wired from Distribution board, allow for cabling and 25 amp circuit breaker Supply and fit 30 amp isolator next to Hydroboil, wired from distribution board, including ducting, wiring and 25 amp single pole circuit breaker Supply and fit 5ft double LED tube light fitting complete with tubes and clip on cover Remove existing vinyl sheeting and skirting, prepare floor to smooth finish using self-levelling screed, supply and install 2mm Eclipse PUR or Classic Mystique PUR vinyl sheeting with welded joints, vinyl must go up the wall 120mm high include cove fillet and capping as per specification Remove all loose and peeling paint from walls, where necessary rhinolite walls to smooth finish, Prepare and paint walls, 2 coats, Plascon Double Velvet, as per specification Remove all loose and peeling paint from ceiling, where necessary rhinolite ceiling to smooth finish, Prepare and paint ceiling, 2 coats, Plascon Double Velvet as per specification Supply and fit new Yale Puch Button door lock No 1 Toilets: Remove existing toilets, basins, and make good Supply and fit porcelain hand bash basin on pedestal including hot and cold goose neck tap mixers, connect to existing hot and cold water and waste, fit shut off valves to each water outlet Supply and fit mirror above basin with aluminium frame, 533mm x No 1 Remove existing flooring, supply and fit 600mm x 600mm grade "A" Porcelain floor tiles including grouting	to match new cupboards including dustbin 7 Supply and fit double both stainless steel sink to grantie top, 1600° No 1 8 Supply and fit flooring with stainless steel sink to grantie top, 1600° No 1 8 Supply and fit Googe next soik mixer rap, connect to hot and cold water supply, supply drainage for sink and counsect 9 Supply and fit microwave shelve, mahogany, 650° wide x 400° No 1 10 Supply and fit information and allow for cabling and 25 amp givent breaker from Distribution board, allow for cabling and 25 amp givent breaker from Distribution board, including ducting, writing and 25 amp single pole circuit breaker distribution board, including ducting, writing and 25 amp single pole circuit breaker and distribution board, including ducting, writing and 25 amp single pole circuit breaker and fifty on cover and first fid double LED tube light fitting complete with tubes and clip on cover and first fid double LED tube light fitting complete with tubes and clip on cover and first fid double LED tube light fitting complete with tubes and clip on cover and first fid with the state of the control of the first fir							
Supply and fit double bowl stainless steel sink to granite top, 1600 No	Supply and fit double bowl stainless steel sink to granite top, 1600mm No	Supply and fit double bowl stainless seel sink to granite top, 1000mm No 1 x 500mm wide, supply and fit 600mm x 200mm water tap, connect to hot and cold No 1 water supply, supply drainage for sink and connect Supply and fit incrowave shelve, mahogany, 650mm wide x 4000mm chep No 1 water supply, supply drainage for sink and connect No 1 water supply supply and fit incrowave shelve, mahogany, 650mm wide x 4000mm chep No 1 water supply and fit 13 map Craburez double surface mounted plags wired No 3 supply and fit 13 map Craburez double surface mounted plags wired No 1 water supply and fit 15 map Craburez double surface mounted plags wired No 1 water supply and fit 15 map Craburez double surface mounted plags wired No 1 water supply and fit 15 double LED tube light fitting or mapter with tubes No 1 water supply and fit 15 double LED tube light fitting complete with tubes No 1 water supply and fit 15 double LeD tube light fitting complete with tubes No 1 water supply and fit 15 water supply and supply and six fitting, prepare floor to smooth finish using self-levelling sereed, supply and install 2 = Eclipse PUR or Classic Mystique PUR virily sheeting with welded joins, virily must go up the wall 120 = high include cover lifte and capping as per specification may be called the plant of the plant with the plant of the plant with the plant of the plant with well to smooth finish. Prepare and paint valid, 2 coats, Plascon Double Velvet, as per specification, where necessary m² 13 water supply and fit will be supply and fit parcelain band hash basin on pedestal including hot and cold goose neck tap mixers, connect to existing hot and cold water and water, if short for Valvets to each water outlet No 1	6	** *	No	1			
8 Supply and fit Goose neck sink mixer tap, connect to hot and cold water supply, supply drainage for sink and connect 9 Supply and fit microwave shelve, mahogany, 650mm wide x 400mm high x 400mm deep high x 400mm deep from Distribution board, allow for cabling and 25 amp circuit breaker 11 Supply and fit 15 amp Crabtree double surface mounted plugs wired from Distribution board, allow for cabling and 25 amp circuit breaker 11 Supply and fit 30 amp isolator next to Hydroboil, wired from distribution board, including ducting, wiring and 25 amp single pole circuit breaker 12 Supply and fit 5ft double LED tube light fitting complete with tubes and clip on cover 13 Remove existing vinyl sheeting and skirting, prepare floor to smooth finish using self-levelling screed, supply and install 2mm Eclipse PUR or Classic Mystique PUR vinyl sheeting with welded joints, vinyl must go up the wall 120mm high include cove fillet and capping as per specification 14 Remove all loose and peeling paint from walls, where necessary rhinolite walls to smooth finish, Prepare and paint walls, 2 coats, Plascon Double Velvet, as per specification 15 Remove all loose and peeling paint from ceiling, where necessary rhinolite eciling to smooth finish, Prepare and paint ceiling, 2 coats, Plascon Double Velvet, as per specification 16 Supply and fit new Yale Puch Button door lock 10 No 1 Remove existing toilets, basins, and make good Item 11 Remove existing toilets, basins, and make good Item 12 Supply and fit incror above basin with aluminium frame, 533mm x 533mm x 533mm 13 Supply and fit mirror above basin with aluminium frame, 533mm x 7 S33mm 14 Remove existing flooring, supply and fit 600mm x 600mm grade "A" more all location for the situating grouting growting Grade A more 32	S 500mm vide, supply and fit 600mm x 200mm vall tiles above sink	Supply and fit 6000 = 6x shir hirest rap. comest to bot and cold water supply, supply drainage for sink and comest. Supply and fit increases she he, make supply, \$1							
Supply and fit Goose neck sink mixer tap, connect to hot and cold water supply, supply drainage for sink and connect 9 Supply and fit intercowave shelve, mahogany, 650°mm wide x 400°mm No high x 400°mm deep 10 Supply and fit intercowave shelve, mahogany, 650°mm wide x 400°mm No high x 400°mm deep 11 Supply and fit 30 amp Crabtree double surface mounted plugs wired from Distribution board, allow for cabling and 25 amp circuit breaker 11 Supply and fit 30 amp isolator next to Hydroboil, wired from distribution board, including ducting, wiring and 25 amp single pole circuit breaker 12 Supply and fit 5ft double LED tube light fitting complete with tubes and clip on cover 13 Remove existing vinyl sheeting and skirting, prepare floor to smooth finish using self-levelling screed, supply and install 2°mm Eclipse PUR or Classic Mystique PUR vinyl sheeting with welded joints, vinyl must go up the wall 120°mm high include cove fillet and capping as per specification 14 Remove all loose and peeling paint from walls, where necessary rhinolite walls to smooth finish, Prepare and paint walls, 2 coats, Plascon Double Velvet, as per specification 15 Remove all loose and peeling paint from ceiling, where necessary rhinolite ceiling to smooth finish, Prepare and paint ceiling, 2 coats, Plascon Double Velvet, as per specification 16 Supply and fit new Yale Puch Button door lock No 1 Toilets: 1 Remove existing toilets, basins, and make good 2 Supply and fit procelain hand bash basin on pedestal including hot and cold goose neck tap mixers, connect to existing hot and cold water and waste, fit shut off valves to each water outlet 3 Supply and fit mirror above basin with aluminium frame, 533°mm x No 1 5 Supply and fit mirror above basin with aluminium frame, 533°mm x Porcelain floor tiles including grouting 5 Remove existing wall tiles, supply and fit 600°mm x 600°mm grade "A" Porcelain floor tiles including grouting	Supply and fit Goose neck sink mixer tap, connect to hot and cold water supply, supply drainage for sink and connect Supply and fit microwave shelve, mahogany, 650mm wide x 400mm high x 400mm deep Supply and fit 15 amp Crabtree double surface mounted plugs wired from Distribution board, allow for cabling and 25 amp circuit breaker Supply and fit 30 amp isolator next to Hydroboil, wired from distribution board, including ducting, wiring and 25 amp single pole circuit breaker Supply and fit 5ft double LED tube light fitting complete with tubes and clip on cover Supply and fit 5ft double LED tube light fitting complete with tubes and clip on cover Remove existing vinyl sheeting and skirting, prepare floor to smooth finish using self-levelling screed, supply and install 2mm Eclipse PUR or Classic Mystique PUR vinyl sheeting with welded joints, vinyl must go up the wall 120mm high include cove fillet and capping as per specification Remove all loose and peeling paint from walls, where necessary thinolite walls to smooth finish, Prepare and paint walls, 2 coats, Plascon Double Velvet, as per specification Remove all loose and peeling paint from ceiling, where necessary withinolite ceiling to smooth finish, Prepare and paint ceiling, 2 coats, Plascon Double Velvet, as per specification Supply and fit new Yale Puch Button door lock Toilets: Remove existing toilets, basins, and make good Supply and fit porcelain hand bash basin on pedestal including hot and cold goose neck tap mixers, connect to existing hot and cold water and waste, fit shut off valves to each water outlet Supply and fit miror above basin with aluminium frame, 533mm No 1 and 14 procelain floor tiles including grouting	Supply and fit Goose neck sink mixer tap, connect to hot and cold water supply, supply draininge for sink and connect Supply and fit incrowave shelve, mahogany, 650°°° wide x 400°°° high x A00°° deep 10 Supply and fit 1.5 amp Crabtere choulte surface mounted plags wired No 3 from Distribution board, allow for cabling and 2.5 amp circuit breaker 11 Supply and fit 1.5 amp Crabtere choulte surface mounted plags wired 12 Supply and fit 30 amp isolator nex to Hydrobol, wired from Ond distribution board, including ducting, wiring and 2.5 amp circuit breaker 12 Supply and fit 5f double LED table light fitting complete with tubes. 13 Remove existing vinyl sheeting and skirting, prepare floor to smooth finish using self-levelling screed, supply and install 2°° Echipse PUR or Classic Mystique PUR vinyl sheeting with welded joints, winyl must go up the wall 120°° migh is hicake core fillet and capping as per specification 14 Remove all loose and pecling paint from walls, where necessary rhinolite walls to smooth finish. Prepare and paint valls, 2 coats, Plascon Double Velvet, as per specification 15 Remove all loose and pecling paint from ceiling, where necessary rhinolite eciling to smooth finish. Prepare and paint ceiling, 2 coats, Plascon Double Velvet, as per specification 16 Supply and fit new Yale Puch Button door lock 10 No 1	7	Supply and fit double bowl stainless steel sink to granite top, 1600 ^{mm}	No	1			
water supply, supply drainage for sink and connect 9 Supply and fit microwave shelve, mahogany, 650mm wide x 400mm high x 400mm deep 10 Supply and fit 15 amp Crabtree double surface mounted plugs wired from Distribution board, allow for cabling and 25 amp circuit breaker 11 Supply and fit 30 amp isolator next to Hydroboil, wired from distribution board, including ducting, wiring and 25 amp single pole circuit breaker 12 Supply and fit 5ft double LED tube light fitting complete with tubes and clip on cover 13 Remove existing vinyl sheeting and skirting, prepare floor to smooth finish using self-levelling screed, supply and install 2mm Eclipse PUR or Classic Mystique PUR vinyl sheeting with welded joints, vinyl must go up the wall 120mm high include cove fillet and capping as per specification 14 Remove all loose and peeling paint from walls, where necessary rhinolite walls to smooth finish, Prepare and paint walls, 2 coats, Plascon Double Velvet, as per specification 15 Remove all loose and peeling paint from ceiling, where necessary rhinolite ceiling to smooth finish, Prepare and paint ceiling, 2 coats, Plascon Double Velvet, as per specification 16 Supply and fit new Yale Puch Button door lock No 1 Toilets: 1 Remove existing toilets, basins, and make good 5 Supply and fit porcelain hand bash basin on pedestal including hot and cold goose neck tap mixers, connect to existing hot and cold water and waste, fit shut off valves to each water outlet Supply and fit mirror above basin with aluminium frame, 533mm No 1 Remove existing flooring, supply and fit 600mm x 600mm grade "A" m² 14 Porcelain floor tiles including grouting 5 Remove existing wall tiles, supply and fit 600mm x 200mm Grade A m² 32	water supply, supply drainage for sink and connect Supply and fit microwave shelve, mahogany, 650mm wide x 400mm high x 400mm deep Supply and fit 15 amp Crabtree double surface mounted plugs wired from Distribution board, allow for cabling and 25 amp circuit breaker Supply and fit 30 amp isolator next to Hydroboil, wired from distribution board, including ducting, wiring and 25 amp single pole circuit breaker Supply and fit 5ft double LED tube light fitting complete with tubes and clip on cover Remove existing vinyl sheeting and skirting, prepare floor to smooth finish using self-levelling screed, supply and install 2mm Eclipse PUR or Classic Mystique PUR vinyl sheeting with welded joints, vinyl must go up the wall 120mm high include cove fillet and capping as per specification Remove all loose and peeling paint from walls, where necessary rhinolite walls to smooth finish, Prepare and paint walls, 2 coats, Plascon Double Velvet, as per specification Remove all loose and peeling paint from ceiling, where necessary rhinolite ceiling to smooth finish, Prepare and paint ceiling, 2 coats, Plascon Double Velvet, as per specification Supply and fit new Yale Puch Button door lock No 1 Toilets: Remove existing toilets, basins, and make good Item Supply and fit porcelain hand bash basin on pedestal including hot and cold goose neck tap mixers, connect to existing hot and cold water and waste, fit shut off valves to each water outlet Supply and fit mirror above basin with aluminium frame, 533mm x S33mm Remove existing flooring, supply and fit 600mm x 600mm grade "A" Porcelain floor tiles including grouting	water supply, supply drainage for sink and connect 9 Supply and fit microwave shelve, mahogany, 650 ^{mm} wide x 400 ^{mm} ligh x 400 ^{mm} deep 10 Supply and fit 30 amp toolstor next to Hydroboli, wired from 11 Supply and fit 30 amp toolstor next to Hydroboli, wired from 12 Supply and fit 30 amp toolstor next to Hydroboli, wired from 13 Supply and fit 30 amp toolstor next to Hydroboli, wired from 14 Supply and fit 30 amp toolstor next to Hydroboli, wired from 15 Supply and fit 35 double LED tube light fitting complete with tubes 16 Amplitude of the supply supply and fit and skirting, prepare floor to smooth 17 finish using self-levelling screed, supply and install 2 ^{mm} Echipse PUR 18 or Classic Mystique PUR kinyl sheeting with welded joints, vinyl 19 must go up the wall 120 ^{mm} high include cove fillet and capping as per 19 specification 10 Remove all loose and peeling paint from walls, where necessary 10 discretication should be supply and sing from ceiling, where necessary 19 dissolve walls to smooth finish, Prepare and paint walls, 2 coats, 19 Plascon Double Velvet, as per specification 10 Supply and fit new Yale Puch Button door lock 11 No 1 Toilets: 12 Supply and fit new Yale Puch Button door lock 13 Supply and fit porcelain hand bash basin on pedestal including hot and cold goose neck tup mixers, connect to existing hot and cold water and waste, fit short of Yalves to each water outlet 13 Supply and fit mirror above basin with aluminium frame, 533 ^{mm} x 14 Remove existing flooring, supply and fit 600 ^{mm} x 600 ^{mm} grade "A" 19 procelain floor tiles including grotting 2 Supply and fit mirror above basin with aluminium frame, 530 ^{mm} x 2 Nupply and fit mirror above basin with aluminium frame, 530 ^{mm} x 3 Supply and fit mirror above basin with aluminium frame, 530 ^{mm} x 3 Supply and fit mirror above basin with aluminium frame, 530 ^{mm} x 4 Remove existing folloring, supply and fit 600 ^{mm} x 600 ^{mm} grade "A" 2 Procelain floor tiles including grotting 3 Supply and fit mirror above basin with aluminium frame, 530 ^m							
Supply and fit microwave shelve, mahogany, 650 ^{mm} wide x 400 ^{mm} logh x 400 ^{mm} deep 10 Supply and fit 15 amp Crabtree double surface mounted plugs wired from Distribution board, allow for cabling and 25 amp circuit breaker 11 Supply and fit 15 amp Isolator next to Hydroboil, wired from distribution board, including ducting, wiring and 25 amp single pole circuit breaker 12 Supply and fit 5ft double LED tube light fitting complete with tubes and clip on cover 13 Remove existing vinyl sheeting and skirting, prepare floor to smooth finish using self-levelling screed, supply and install 2 ^{mm} Eclipse PUR or Classic Mystique PUR vinyl sheeting with welded joints, vinyl must go up the wall 120 ^{mm} high include cove fillet and capping as per specification 14 Remove all loose and peeling paint from walls, where necessary rhinolite walls to smooth finish, Prepare and paint walls, 2 coats, Plascon Double Velvet, as per specification 15 Remove all loose and peeling paint from ceiling, where necessary rhinolite ceiling to smooth finish, Prepare and paint ceiling, 2 coats, Plascon Double Velvet, as per specification 16 Supply and fit new Yale Puch Button door lock 1 Remove existing toilets, basins, and make good 2 Supply and fit porcelain hand bash basin on pedestal including hot and cold goose neck tap mixers, connect to existing hot and cold water and waste, fit shut off valves to each water outlet 3 Supply and fit mirror above basin with aluminium frame, 533 ^{mm} x 4 Remove existing flooring, supply and fit 600 ^{mm} x 600 ^{mm} grade "A" Porcelain floor tiles including grouting 5 Remove existing wall tiles, supply and fit 600 ^{mm} x 200 ^{mm} Grade A m² 32	Supply and fit microwave shelve, mahogany, 650mm wide x 400mm No 1 high x 400mm deep Supply and fit 15 amp Crabtree double surface mounted plugs wired from Distribution board, allow for cabling and 25 amp circuit breaker Supply and fit 30 amp isolator next to Hydroboil, wired from distribution board, including ducting, wiring and 25 amp single pole circuit breaker Supply and fit 30 amp isolator next to Hydroboil, wired from distribution board, including ducting, wiring and 25 amp single pole circuit breaker Supply and fit 5ft double LED tube light fitting complete with tubes and clip on cover Supply and fit 5ft double LED tube light fitting complete with tubes and clip on cover Remove existing vinyl sheeting and skirting, prepare floor to smooth finish using self-levelling screed, supply and install 2mm Eclipse PUR or Classic Mystique PUR vinyl sheeting with welded joints, vinyl must go up the wall 120mm high include cove fillet and capping as per specification Remove all loose and peeling paint from walls, where necessary rhinolite walls to smooth finish, Prepare and paint walls, 2 coats, Plascon Double Velvet, as per specification Remove all loose and peeling paint from ceiling, where necessary rhinolite ceiling to smooth finish, Prepare and paint ceiling, 2 coats, Plascon Double Velvet, as per specification Supply and fit new Yale Puch Button door lock No 1 Toilets: Remove existing toilets, basins, and make good Item Supply and fit porcelain hand bash basin on pedestal including hot and cold goose neck tap mixers, connect to existing hot and cold water and waste, fit shut off valves to each water outlet Supply and fit mirror above basin with aluminium frame, 533mm x No 1 Sagmome Remove existing flooring, supply and fit 600mm x 600mm grade "A" m² 14 Remove existing flooring, supply and fit 600mm x 600mm grade "A" m² 14	9 Supply and fit microwave shelve, umbogany, 650° wide x 400°° microwave shelve, umbogany, 650° wide x 600° microwave shelve, and 61° samp solutor next to Hydroboli, wired from distribution board, including ducting, wiring and 25 amp single pole circuit breaker 12 Supply and fit 30 amp isolator next to Hydroboli, wired from distribution board, including ducting, wiring and 25 amp single pole circuit breaker 13 Remove existing vinyl sheeting and skirting, prepare floor to smooth finish times geef levelling screed, supply and install 2°° Eclipse PUR or Classic Mystique PUR vinyl sheeting with welded joints, vinyl must go up the walt 120°° migh include cover filet and capping as per specification 14 Remove all loose and peeling paint from walls, where necessary rhinolite walls to smooth finish. Prepare and paint valls, 2 coats, Plascon Double Velvet, as per specification 15 Remove all loose and peeling paint from ceiling, where necessary rhinolite ceiling to smooth finish. Prepare and paint ceiling, 2 coats, Plascon Double Velvet, as per specification 16 Supply and fit new Yale Putch Button door look 10 Toilets: 1 Remove existing toilets, basins, and make good 2 Supply and fit procelain hand bash basin on pedestal including hot and cold goose next part mixers, connect to existing hot and cold water and waste, fit shut off valves to each water outlet 3 Supply and fit procelain hand bash basin on pedestal including hot and cold goose next part mixers, connect to existing hot and cold water and waste, fit shut off valves to each water outlet 3 Supply and fit inturn bout be sain with aluminium frame, 53°° mx X No 1 5 Supply and fit inturn bout be sain with aluminium frame, 53°° mx X No 1 5 Supply and fit is supply and fit 600°° m Color m Grade A Porcelain walt lies 2200° m light up to door height Porcelain floor riles includi	8		No	1			
high x 400mm deep 10 Supply and fit 15 amp Crabtree double surface mounted plugs wired from Distribution board, allow for cabling and 25 amp circuit breaker 11 Supply and fit 30 amp isolator next to Hydroboil, wired from distribution board, including ducting, wiring and 25 amp single pole circuit breaker 12 Supply and fit 5ft double LED tube light fitting complete with tubes and clip on cover and clip on c	high x 400mm deep Supply and fit 15 amp Crabtree double surface mounted plugs wired from Distribution board, allow for cabling and 25 amp circuit breaker Supply and fit 30 amp isolator next to Hydroboil, wired from distribution board, including ducting, wiring and 25 amp single pole circuit breaker Supply and fit 5ft double LED tube light fitting complete with tubes and clip on cover Remove existing vinyl sheeting and skirting, prepare floor to smooth finish using self-levelling screed, supply and install 2mm Eclipse PUR or Classic Mystique PUR vinyl sheeting with welded joints, vinyl must go up the wall 120mm high include cove fillet and capping as per specification Remove all loose and peeling paint from walls, where necessary thinolite walls to smooth finish, Prepare and paint walls, 2 coats, Plascon Double Velvet, as per specification Remove all loose and peeling paint from ceiling, where necessary thinolite ceiling to smooth finish, Prepare and paint ceiling, 2 coats, Plascon Double Velvet, as per specification Supply and fit new Yale Puch Button door lock No 1 Toilets: Remove existing toilets, basins, and make good Supply and fit porcelain hand bash basin on pedestal including hot and cold goose neck tap mixers, connect to existing hot and cold water and waste, fit shut off valves to each water outlet Supply and fit mirror above basin with aluminium frame, 533mm x No 1 Sa3mm Remove existing flooring, supply and fit 600mm x 600mm grade "A" m² 14 Porcelain floor tiles including grouting	high x 400 m deep							
Supply and fit 15 amp Crabtree double surface mounted plugs wired from Distribution board, allow for cabling and 25 amp circuit breaker Supply and fit 30 amp isolator next to Hydroboil, wired from distribution board, including ducting, wiring and 25 amp single pole circuit breaker Supply and fit 5ft double LED tube light fitting complete with tubes and clip on cover Supply and fit 5ft double LED tube light fitting complete with tubes and clip on cover Supply and fit 5ft double LED tube light fitting complete with tubes and clip on cover Supply and fit follows and clip on cover Supply and fit sit sit sit sit sit sit sit sit sit s	Supply and fit 15 amp Crabtree double surface mounted plugs wired from Distribution board, allow for cabling and 25 amp circuit breaker Supply and fit 30 amp isolator next to Hydroboil, wired from distribution board, including ducting, wiring and 25 amp single pole circuit breaker Supply and fit 5ft double LED tube light fitting complete with tubes and clip on cover Remove existing vinyl sheeting and skirting, prepare floor to smooth finish using self-levelling screed, supply and install 2mm Eclipse PUR or Classic Mystique PUR vinyl sheeting with welded joints, vinyl must go up the wall 120mm high include cove fillet and capping as per specification Remove all loose and peeling paint from walls, where necessary thinolite walls to smooth finish, Prepare and paint walls, 2 coats, Plascon Double Velvet, as per specification Remove all loose and peeling paint from ceiling, where necessary thinolite ceiling to smooth finish, Prepare and paint ceiling, 2 coats, Plascon Double Velvet, as per specification Supply and fit new Yale Puch Button door lock Toilets: Remove existing toilets, basins, and make good Supply and fit porcelain hand bash basin on pedestal including hot and cold goose neck tap mixers, connect to existing hot and cold water and waste, fit shut off valves to each water outlet Supply and fit mirror above basin with aluminium frame, 533mm x 533mm Remove existing flooring, supply and fit 600mm x 600mm grade "A" Remove existing flooring, supply and fit 600mm x 600mm grade "A" Remove existing flooring, supply and fit 600mm x 600mm grade "A" Remove existing flooring, supply and fit 600mm x 600mm grade "A" Remove existing flooring supply and fit 600mm x 600mm grade "A" Remove existing flooring supply and fit 600mm x 600mm grade "A"	Supply and fit 15 amp Crabtnee double surface mounted plugs wired from Distribution board, allow for cabling and 25 amp circuit breaker	9		No	1			
from Distribution board, allow for cabling and 25 amp circuit breaker 11 Supply and fit 30 amp isolator next to Hydroboil, wired from distribution board, including ducting, wiring and 25 amp single pole circuit breaker 12 Supply and fit 5ft double LED tube light fitting complete with tubes and clip on cover 13 Remove existing vinyl sheeting and skirting, prepare floor to smooth finish using self-levelling screed, supply and install 2nm Eclipse PUR or Classic Mystique PUR vinyl sheeting with welded joints, vinyl must go up the wall 120mm high include cove fillet and capping as per specification 14 Remove all loose and peeling paint from walls, where necessary rhinolite walls to smooth finish, Prepare and paint walls, 2 coats, Plascon Double Velvet, as per specification 15 Remove all loose and peeling paint from ceiling, where necessary rhinolite ceiling to smooth finish, Prepare and paint ceiling, 2 coats, Plascon Double Velvet, as per specification 16 Supply and fit new Yale Puch Button door lock No 1 Toilets: 1 Remove existing toilets, basins, and make good 2 Supply and fit porcelain hand bash basin on pedestal including hot and cold goose neck tap mixers, connect to existing bot and cold water and waste, fit shut off valves to each water outlet 3 Supply and fit mirror above basin with aluminium frame, 533mm x 533mm 4 Remove existing flooring, supply and fit 600mm x 600mm grade "A" Porcelain floor tiles including grouting 5 Remove existing wall tiles, supply and fit 600mm x 200mm Grade A m² 32	from Distribution board, allow for cabling and 25 amp circuit breaker Supply and fit 30 amp isolator next to Hydroboil, wired from distribution board, including ducting, wiring and 25 amp single pole circuit breaker Supply and fit 5ft double LED tube light fitting complete with tubes and clip on cover Remove existing vinyl sheeting and skirting, prepare floor to smooth finish using self-levelling screed, supply and install 2mm Eclipse PUR or Classic Mystique PUR vinyl sheeting with welded joints, vinyl must go up the wall 120mm high include cove fillet and capping as per specification Remove all loose and peeling paint from walls, where necessary thinolite walls to smooth finish, Prepare and paint walls, 2 coats, Plascon Double Velvet, as per specification Remove all loose and peeling paint from ceiling, where necessary thinolite ceiling to smooth finish, Prepare and paint ceiling, 2 coats, Plascon Double Velvet, as per specification Supply and fit new Yale Puch Button door lock Toilets: Remove existing toilets, basins, and make good Item Toilets: Remove existing toilets, basins, and make good Supply and fit porcelain hand bash basin on pedestal including hot and cold goose neck tap mixers, connect to existing hot and cold goose neck tap mixers, connect to existing hot and cold goose neck tap mixers, connect to existing hot and cold goose neck tap mixers, connect to existing hot and cold water and waste, fit shut off valves to each water outlet Supply and fit mirror above basin with aluminium frame, 533mm x 533mm x 533mm Remove existing flooring, supply and fit 600mm x 600mm grade "A" m² 14	From Distribution board, allow for cabling and 25 amp circuit breaker No 1		<u> </u>					
Supply and fit 30 amp isolator next to Hydroboil, wired from distribution board, including ducting, wiring and 25 amp single pole circuit breaker	Supply and fit 30 amp isolator next to Hydroboil, wired from distribution board, including ducting, wiring and 25 amp single pole circuit breaker Supply and fit 5ft double LED tube light fitting complete with tubes and clip on cover Remove existing vinyl sheeting and skirting, prepare floor to smooth finish using self-levelling screed, supply and install 2mm Eclipse PUR or Classic Mystique PUR vinyl sheeting with welded joints, vinyl must go up the wall 120mm high include cove fillet and capping as per specification Remove all loose and peeling paint from walls, where necessary rhinolite walls to smooth finish, Prepare and paint walls, 2 coats, Plascon Double Velvet, as per specification Remove all loose and peeling paint from ceiling, where necessary frinolite ceiling to smooth finish, Prepare and paint ceiling, 2 coats, Plascon Double Velvet, as per specification Supply and fit new Yale Puch Button door lock No 1 Toilets: Remove existing toilets, basins, and make good Item Supply and fit porcelain hand bash basin on pedestal including hot and cold goose neck tap mixers, connect to existing hot and cold goose neck tap mixers, connect to existing hot and cold goose neck tap mixers, connect to existing hot and cold goose neck tap mixers, connect to existing hot and cold goose neck tap mixers, connect to existing hot and cold water and waste, fit shut off valves to each water outlet Supply and fit mirror above basin with aluminium frame, 533mm x 533mm x 533mm x Family 14 Porcelain floor tiles including grouting	Supply and fit 30 amp isolator next to Hydroboil, wired from distribution board, including ducting, wiring and 25 amp single pole circuit breaker	10		No	3			
distribution board, including ducting, wiring and 25 amp single pole circuit breaker 12 Supply and fit 5ft double LED tube light fitting complete with tubes and clip on cover 13 Remove existing vinyl sheeting and skirting, prepare floor to smooth finish using self-levelling screed, supply and install 2mm Eclipse PUR or Classic Mystique PUR vinyl sheeting with welded joints, vinyl must go up the wall 120mm high include cove fillet and capping as per specification 14 Remove all loose and peeling paint from walls, where necessary rhinolite walls to smooth finish, Prepare and paint walls, 2 coats, Plascon Double Velvet, as per specification 15 Remove all loose and peeling paint from ceiling, where necessary rhinolite ceiling to smooth finish, Prepare and paint ceiling, 2 coats, Plascon Double Velvet, as per specification 16 Supply and fit new Yale Puch Button door lock Toilets: 1 Remove existing toilets, basins, and make good Toilets: 1 Remove existing toilets, basins, and make good Supply and fit procelain hand bash basin on pedestal including hot and cold goose neck tap mixers, connect to existing hot and cold water and waste, fit shut off valves to each water outlet 3 Supply and fit mirror above basin with aluminium frame, 533mm x 533mm 4 Remove existing flooring, supply and fit 600mm x 600mm grade "A" Porcelain floor tiles including grouting 5 Remove existing wall tiles, supply and fit 600mm x 200mm Grade A m² 3 Supply and lites, supply and fit 600mm x 200mm Grade A m² 3 Supply and fit floored and tiles, supply and fit 600mm x 200mm Grade A m² 3 Supply and fit floored and tiles, supply and fit 600mm x 200mm Grade A m² 3 Supply and fit floored and tiles, supply and fit 600mm x 200mm Grade A m² 3 Supply and fit floored and tiles, supply and fit 600mm x 200mm Grade A m² 3 Supply and fit floored and tiles, supply and fit 600mm x 200mm Grade A m² 4 Porcelain floor tiles including grouting	distribution board, including ducting, wiring and 25 amp single pole circuit breaker Supply and fit 5ft double LED tube light fitting complete with tubes and clip on cover Remove existing vinyl sheeting and skirting, prepare floor to smooth finish using self-levelling screed, supply and install 2 ^{mm} Eclipse PUR or Classic Mystique PUR vinyl sheeting with welded joints, vinyl must go up the wall 120 ^{mm} high include cove fillet and capping as per specification Remove all loose and peeling paint from walls, where necessary rhinolite walls to smooth finish, Prepare and paint walls, 2 coats, Plascon Double Velvet, as per specification Remove all loose and peeling paint from ceiling, where necessary rhinolite ceiling to smooth finish, Prepare and paint ceiling, 2 coats, Plascon Double Velvet, as per specification Supply and fit new Yale Puch Button door lock Toilets: Remove existing toilets, basins, and make good Item Supply and fit porcelain hand bash basin on pedestal including hot and cold goose neck tap mixers, connect to existing hot and cold water and waste, fit shut off valves to each water outlet Supply and fit mirror above basin with aluminium frame, 533 ^{mm} x Supply and fit mirror above basin with aluminium frame, 533 ^{mm} x No 1 Remove existing flooring, supply and fit 600 ^{mm} x 600 ^{mm} grade "A" Porcelain floor tiles including grouting	distribution board, including ducting, wiring and 25 amp single pole circuit breaker 12 Supply and fit 5ft double LED tube light fitting complete with tubes and clip on cover 13 Remove existing vinyl sheeting and skirting, prepare floor to smooth finish using self-levelling screed, supply and install 2 ^{mm} Eclipse PUR or Classic Mystique PUR vinyl sheeting with welded joints, vinyl must go up the wall 120 ^{mm} high include cove fillet and capping as per specification 14 Remove all loose and peeling paint from walls, where necessary thinolite walls to smooth finish, Prepare and paint walls, 2 coats, Plascon Double Velvet, as per specification 15 Remove all loose and peeling paint from ceiling, where necessary thinolite ceiling to smooth finish, Prepare and paint ceiling, 2 coats, Plascon Double Velvet, as per specification 16 Supply and fit new Yale Puch Button door lock No 1 Toilets: 1 Remove existing toilets, basins, and make good 1 Remove existing toilets, basins, and make good 2 Supply and fit proreclain hand bash busin on pedestal including hot and cold goose neck ten mixers, connect to existing hot and cold water and waste, fit shut off valves to each water outlet 3 Supply and fit miror above basin with aluminium frame, 533 ^{mm} x S33 ^{mm} S33 ^{mm} S33 ^{mm} S03 ^{mm} S13 ^m							
circuit breaker 12 Supply and fit 5ft double LED tube light fitting complete with tubes and clip on cover 13 Remove existing vinyl sheeting and skirting, prepare floor to smooth finish using self-levelling screed, supply and install 2mm Eclipse PUR or Classic Mystique PUR vinyl sheeting with welded joints, vinyl must go up the wall 120mm high include cove fillet and capping as per specification 14 Remove all loose and peeling paint from walls, where necessary rhinolite walls to smooth finish, Prepare and paint walls, 2 coats, Plascon Double Velvet, as per specification 15 Remove all loose and peeling paint from ceiling, where necessary rhinolite ceiling to smooth finish, Prepare and paint ceiling, 2 coats, Plascon Double Velvet, as per specification 16 Supply and fit new Yale Puch Button door lock Toilets: 1 Remove existing toilets, basins, and make good 2 Supply and fit porcelain hand bash basin on pedestal including hot and cold goose neck tap mixers, connect to existing hot and cold water and waste, fit shut off valves to each water outlet 3 Supply and fit mirror above basin with aluminium frame, 533mm x 533mm 4 Remove existing flooring, supply and fit 600mm x 600mm grade "A" m² 14 Porcelain floor tiles including grouting 5 Remove existing wall tiles, supply and fit 600mm x 200mm Grade A m² 32	circuit breaker Supply and fit 5ft double LED tube light fitting complete with tubes and clip on cover Remove existing vinyl sheeting and skirting, prepare floor to smooth finish using self-levelling screed, supply and install 2mm Eclipse PUR or Classic Mystique PUR vinyl sheeting with welded joints, vinyl must go up the wall 120mm high include cove fillet and capping as per specification Remove all loose and peeling paint from walls, where necessary rhinolite walls to smooth finish, Prepare and paint walls, 2 coats, Plascon Double Velvet, as per specification Remove all loose and peeling paint from ceiling, where necessary rhinolite ceiling to smooth finish, Prepare and paint ceiling, 2 coats, Plascon Double Velvet, as per specification Supply and fit new Yale Puch Button door lock No 1 Toilets: Remove existing toilets, basins, and make good Supply and fit porcelain hand bash basin on pedestal including hot and cold goose neck tap mixers, connect to existing hot and cold water and waste, fit shut off valves to each water outlet Supply and fit mirror above basin with aluminium frame, 533mm x 533mm Remove existing flooring, supply and fit 600mm x 600mm grade "A" Porcelain floor tiles including grouting	circuit breaker	11		No	1			
Supply and fit 5ft double LED tube light fitting complete with tubes and clip on cover	Supply and fit 5ft double LED tube light fitting complete with tubes and clip on cover Remove existing vinyl sheeting and skirting, prepare floor to smooth finish using self-levelling screed, supply and install 2 ^{mm} Eclipse PUR or Classic Mystique PUR vinyl sheeting with welded joints, vinyl must go up the wall 120 ^{mm} high include cove fillet and capping as per specification Remove all loose and peeling paint from walls, where necessary rhinolite walls to smooth finish, Prepare and paint walls, 2 coats, Plascon Double Velvet, as per specification Remove all loose and peeling paint from ceiling, where necessary rhinolite ceiling to smooth finish, Prepare and paint ceiling, 2 coats, Plascon Double Velvet, as per specification Supply and fit new Yale Puch Button door lock No 1 Toilets: Remove existing toilets, basins, and make good Supply and fit porcelain hand bash basin on pedestal including hot and cold goose neck tap mixers, connect to existing hot and cold water and waste, fit shut off valves to each water outlet Supply and fit mirror above basin with aluminium frame, 533 ^{mm} x Sayamm Remove existing flooring, supply and fit 600 ^{mm} x 600 ^{mm} grade "A" Porcelain floor tiles including grouting	Supply and fit 5ft double LED tube light fitting complete with tubes and clip on cover							
and clip on cover Remove existing vinyl sheeting and skirting, prepare floor to smooth finish using self-levelling screed, supply and install 2 ^{mm} Eclipse PUR or Classic Mystique PUR vinyl sheeting with welded joints, vinyl must go up the wall 120 ^{mm} high include cove fillet and capping as per specification 14 Remove all loose and peeling paint from walls, where necessary rhinolite walls to smooth finish, Prepare and paint walls, 2 coats, Plascon Double Velvet, as per specification 15 Remove all loose and peeling paint from ceiling, where necessary rhinolite ceiling to smooth finish, Prepare and paint ceiling, 2 coats, Plascon Double Velvet, as per specification 16 Supply and fit new Yale Puch Button door lock No 1 Toilets: 1 Remove existing toilets, basins, and make good Item 2 Supply and fit porcelain hand bash basin on pedestal including hot and cold goose neck tap mixers, connect to existing hot and cold water and waste, fit shut off valves to each water outlet 3 Supply and fit mirror above basin with aluminium frame, 533 ^{mm} x 533 ^{mm} 4 Remove existing flooring, supply and fit 600 ^{mm} x 600 ^{mm} grade "A" m² 14 Porcelain floor tiles including grouting 5 Remove existing wall tiles, supply and fit 600 ^{mm} x 200 ^{mm} Grade A m² 32	and clip on cover Remove existing vinyl sheeting and skirting, prepare floor to smooth finish using self-levelling screed, supply and install 2 ^{mm} Eclipse PUR or Classic Mystique PUR vinyl sheeting with welded joints, vinyl must go up the wall 120 ^{mm} high include cove fillet and capping as per specification Remove all loose and peeling paint from walls, where necessary rhinolite walls to smooth finish, Prepare and paint walls, 2 coats, Plascon Double Velvet, as per specification Remove all loose and peeling paint from ceiling, where necessary rhinolite ceiling to smooth finish, Prepare and paint ceiling, 2 coats, Plascon Double Velvet, as per specification Supply and fit new Yale Puch Button door lock Toilets: Remove existing toilets, basins, and make good Supply and fit porcelain hand bash basin on pedestal including hot and cold goose neck tap mixers, connect to existing hot and cold water and waste, fit shut off valves to each water outlet Supply and fit mirror above basin with aluminium frame, 533 ^{mm} x Sommon Supply and fit mirror above basin with aluminium frame, 533 ^{mm} x Porcelain floor tiles including grouting	and clip on cover Remove existing vinyl sheeting and skirting, prepare floor to smooth finish using self-levelling screed, supply and install 2mm Eclipse PUR or Classic Mystique PUR vinyl sheeting with welded joints, vinyl must go up the wall Izomm high include cove filter and capping as per specification 14 Remove all loose and peeling paint from walls, where necessary phinolite walls to smooth finish, Prepare and paint walls, 2 coats, Plascon Double Velvet, as per specification 15 Remove all loose and peeling paint from ceiling, where necessary phinolite ceiling to smooth finish, Prepare and paint ceiling, 2 coats, Plascon Double Velvet, as per specification 16 Supply and fit new Yale Puch Button door lock 17 Toilets: 1 Remove existing toilets, basins, and make good 2 Supply and fit prorelain hand bash basin on pedestal including hot and cold goose neck tap mixers, connect to existing hot and cold water and waste, fit shut off valves to each water outlet 3 Supply and fit mirror above basin with aluminium frame, 533mm x S33mm 4 Remove existing flooring, supply and fit 600mm x 600mm grade "A" m² 14 Porcelain floor tiles including grouting 5 Remove existing flooring, supply and fit 600mm x 600mm grade "A" m² 14 Porcelain floor tiles including grouting 6 Supply and fit aluminium male and female sign to the internal doors No 1 Supply and fit aluminium male and female sign to the internal doors No 1 Supply and fit sell lockable toilet sear, connect to existing water supply and drain 9 Supply and fit aluminium male and female sign to the internal doors No 2 cristen, enamel coated wooden toilet seat, connect to existing water supply and fit new vacantiengaged lockset to each door No 2 cristen, enamel coated wooden toilet seat, connect to existing water supply and fit new vacantiengaged lockset to each door No 2 perspecification 10 Supply and fit new hollow core wooden doors to each toilet 11 Supply and fit new bollow core wooden doors to each toilet 12 Prepare and paint door and door frames 2 coats Pla	10		NT	1			
Remove existing vinyl sheeting and skirting, prepare floor to smooth finish using self-levelling screed, supply and install 2 ^{mm} Eclipse PUR or Classic Mystique PUR vinyl sheeting with welded joints, vinyl must go up the wall 120 ^{mm} high include cove fillet and capping as per specification 14 Remove all loose and peeling paint from walls, where necessary rhinolite walls to smooth finish, Prepare and paint walls, 2 coats, Plascon Double Velvet, as per specification 15 Remove all loose and peeling paint from ceiling, where necessary rhinolite ceiling to smooth finish, Prepare and paint ceiling, 2 coats, Plascon Double Velvet, as per specification 16 Supply and fit new Yale Puch Button door lock Toilets: 1 Remove existing toilets, basins, and make good Supply and fit porcelain hand bash basin on pedestal including hot and cold goose neck tap mixers, connect to existing hot and cold water and waste, fit shut off valves to each water outlet 3 Supply and fit mirror above basin with aluminium frame, 533 ^{mm} x Supply and fit mirror above basin with aluminium frame, 533 ^{mm} x A Remove existing flooring, supply and fit 600 ^{mm} x 600 ^{mm} grade "A" Porcelain floor tiles including grouting 5 Remove existing wall tiles, supply and fit 600 ^{mm} x 200 ^{mm} Grade A m² 32	Remove existing vinyl sheeting and skirting, prepare floor to smooth finish using self-levelling screed, supply and install 2 ^{mm} Eclipse PUR or Classic Mystique PUR vinyl sheeting with welded joints, vinyl must go up the wall 120 ^{mm} high include cove fillet and capping as per specification Remove all loose and peeling paint from walls, where necessary rhinolite walls to smooth finish, Prepare and paint walls, 2 coats, Plascon Double Velvet, as per specification Remove all loose and peeling paint from ceiling, where necessary rhinolite ceiling to smooth finish, Prepare and paint ceiling, 2 coats, Plascon Double Velvet, as per specification Supply and fit new Yale Puch Button door lock Toilets: Remove existing toilets, basins, and make good Item Supply and fit porcelain hand bash basin on pedestal including hot and cold goose neck tap mixers, connect to existing hot and cold water and waste, fit shut off valves to each water outlet Supply and fit mirror above basin with aluminium frame, 533 ^{mm} x Supply and fit mirror above basin with aluminium frame, 533 ^{mm} x Remove existing flooring, supply and fit 600 ^{mm} x 600 ^{mm} grade "A" Porcelain floor tiles including grouting	Remove existing vinyl sheeting and skirting, prepare floor to smooth finish using self-levelling screed, supply and install 2 ^{mm} Eclipse PUR or Classic Mystique PUR vinyl sheeting with welded joints, vinyl must go up the wall 120 ^{mm} high include cove fillet and capping as per specification Remove all loose and peeling paint from walls, where necessary rhinolite walls to smooth finish, Prepare and paint walls, 2 coats, Plascon Double Velvet, as per specification Remove all loose and peeling paint from ceiling, where necessary rhinolite celling to smooth finish, Prepare and paint ceiling, 2 coats, Plascon Double Velvet, as per specification Remove all fore and paint from ceiling, where necessary rhinolite celling to smooth finish, Prepare and paint ceiling, 2 coats, Plascon Double Velvet, as per specification Remove existing toilets, basins, and make good Remove existing toilets, basins on pedestal including hot and cold goose neck tap mixers, connect to existing hot and cold water and waste, fit shut off valves to each water outlet Supply and fit mirror above basin with aluminium frame, 533 ^{mm} x Remove existing flooring, supply and fit 600 ^{mm} x 600 ^{mm} grade "A" Porcelain floor tiles including grouting Remove existing wall tiles, supply and fit 600 ^{mm} x 200 ^{mm} grade A Porcelain wall tiles 2200 ^{mm} high up to door height Supply and fit aluminium toilet sign on entrance door No Supply and fit aluminium male and female sign to the internal doors Remove existing toilets, supply and fit new Ceramic toilet including cistern, enamel coated wooden toilet seat, connect to existing water supply and fit new look of the part holder to accommodate 3 Supply and fit new vacant/engaged lookset to each door Supply and fit new look of the pare holder to accommodate 3 Prepare and paint door and door frames 2 coats Plasc	12		No	1			
finish using self-levelling screed, supply and install 2 ^{mm} Eclipse PUR or Classic Mystique PUR vinyl sheeting with welded joints, vinyl must go up the wall 120 ^{mm} high include cove fillet and capping as per specification 14 Remove all loose and peeling paint from walls, where necessary rhinolite walls to smooth finish, Prepare and paint walls, 2 coats, Plascon Double Velvet, as per specification 15 Remove all loose and peeling paint from ceiling, where necessary rhinolite ceiling to smooth finish, Prepare and paint ceiling, 2 coats, Plascon Double Velvet, as per specification 16 Supply and fit new Yale Puch Button door lock Toilets: 1 Remove existing toilets, basins, and make good Item 2 Supply and fit porcelain hand bash basin on pedestal including hot and cold goose neck tap mixers, connect to existing hot and cold water and waste, fit shut off valves to each water outlet 3 Supply and fit mirror above basin with aluminium frame, 533 ^{mm} x 533 ^{mm} 4 Remove existing flooring, supply and fit 600 ^{mm} x 600 ^{mm} grade "A" m ² 14 Porcelain floor tiles including grouting 5 Remove existing wall tiles, supply and fit 600 ^{mm} x 200 ^{mm} Grade A m ² 32	finish using self-levelling screed, supply and install 2 ^{mm} Eclipse PUR or Classic Mystique PUR vinyl sheeting with welded joints, vinyl must go up the wall 120 ^{mm} high include cove fillet and capping as per specification Remove all loose and peeling paint from walls, where necessary rhinolite walls to smooth finish, Prepare and paint walls, 2 coats, Plascon Double Velvet, as per specification Remove all loose and peeling paint from ceiling, where necessary rhinolite ceiling to smooth finish, Prepare and paint ceiling, 2 coats, Plascon Double Velvet, as per specification Supply and fit new Yale Puch Button door lock No Toilets: Remove existing toilets, basins, and make good Item Supply and fit porcelain hand bash basin on pedestal including hot and cold goose neck tap mixers, connect to existing hot and cold water and waste, fit shut off valves to each water outlet Supply and fit mirror above basin with aluminium frame, 533 ^{mm} x Supply and fit mirror above basin with aluminium frame, 533 ^{mm} x Remove existing flooring, supply and fit 600 ^{mm} x 600 ^{mm} grade "A" Porcelain floor tiles including grouting	finish using self-levelling screed, supply and install 2mm Eclipse PUR or Classic Mystique PUR vinyl sheeting with welded joints, vinyl must go up the wall 120mm high include cove filter and capping as per specification 14 Remove all loose and peeling paint from walls, where necessary thinolite walls to smooth finish, Prepare and paint walls, 2 coats, Plascon Double Velvet, as per specification 15 Remove all loose and peeling paint from ceiling, where necessary thinolite ceiling to smooth finish, Prepare and paint ceiling, 2 coats, Plascon Double Velvet, as per specification 16 Supply and fit new Yale Puch Button door lock 10 Supply and fit new Yale Puch Button door lock 11 Remove existing toilets, basins, and make good 12 Supply and fit prorelain hand bash basin on pedestal including hot and cold goose neck tap mixers, connect to existing hot and cold water and waste, fit shut off valves to each water outlet 13 Supply and fit mirror above basin with aluminium frame, 533mm x 533mm 24 Remove existing flooring, supply and fit 600mm x 600mm grade "A" porcelain floor tiles including grouting 25 Remove existing wall tiles, supply and fit 600mm x 200mm Grade A porcelain wall tiles, supply and fit more of the other hand to grade the processing wall tiles, supply and fit fit mere and cold water and waste, with the process of the supply and fit aluminium toilet sign on entrance door 26 Supply and fit aluminium toilet sign on entrance door 27 Supply and fit aluminium male and female sign to the internal doors 28 Remove existing toilets, supply and fit new Ceramic toilet including cistern, enamel coated wooden toilet seat, connect to existing water supply and fit new thollow core wooden doors to each toolet 29 Supply and fit new vacant/engaged lockset to each door 30 Supply and fit new vacant/engaged lockset to each door 31 Supply and fit new vacant/engaged lockset to each door 32 Prepare and paint door and door frames 2 coats Plascon Enamel as per specification above tiles up to ceiling Plascon Double Vel	12		2	1.5			
or Classic Mystique PUR vinyl sheeting with welded joints, vinyl must go up the wall 120 ^{mm} high include cove fillet and capping as per specification 14 Remove all loose and peeling paint from walls, where necessary rhinolite walls to smooth finish, Prepare and paint walls, 2 coats, Plascon Double Velvet, as per specification 15 Remove all loose and peeling paint from ceiling, where necessary rhinolite ceiling to smooth finish, Prepare and paint ceiling, 2 coats, Plascon Double Velvet, as per specification 16 Supply and fit new Yale Puch Button door lock 18 Toilets: 1 Remove existing toilets, basins, and make good 19 Toilets: 1 Remove existing toilets, basins, and make good 2 Supply and fit porcelain hand bash basin on pedestal including hot and cold goose neck tap mixers, connect to existing hot and cold water and waste, fit shut off valves to each water outlet 3 Supply and fit mirror above basin with aluminium frame, 533 ^{mm} x No 1 533 ^{mm} 4 Remove existing flooring, supply and fit 600 ^{mm} x 600 ^{mm} grade "A" m² 14 Porcelain floor tiles including grouting 5 Remove existing wall tiles, supply and fit 600 ^{mm} x 200 ^{mm} Grade A m² 32	or Classic Mystique PUR vinyl sheeting with welded joints, vinyl must go up the wall 120 ^{mm} high include cove fillet and capping as per specification Remove all loose and peeling paint from walls, where necessary rhinolite walls to smooth finish, Prepare and paint walls, 2 coats, Plascon Double Velvet, as per specification Remove all loose and peeling paint from ceiling, where necessary rhinolite ceiling to smooth finish, Prepare and paint ceiling, 2 coats, Plascon Double Velvet, as per specification Supply and fit new Yale Puch Button door lock No 1 Toilets: Remove existing toilets, basins, and make good Supply and fit porcelain hand bash basin on pedestal including hot and cold goose neck tap mixers, connect to existing hot and cold water and waste, fit shut off valves to each water outlet Supply and fit mirror above basin with aluminium frame, 533 ^{mm} x Supply and fit mirror above basin with aluminium frame, 533 ^{mm} x Remove existing flooring, supply and fit 600 ^{mm} x 600 ^{mm} grade "A" Porcelain floor tiles including grouting	or Classic Mystique PUR vinyl sheeting with welded joints, vinyl must go up the wall 120mm high include cove fillet and capping as per specification Remove all loose and peeling paint from walls, where necessary thinolite walls to smooth finish, Prepare and paint walls, 2 coats, Plascon Double Velvet, as per specification Remove all loose and peeling paint from ceiling, where necessary thinolite ceiling to smooth finish, Prepare and paint ceiling, 2 coats, Plascon Double Velvet, as per specification Remove all loose and peeling paint from ceiling, where necessary thinolite ceiling to smooth finish, Prepare and paint ceiling, 2 coats, Plascon Double Velvet, as per specification Toilets: Toilets: Remove existing toilets, basins, and make good Supply and fit porcelain hand bash basin on pedestal including hot and cold goose neck tap mixers, connect to existing hot and cold water and waste, fit shut off valves to each water outlet Supply and fit mirror above basin with aluminium frame, 533mm x Supply and fit mirror above basin with aluminium frame, 533mm x Remove existing flooring, supply and fit 600mm x 600mm grade "A" Porcelain floor tiles including grouting Remove existing wall tiles, supply and fit 600mm x 200mm Grade A Porcelain wall tiles 2200mm high up to door height Supply and fit aluminium toilet sign on entrance door No Remove existing toilets, supply and fit new Ceramic toilet including cistern, enamel coated wooden toilet seat, connect to existing water supply and fir aluminium male and female sign to the internal doors Remove existing toilets, supply and fit new Ceramic toilet including cistern, enamel coated wooden toilet seat, connect to existing water supply and fir aluminium toilet sign on entrance door No Supply and fir new Vacant/engaged lockset to each door No Prepare and paint door and door frames 2 coats Plascon Enamel as per specification Supply and fir new Vacant/engaged lockset to each door No Prepare and paint door and door frames 2 coats Plascon Enamel as per speci	13		III-	13			
must go up the wall 120mm high include cove fillet and capping as per specification 14 Remove all loose and peeling paint from walls, where necessary rhinolite walls to smooth finish, Prepare and paint walls, 2 coats, Plascon Double Velvet, as per specification 15 Remove all loose and peeling paint from ceiling, where necessary rhinolite ceiling to smooth finish, Prepare and paint ceiling, 2 coats, Plascon Double Velvet, as per specification 16 Supply and fit new Yale Puch Button door lock No 1 Toilets: 1 Remove existing toilets, basins, and make good 2 Supply and fit porcelain hand bash basin on pedestal including hot and cold goose neck tap mixers, connect to existing hot and cold water and waste, fit shut off valves to each water outlet 3 Supply and fit mirror above basin with aluminium frame, 533mm x 533mm 4 Remove existing flooring, supply and fit 600mm x 600mm grade "A" Porcelain floor tiles including grouting 5 Remove existing wall tiles, supply and fit 600mm x 200mm Grade A m² 32	must go up the wall 120 ^{mm} high include cove fillet and capping as per specification Remove all loose and peeling paint from walls, where necessary rhinolite walls to smooth finish, Prepare and paint walls, 2 coats, Plascon Double Velvet, as per specification Remove all loose and peeling paint from ceiling, where necessary rhinolite ceiling to smooth finish, Prepare and paint ceiling, 2 coats, Plascon Double Velvet, as per specification Supply and fit new Yale Puch Button door lock No 1 Toilets: Remove existing toilets, basins, and make good Supply and fit porcelain hand bash basin on pedestal including hot and cold goose neck tap mixers, connect to existing hot and cold water and waste, fit shut off valves to each water outlet Supply and fit mirror above basin with aluminium frame, 533 ^{mm} x Supply and fit mirror above basin with aluminium frame, 533 ^{mm} x Remove existing flooring, supply and fit 600 ^{mm} x 600 ^{mm} grade "A" Porcelain floor tiles including grouting	must go up the wall 120*** high include cove fillet and capping as per specification Remove all loose and peeling paint from walls, where necessary rhinolite walls to smooth finish, Prepare and paint walls, 2 coats, Plascon Double Velvet, as per specification Remove all loose and peeling paint from ceiling, where necessary finiolite ceiling to smooth finish, Prepare and paint ceiling, 2 coats, Plascon Double Velvet, as per specification Remove all loose and peeling paint from ceiling, where necessary finiolite ceiling to smooth finish, Prepare and paint ceiling, 2 coats, Plascon Double Velvet, as per specification Remove all loose and peeling paint from ceiling, where necessary finiolite veiling to smooth finish, Prepare and paint ceiling, 2 coats, Plascon Double Velvet, as per specification Toilets: Toilets: Remove existing toilets, basins, and make good Supply and fit procelain hand bash basin on pedestal including hot and cold goose neck tap mixers, connect to existing hot and cold water and waste, fit shut off valves to each water outlet Supply and fit fit procelain band bash basin on pedestal including hot and cold goose neck tap mixers, connect to existing hot and cold water and waste, fit shut off valves to each water outlet Supply and fit fit procelain band bash basin on pedestal including hot and cold goose neck tap mixers, connect to existing hot and cold water and waste, fit shut off valves to each water outlet Remove existing flooring, supply and fit 600***mx x 600***mm x 33***mm x							
specification 14 Remove all loose and peeling paint from walls, where necessary rhinolite walls to smooth finish, Prepare and paint walls, 2 coats, Plascon Double Velvet, as per specification 15 Remove all loose and peeling paint from ceiling, where necessary rhinolite ceiling to smooth finish, Prepare and paint ceiling, 2 coats, Plascon Double Velvet, as per specification 16 Supply and fit new Yale Puch Button door lock No 1 Toilets: 1 Remove existing toilets, basins, and make good Item 2 Supply and fit porcelain hand bash basin on pedestal including hot and cold goose neck tap mixers, connect to existing hot and cold water and waste, fit shut off valves to each water outlet 3 Supply and fit mirror above basin with aluminium frame, 533mm x 533mm 4 Remove existing flooring, supply and fit 600mm x 600mm grade "A" m² 14 Porcelain floor tiles including grouting 5 Remove existing wall tiles, supply and fit 600mm x 200mm Grade A m² 32	Remove all loose and peeling paint from walls, where necessary rhinolite walls to smooth finish, Prepare and paint walls, 2 coats, Plascon Double Velvet, as per specification Remove all loose and peeling paint from ceiling, where necessary rhinolite ceiling to smooth finish, Prepare and paint ceiling, 2 coats, Plascon Double Velvet, as per specification Supply and fit new Yale Puch Button door lock No 1 Toilets: Remove existing toilets, basins, and make good Supply and fit porcelain hand bash basin on pedestal including hot and cold goose neck tap mixers, connect to existing hot and cold water and waste, fit shut off valves to each water outlet Supply and fit mirror above basin with aluminium frame, 533mm x Supply and fit mirror above basin with aluminium frame, 533mm x Remove existing flooring, supply and fit 600mm x 600mm grade "A" Porcelain floor tiles including grouting	Remove all loose and peeling paint from walls, where necessary thinolite walls to smooth finish, Prepare and paint walls, 2 coats, Plascon Double Velvet, as per specification							
Remove all loose and peeling paint from walls, where necessary rhinolite walls to smooth finish, Prepare and paint walls, 2 coats, Plascon Double Velvet, as per specification 15 Remove all loose and peeling paint from ceiling, where necessary rhinolite ceiling to smooth finish, Prepare and paint ceiling, 2 coats, Plascon Double Velvet, as per specification 16 Supply and fit new Yale Puch Button door lock No 1	Remove all loose and peeling paint from walls, where necessary rhinolite walls to smooth finish, Prepare and paint walls, 2 coats, Plascon Double Velvet, as per specification Remove all loose and peeling paint from ceiling, where necessary rhinolite ceiling to smooth finish, Prepare and paint ceiling, 2 coats, Plascon Double Velvet, as per specification Supply and fit new Yale Puch Button door lock Toilets: Remove existing toilets, basins, and make good Supply and fit porcelain hand bash basin on pedestal including hot and cold goose neck tap mixers, connect to existing hot and cold water and waste, fit shut off valves to each water outlet Supply and fit mirror above basin with aluminium frame, 533 ^{mm} x Supply and fit mirror above basin with aluminium frame, 533 ^{mm} x Remove existing flooring, supply and fit 600 ^{mm} x 600 ^{mm} grade "A" Porcelain floor tiles including grouting	Remove all loose and peeling paint from walls, where necessary rhinolite walls to smooth finish, Prepare and paint walls, 2 coats, Plascon Double Velvet, as per specification							
rhinolite walls to smooth finish, Prepare and paint walls, 2 coats, Plascon Double Velvet, as per specification 15 Remove all loose and peeling paint from ceiling, where necessary rhinolite ceiling to smooth finish, Prepare and paint ceiling, 2 coats, Plascon Double Velvet, as per specification 16 Supply and fit new Yale Puch Button door lock No 1 Toilets: 1 Remove existing toilets, basins, and make good Supply and fit porcelain hand bash basin on pedestal including hot and cold goose neck tap mixers, connect to existing hot and cold water and waste, fit shut off valves to each water outlet 3 Supply and fit mirror above basin with aluminium frame, 533mm x 533mm 4 Remove existing flooring, supply and fit 600mm x 600mm grade "A" Porcelain floor tiles including grouting 5 Remove existing wall tiles, supply and fit 600mm x 200mm Grade A m² 32	rhinolite walls to smooth finish, Prepare and paint walls, 2 coats, Plascon Double Velvet, as per specification Remove all loose and peeling paint from ceiling, where necessary rhinolite ceiling to smooth finish, Prepare and paint ceiling, 2 coats, Plascon Double Velvet, as per specification Supply and fit new Yale Puch Button door lock No Toilets: Remove existing toilets, basins, and make good Supply and fit porcelain hand bash basin on pedestal including hot and cold goose neck tap mixers, connect to existing hot and cold water and waste, fit shut off valves to each water outlet Supply and fit mirror above basin with aluminium frame, 533mm x Supply and fit mirror above basin with aluminium frame, 533mm x Remove existing flooring, supply and fit 600mm x 600mm grade "A" Porcelain floor tiles including grouting	rhinolite walls to smooth finish, Prepare and paint walls, 2 coats, Plascon Double Velvet, as per specification 15 Remove all loose and peeling paint from ceiling, where necessary rhinolite ceiling to smooth finish, Prepare and paint ceiling, 2 coats, Plascon Double Velvet, as per specification 16 Supply and fit new Yale Puch Button door lock No 1 Toilets: 1 Remove existing toilets, basins, and make good 2 Supply and fit porcelain hand bash basin on pedestal including hot and cold goose neck tap mixers, connect to existing hot and cold water and waste, fit shut off valves to each water outlet 3 Supply and fit mirror above basin with aluminium frame, 533***m* 4 Remove existing flooring, supply and fit 600***m* x 600***m*	14		m ²	40			
Plascon Double Velvet, as per specification Remove all loose and peeling paint from ceiling, where necessary rhinolite ceiling to smooth finish, Prepare and paint ceiling, 2 coats, Plascon Double Velvet, as per specification Supply and fit new Yale Puch Button door lock No Toilets: Remove existing toilets, basins, and make good Supply and fit porcelain hand bash basin on pedestal including hot and cold goose neck tap mixers, connect to existing hot and cold water and waste, fit shut off valves to each water outlet Supply and fit mirror above basin with aluminium frame, 533mm x No Remove existing flooring, supply and fit 600mm x 600mm grade "A" Porcelain floor tiles including grouting Remove existing wall tiles, supply and fit 600mm x 200mm Grade A m² 32	Plascon Double Velvet, as per specification Remove all loose and peeling paint from ceiling, where necessary rhinolite ceiling to smooth finish, Prepare and paint ceiling, 2 coats, Plascon Double Velvet, as per specification Supply and fit new Yale Puch Button door lock No 1 Toilets: Remove existing toilets, basins, and make good Supply and fit porcelain hand bash basin on pedestal including hot and cold goose neck tap mixers, connect to existing hot and cold water and waste, fit shut off valves to each water outlet Supply and fit mirror above basin with aluminium frame, 533mm x Supply and fit mirror above basin with aluminium frame, 533mm x Remove existing flooring, supply and fit 600mm x 600mm grade "A" Porcelain floor tiles including grouting	Plascon Double Velvet, as per specification Remove all loose and peeling paint from ceiling, where necessary thinolite ceiling to smooth finish, Prepare and paint ceiling, 2 coats, Plascon Double Velvet, as per specification Supply and fit new Yale Puch Button door lock No 1 Toilets: Remove existing toilets, basins, and make good Remove existing toilets, basins, and make good Supply and fit porcelain hand bash basin on pedestal including hot and cold goose neck tap mixers, connect to existing hot and cold water and waste, fit shut off valves to each water outlet Remove existing flooring, supply and fit folonems x 600mm grade "A" Porcelain floor tiles including grouting Remove existing flooring, supply and fit 600mm x 600mm grade "A" Porcelain floor tiles including grouting Remove existing wall tiles 2200mm high up to door height Supply and fit aluminium male and female sign to the internal doors Remove existing toilets, supply and fit new Ceramic toilet including cistern, enamel coated wooden toilet seat, connect to existing water supply and drain Supply and fit new vacant/engaged lockset to each door Supply and fit new vacant/engaged lockset to each door Supply and fit new vacant/engaged lockset to each door Supply and fit new vacant/engaged lockset to each door Supply and fit new vacant/engaged lockset to each door Supply and fit fit ouble LED tube light fitting complete with tubes and clip on cover Remove all loose and peeling paint from walls, where necessary rhinolite walls to smooth finish, Prepare and paint walls, 2 coats, Plascon Double Velvet, as per specification above tiles up to ceiling. Remove all loose and peeling paint from ceiling, where necessary rhinolite walls to smooth finish, Prepare and paint walls, 2 coats, Plascon Double Velvet, as per specification above tiles up to ceiling	14		111	40			
Remove all loose and peeling paint from ceiling, where necessary rhinolite ceiling to smooth finish, Prepare and paint ceiling, 2 coats, Plascon Double Velvet, as per specification	Remove all loose and peeling paint from ceiling, where necessary rhinolite ceiling to smooth finish, Prepare and paint ceiling, 2 coats, Plascon Double Velvet, as per specification Supply and fit new Yale Puch Button door lock No I Toilets: Remove existing toilets, basins, and make good Supply and fit porcelain hand bash basin on pedestal including hot and cold goose neck tap mixers, connect to existing hot and cold water and waste, fit shut off valves to each water outlet Supply and fit mirror above basin with aluminium frame, 533 mm x 533 mm Remove existing flooring, supply and fit 600 mm x 600 mm grade "A" Porcelain floor tiles including grouting	Remove all loose and peeling paint from ceiling, where necessary rhinolite ceiling to smooth finish, Prepare and paint ceiling, 2 coats, Plascon Double Velvet, as per specification 16 Supply and fit new Yale Puch Button door lock No 1 Toilets: 1 Remove existing toilets, basins, and make good 2 Supply and fit porcelain hand bash basin on pedestal including hot and cold goose neck tap mixers, connect to existing hot and cold water and waste, fit shut off valves to each water outlet 3 Supply and fit mirror above basin with aluminium frame, 533mm x S33mm 4 Remove existing flooring, supply and fit 600mm x 600mm grade "A" porcelain floor tiles including grouting 5 Remove existing wall tiles, supply and fit 600mm x 200mm Grade A porcelain wall tiles 2200mm high up to door height 6 Supply and fit aluminium toilet sign on entrance door 7 Supply and fit aluminium male and female sign to the internal doors No 1 8 Remove existing toilets, supply and fit new Ceramic toilet including cistern, enamel coated wooden toilet seat, connect to existing water supply and fit steel lockable toilet paper holder to accommodate 3 no 2 controls at a time 10 Supply and fit new vacant/engaged lockset to each door No 2 11 Supply and fit new vacant/engaged lockset to each door No 2 12 Prepare and paint door and door frames 2 coats Plascon Enamel as per specification paint walls, 2 coats, Plascon Double Velvet, as per specification above tiles up to ceiling made in the paint was and clip on cover whole loose and peeling paint from walls, where necessary thinolite walls to smooth finish, Prepare and paint walls, 2 coats, Plascon Double Velvet, as per specification above tiles up to ceiling made in the part of the							
rhinolite ceiling to smooth finish, Prepare and paint ceiling, 2 coats, Plascon Double Velvet, as per specification 16 Supply and fit new Yale Puch Button door lock No 1 Toilets: 1 Remove existing toilets, basins, and make good 2 Supply and fit porcelain hand bash basin on pedestal including hot and cold goose neck tap mixers, connect to existing hot and cold water and waste, fit shut off valves to each water outlet 3 Supply and fit mirror above basin with aluminium frame, 533mm x 5 Remove existing flooring, supply and fit 600mm x 600mm grade "A" Porcelain floor tiles including grouting 5 Remove existing wall tiles, supply and fit 600mm x 200mm Grade A m² 32	rhinolite ceiling to smooth finish, Prepare and paint ceiling, 2 coats, Plascon Double Velvet, as per specification Supply and fit new Yale Puch Button door lock No Toilets: Remove existing toilets, basins, and make good Supply and fit porcelain hand bash basin on pedestal including hot and cold goose neck tap mixers, connect to existing hot and cold water and waste, fit shut off valves to each water outlet Supply and fit mirror above basin with aluminium frame, 533 mm x Supply and fit mirror above basin with aluminium frame, 533 mm x Remove existing flooring, supply and fit 600 mm x 600 mm grade "A" Porcelain floor tiles including grouting	rhinolite ceiling to smooth finish, Prepare and paint ceiling, 2 coats, Plascon Double Velvet, as per specification Supply and fit new Yale Puch Button door lock No Toilets: Remove existing toilets, basins, and make good Supply and fit porcelain hand bash basin on pedestal including hot and cold goose neck tap mixers, connect to existing hot and cold water and waste, fit shut off valves to each water outlet Supply and fit mirror above basin with aluminium frame, 533mm x Supply and fit mirror above basin with aluminium frame, 533mm x Remove existing flooring, supply and fit 600mm x 600mm grade "A" Porcelain floor tiles including grouting Remove existing wall tiles, supply and fit 600mm x 200mm Grade A Porcelain wall tiles 2200mm high up to door height Supply and fit aluminium toilet sign on entrance door Supply and fit aluminium ale and female sign to the internal doors Remove existing toilets, supply and fit new Ceramic toilet including cistern, enamel coated wooden toilet seat, connect to existing water supply and drain Supply and fit seel lockable toilet paper holder to accommodate 3 rolls at a time Supply and fit new vacant/engaged lockset to each door Supply and fit new vacant/engaged lockset to each door Supply and fit new vacant/engaged lockset to each door Supply and fit new vacant/engaged lockset to each door Supply and fit new hollow core wooden doors to each toilet Prepare and paint door and door frames 2 coats Plascon Enamel as per specification Supply and fit fit double LED tube light fitting complete with tubes and clip on cover Remove all loose and peeling paint from walls, where necessary rhinolite walls to smooth finish, Prepare and paint walls, 2 coats, Plascon Double Velvet, as per specification above tiles up to ceiling Remove all loose and peeling paint from ceiling, where necessary rhinolite walls to smooth finish, Prepare and paint walls, 2 coats, Plascon Double Velvet, as per specification above tiles up to ceiling	15		m ²	13			
Plascon Double Velvet, as per specification 16 Supply and fit new Yale Puch Button door lock No 1 Toilets: 1 Remove existing toilets, basins, and make good 2 Supply and fit porcelain hand bash basin on pedestal including hot and cold goose neck tap mixers, connect to existing hot and cold water and waste, fit shut off valves to each water outlet 3 Supply and fit mirror above basin with aluminium frame, 533mm x 5 Supply and fit mirror above basin with aluminium frame, 533mm x 4 Remove existing flooring, supply and fit 600mm x 600mm grade "A" Porcelain floor tiles including grouting 5 Remove existing wall tiles, supply and fit 600mm x 200mm Grade A m² 32	Plascon Double Velvet, as per specification Supply and fit new Yale Puch Button door lock No Toilets: Remove existing toilets, basins, and make good Supply and fit porcelain hand bash basin on pedestal including hot and cold goose neck tap mixers, connect to existing hot and cold water and waste, fit shut off valves to each water outlet Supply and fit mirror above basin with aluminium frame, 533mm x Supply and fit mirror above basin with aluminium frame, 533mm x Remove existing flooring, supply and fit 600mm x 600mm grade "A" Porcelain floor tiles including grouting	Plascon Double Velvet, as per specification Supply and fit new Yale Puch Button door lock No Toilets: Remove existing toilets, basins, and make good Supply and fit porcelain hand bash basin on pedestal including hot and cold goose neck tap mixers, connect to existing hot and cold water and waste, fit shut off valves to each water outlet Supply and fit mirror above basin with aluminium frame, 533mm x Supply and fit mirror above basin with aluminium frame, 533mm x Porcelain floor tiles including grouting Remove existing flooring, supply and fit 600mm x 600mm grade "A" Porcelain floor tiles including grouting Remove existing walt tiles, supply and fit 600mm x 200mm Grade A Porcelain wall tiles 2200mm high up to door height Supply and fit aluminium toilet sign on entrance door Supply and fit aluminium male and female sign to the internal doors Remove existing toilets, supply and fit new Ceramic toilet including cistern, enamel coated wooden toilet seat, connect to existing water supply and fit steel lockable toilet paper holder to accommodate 3 rolls at a time Supply and fit steel lockable toilet paper holder to accommodate 3 rolls at a time Supply and fit new vacant/engaged lockset to each door Supply and fit new vacant/engaged lockset to each door Supply and fit new vacant/engaged lockset to each door Supply and fit new vacant/engaged lockset to each door Supply and fit new vacant/engaged lockset to each door Supply and fit new vacant/engaged lockset to each door Prepare and paint door and door frames 2 coats Plascon Enamel as per specification Supply and fit fit double LED tube light fitting complete with tubes and clip on cover Remove all loose and peeling paint from walls, where necessary thinolite walls to smooth finish, Prepare and paint walls, 2 coats, Plascon Double Velvet, as per specification above tiles up to ceiling	13		111	13			
Toilets: Remove existing toilets, basins, and make good Supply and fit porcelain hand bash basin on pedestal including hot and cold goose neck tap mixers, connect to existing hot and cold water and waste, fit shut off valves to each water outlet Supply and fit mirror above basin with aluminium frame, 533 ^{mm} x Supply and fit mirror above basin with aluminium frame, 533 ^{mm} x No Remove existing flooring, supply and fit 600 ^{mm} x 600 ^{mm} grade "A" Porcelain floor tiles including grouting Remove existing wall tiles, supply and fit 600 ^{mm} x 200 ^{mm} Grade A m² 32	Supply and fit new Yale Puch Button door lock Toilets: Remove existing toilets, basins, and make good Supply and fit porcelain hand bash basin on pedestal including hot and cold goose neck tap mixers, connect to existing hot and cold water and waste, fit shut off valves to each water outlet Supply and fit mirror above basin with aluminium frame, 533mm x Supply and fit mirror above basin with aluminium frame, 533mm x Remove existing flooring, supply and fit 600mm x 600mm grade "A" Porcelain floor tiles including grouting	Toilets: Toilets: Remove existing toilets, basins, and make good Supply and fit procelain hand bash basin on pedestal including hot and cold goose neck tap mixers, connect to existing hot and cold goose neck tap mixers, connect to existing hot and cold water and waste, fit shut off valves to each water outlet Supply and fit mirror above basin with aluminium frame, 533mm x 533mm Remove existing flooring, supply and fit 600mm x 600mm grade "A" m² 14 Porcelain floor tiles including grouting Remove existing wall tiles, supply and fit 600mm x 200mm Grade A porcelain wall tiles 2200mm high up to door height Supply and fit aluminium toilet sign on entrance door Supply and fit aluminium male and female sign to the internal doors Remove existing toilets, supply and fit new Ceramic toilet including cistern, enamel coated wooden toilet seat, connect to existing water supply and fit steel lockable toilet paper holder to accommodate 3 rolls at a time Supply and fit new vacant/engaged lockset to each door Supply and fit new vacant/engaged lockset to each door Supply and fit new vacant/engaged lockset to each door Supply and fit new vacant/engaged lockset to each door Supply and fit new vacant/engaged lockset to each door Supply and fit fit fit double LED tube light fitting complete with tubes and clip on cover Remove all loose and peeling paint from walls, where necessary thinolite walls to smooth finish, Prepare and paint walls, 2 coats, Plascon Double Velvet, as per specification above tiles up to ceiling late.							
Toilets: Remove existing toilets, basins, and make good Supply and fit porcelain hand bash basin on pedestal including hot and cold goose neck tap mixers, connect to existing hot and cold water and waste, fit shut off valves to each water outlet Supply and fit mirror above basin with aluminium frame, 533mm x Supply and fit mirror above basin with aluminium frame, 533mm x Remove existing flooring, supply and fit 600mm x 600mm grade "A" Porcelain floor tiles including grouting Remove existing wall tiles, supply and fit 600mm x 200mm Grade A m² 32	Toilets: Remove existing toilets, basins, and make good Supply and fit porcelain hand bash basin on pedestal including hot and cold goose neck tap mixers, connect to existing hot and cold water and waste, fit shut off valves to each water outlet Supply and fit mirror above basin with aluminium frame, 533 ^{mm} x No Remove existing flooring, supply and fit 600 ^{mm} x 600 ^{mm} grade "A" Porcelain floor tiles including grouting	Toilets: 1 Remove existing toilets, basins, and make good 2 Supply and fit porcelain hand bash basin on pedestal including hot and cold goose neck tap mixers, connect to existing hot and cold water and waste, fit shut off valves to each water outlet 3 Supply and fit mirror above basin with aluminium frame, 533mm x 533mm 4 Remove existing flooring, supply and fit 600mm x 600mm grade "A" Porcelain floor tiles including grouting 5 Remove existing wall tiles, supply and fit 600mm x 200mm Grade A Porcelain wall tiles 2200mm high up to door height 6 Supply and fit aluminium toilet sign on entrance door No 1 7 Supply and fit aluminium male and female sign to the internal doors 8 Remove existing toilets, supply and fit new Ceramic toilet including cistern, enamel coated wooden toilet seat, connect to existing water supply and frat steel lockable toilet paper holder to accommodate 3 9 Supply and fit steel lockable toilet paper holder to accommodate 3 rolls at a time 10 Supply and fit new vacant/engaged lockset to each door No 2 11 Supply and fit new hollow core wooden doors to each toilet No 2 Prepare and paint door and door frames 2 coats Plascon Enamel as per specification 13 Supply and fit 5ft double LED tube light fitting complete with tubes and clip on cover 14 Remove all loose and peeling paint from walls, where necessary rhinolite walls to smooth finish, Prepare and paint walls, 2 coats, Plascon Double Velvet, as per specification above tiles up to ceiling 15 Remove all loose and peeling paint from ceiling, where necessary m² 14	16		No	1			
1 Remove existing toilets, basins, and make good 2 Supply and fit porcelain hand bash basin on pedestal including hot and cold goose neck tap mixers, connect to existing hot and cold water and waste, fit shut off valves to each water outlet 3 Supply and fit mirror above basin with aluminium frame, 533 ^{mm} x No 1 S33 ^{mm} 4 Remove existing flooring, supply and fit 600 ^{mm} x 600 ^{mm} grade "A" Porcelain floor tiles including grouting 5 Remove existing wall tiles, supply and fit 600 ^{mm} x 200 ^{mm} Grade A m² 32	Remove existing toilets, basins, and make good Supply and fit porcelain hand bash basin on pedestal including hot and cold goose neck tap mixers, connect to existing hot and cold water and waste, fit shut off valves to each water outlet Supply and fit mirror above basin with aluminium frame, 533 ^{mm} x Supply and fit mirror above basin with aluminium frame, 533 ^{mm} x Remove existing flooring, supply and fit 600 ^{mm} x 600 ^{mm} grade "A" Porcelain floor tiles including grouting	Remove existing toilets, basins, and make good				_			
1 Remove existing toilets, basins, and make good 2 Supply and fit porcelain hand bash basin on pedestal including hot and cold goose neck tap mixers, connect to existing hot and cold water and waste, fit shut off valves to each water outlet 3 Supply and fit mirror above basin with aluminium frame, 533 ^{mm} x No 1 S33 ^{mm} 4 Remove existing flooring, supply and fit 600 ^{mm} x 600 ^{mm} grade "A" Porcelain floor tiles including grouting 5 Remove existing wall tiles, supply and fit 600 ^{mm} x 200 ^{mm} Grade A m² 32	Remove existing toilets, basins, and make good Supply and fit porcelain hand bash basin on pedestal including hot and cold goose neck tap mixers, connect to existing hot and cold water and waste, fit shut off valves to each water outlet Supply and fit mirror above basin with aluminium frame, 533 ^{mm} x Supply and fit mirror above basin with aluminium frame, 533 ^{mm} x Remove existing flooring, supply and fit 600 ^{mm} x 600 ^{mm} grade "A" Porcelain floor tiles including grouting	Remove existing toilets, basins, and make good							
1 Remove existing toilets, basins, and make good 2 Supply and fit porcelain hand bash basin on pedestal including hot and cold goose neck tap mixers, connect to existing hot and cold water and waste, fit shut off valves to each water outlet 3 Supply and fit mirror above basin with aluminium frame, 533 ^{mm} x No 1 S33 ^{mm} 4 Remove existing flooring, supply and fit 600 ^{mm} x 600 ^{mm} grade "A" Porcelain floor tiles including grouting 5 Remove existing wall tiles, supply and fit 600 ^{mm} x 200 ^{mm} Grade A m² 32	Remove existing toilets, basins, and make good Supply and fit porcelain hand bash basin on pedestal including hot and cold goose neck tap mixers, connect to existing hot and cold water and waste, fit shut off valves to each water outlet Supply and fit mirror above basin with aluminium frame, 533 ^{mm} x Supply and fit mirror above basin with aluminium frame, 533 ^{mm} x Remove existing flooring, supply and fit 600 ^{mm} x 600 ^{mm} grade "A" Porcelain floor tiles including grouting	Remove existing toilets, basins, and make good		Toilete			+		
Supply and fit porcelain hand bash basin on pedestal including hot and cold goose neck tap mixers, connect to existing hot and cold water and waste, fit shut off valves to each water outlet Supply and fit mirror above basin with aluminium frame, 533 ^{mm} x No Remove existing flooring, supply and fit 600 ^{mm} x 600 ^{mm} grade "A" Porcelain floor tiles including grouting Remove existing wall tiles, supply and fit 600 ^{mm} x 200 ^{mm} Grade A m ² 32	Supply and fit porcelain hand bash basin on pedestal including hot and cold goose neck tap mixers, connect to existing hot and cold water and waste, fit shut off valves to each water outlet Supply and fit mirror above basin with aluminium frame, 533 ^{mm} x No Remove existing flooring, supply and fit 600 ^{mm} x 600 ^{mm} grade "A" Porcelain floor tiles including grouting	Supply and fit porcelain hand bash basin on pedestal including hot and cold goose neck tap mixers, connect to existing hot and cold water and waste, fit shut off valves to each water outlet 3 Supply and fit mirror above basin with aluminium frame, 533mm x 533mm x 533mm 2 14 Remove existing flooring, supply and fit 600mm x 600mm grade "A" m² 14 Porcelain floor tiles including grouting 5 Remove existing wall tiles, supply and fit 600mm x 200mm Grade A Porcelain wall tiles 2200mm high up to door height 6 Supply and fit aluminium toilet sign on entrance door No 1 7 Supply and fit aluminium male and female sign to the internal doors No 1 8 Remove existing toilets, supply and fit new Ceramic toilet including cistern, enamel coated wooden toilet seat, connect to existing water supply and drain 9 Supply and fit steel lockable toilet paper holder to accommodate 3 No 2 rolls at a time 10 Supply and fit new vacant/engaged lockset to each door No 2 11 Supply and fit new hollow core wooden doors to each toilet No 2 12 Prepare and paint door and door frames 2 coats Plascon Enamel as per specification 13 Supply and fit 5ft double LED tube light fitting complete with tubes and clip on cover 14 Remove all loose and peeling paint from walls, where necessary m² 25 15 Remove all loose and peeling paint from walls, where necessary m² 14	1			Itam			
and cold goose neck tap mixers, connect to existing hot and cold water and waste, fit shut off valves to each water outlet 3 Supply and fit mirror above basin with aluminium frame, 533 ^{mm} x No 1 4 Remove existing flooring, supply and fit 600 ^{mm} x 600 ^{mm} grade "A" Porcelain floor tiles including grouting 5 Remove existing wall tiles, supply and fit 600 ^{mm} x 200 ^{mm} Grade A m² 32	and cold goose neck tap mixers, connect to existing hot and cold water and waste, fit shut off valves to each water outlet Supply and fit mirror above basin with aluminium frame, 533 ^{mm} x No 1 Say No 1 Remove existing flooring, supply and fit 600 ^{mm} x 600 ^{mm} grade "A" Porcelain floor tiles including grouting	and cold goose neck tap mixers, connect to existing hot and cold water and waste, fit shut off valves to each water outlet 3 Supply and fit mirror above basin with aluminium frame, 533 ^{mm} x 533 ^{mm} x 533 ^{mm} 4 Remove existing flooring, supply and fit 600 ^{mm} x 600 ^{mm} grade "A" Porcelain floor tiles including grouting 5 Remove existing wall tiles, supply and fit 600 ^{mm} x 200 ^{mm} Grade A Porcelain wall tiles 2200 ^{mm} high up to door height 6 Supply and fit aluminium toilet sign on entrance door No 1 Supply and fit aluminium male and female sign to the internal doors 8 Remove existing toilets, supply and fit new Ceramic toilet including cistern, enamel coated wooden toilet seat, connect to existing water supply and fit steel lockable toilet paper holder to accommodate 3 No 2 supply and fit seel lockable toilet paper holder to accommodate 3 No 10 Supply and fit new vacant/engaged lockset to each door No 2 toils at a time 10 Supply and fit new hollow core wooden doors to each toilet No 2 prepare and paint door and door frames 2 coats Plascon Enamel as per specification 13 Supply and fit 5ft double LED tube light fitting complete with tubes and clip on cover 14 Remove all loose and peeling paint from walls, where necessary rhinoilte walls to smooth finish, Prepare and paint walls, 2 coats, Plascon Double Velvet, as per specification above tiles up to ceiling 15 Remove all loose and peeling paint from ceiling, where necessary m ² 14			27	-			
water and waste, fit shut off valves to each water outlet 3 Supply and fit mirror above basin with aluminium frame, 533 ^{mm} x 533 ^{mm} 4 Remove existing flooring, supply and fit 600 ^{mm} x 600 ^{mm} grade "A" Porcelain floor tiles including grouting 5 Remove existing wall tiles, supply and fit 600 ^{mm} x 200 ^{mm} Grade A m ² 32	water and waste, fit shut off valves to each water outlet Supply and fit mirror above basin with aluminium frame, 533 ^{mm} x No 1 533 ^{mm} Remove existing flooring, supply and fit 600 ^{mm} x 600 ^{mm} grade "A" Porcelain floor tiles including grouting	water and waste, fit shut off valves to each water outlet 3	2		No	1			
Supply and fit mirror above basin with aluminium frame, 533 ^{mm} x No 1 533 ^{mm} 4 Remove existing flooring, supply and fit 600 ^{mm} x 600 ^{mm} grade "A" Porcelain floor tiles including grouting 5 Remove existing wall tiles, supply and fit 600 ^{mm} x 200 ^{mm} Grade A m ² 32	Supply and fit mirror above basin with aluminium frame, 533 ^{mm} x No 1 533 ^{mm} Remove existing flooring, supply and fit 600 ^{mm} x 600 ^{mm} grade "A" Porcelain floor tiles including grouting	Supply and fit mirror above basin with aluminium frame, 533 ^{mm} x No Remove existing flooring, supply and fit 600 ^{mm} x 600 ^{mm} grade "A" Porcelain floor tiles including grouting Remove existing wall tiles, supply and fit 600 ^{mm} x 200 ^{mm} Grade A Porcelain wall tiles 2200 ^{mm} high up to door height Supply and fit aluminium toilet sign on entrance door Supply and fit aluminium male and female sign to the internal doors Remove existing toilets, supply and fit new Ceramic toilet including cistern, enamel coated wooden toilet seat, connect to existing water supply and fris tele lockable toilet paper holder to accommodate 3 rolls at a time Supply and fit new vacant/engaged lockset to each door Supply and fit new vacant/engaged lockset to each door Prepare and paint door and door frames 2 coats Plascon Enamel as per specification Supply and fit 5ft double LED tube light fitting complete with tubes and clip on cover Remove all loose and peeling paint from walls, where necessary rhinolite walls to smooth finish, Prepare and paint walls, 2 coats, Plascon Double Velvet, as per specification above tiles up to ceiling Remove all loose and peeling paint from ceiling, where necessary m² 14							
533 ^{mm} 4 Remove existing flooring, supply and fit 600 ^{mm} x 600 ^{mm} grade "A" m ² 14 Porcelain floor tiles including grouting 5 Remove existing wall tiles, supply and fit 600 ^{mm} x 200 ^{mm} Grade A m ² 32	533 ^{mm} Remove existing flooring, supply and fit 600 ^{mm} x 600 ^{mm} grade "A" m ² 14 Porcelain floor tiles including grouting	533 ^{mm} 4 Remove existing flooring, supply and fit 600 ^{mm} x 600 ^{mm} grade "A" m² 14 Porcelain floor tiles including grouting 5 Remove existing wall tiles, supply and fit 600 ^{mm} x 200 ^{mm} Grade A Porcelain wall tiles 2200 ^{mm} high up to door height 6 Supply and fit aluminium toilet sign on entrance door No 1 7 Supply and fit aluminium male and female sign to the internal doors No 1 8 Remove existing toilets, supply and fit new Ceramic toilet including cistern, enamel coated wooden toilet seat, connect to existing water supply and drain 9 Supply and fit steel lockable toilet paper holder to accommodate 3 rolls at a time 10 Supply and fit new vacant/engaged lockset to each door No 2 11 Supply and fit new hollow core wooden doors to each toilet No 2 12 Prepare and paint door and door frames 2 coats Plascon Enamel as per specification 13 Supply and fit 5ft double LED tube light fitting complete with tubes and clip on cover 14 Remove all loose and peeling paint from walls, where necessary rhinolite walls to smooth finish, Prepare and paint walls, 2 coats, Plascon Double Velvet, as per specification above tiles up to ceiling 15 Remove all loose and peeling paint from ceiling, where necessary m² 14	2		No	1			
4 Remove existing flooring, supply and fit 600 ^{mm} x 600 ^{mm} grade "A" m ² 14 Porcelain floor tiles including grouting 5 Remove existing wall tiles, supply and fit 600 ^{mm} x 200 ^{mm} Grade A m ² 32	Remove existing flooring, supply and fit 600 ^{mm} x 600 ^{mm} grade "A" m ² 14 Porcelain floor tiles including grouting	Remove existing flooring, supply and fit 600 ^{mm} x 600 ^{mm} grade "A" Porcelain floor tiles including grouting Remove existing wall tiles, supply and fit 600 ^{mm} x 200 ^{mm} Grade A Porcelain wall tiles 2200 ^{mm} high up to door height Supply and fit aluminium toilet sign on entrance door Supply and fit aluminium male and female sign to the internal doors Remove existing toilets, supply and fit new Ceramic toilet including cistern, enamel coated wooden toilet seat, connect to existing water supply and drain Supply and fit steel lockable toilet paper holder to accommodate 3 No 2 rolls at a time Supply and fit new vacant/engaged lockset to each door Supply and fit new vacant/engaged lockset to each door Supply and fit new hollow core wooden doors to each toilet Prepare and paint door and door frames 2 coats Plascon Enamel as per specification Supply and fit 5ft double LED tube light fitting complete with tubes and clip on cover Remove all loose and peeling paint from walls, where necessary rhinolite walls to smooth finish, Prepare and paint walls, 2 coats, Plascon Double Velvet, as per specification above tiles up to ceiling Remove all loose and peeling paint from ceiling, where necessary m ² Remove all loose and peeling paint from ceiling, where necessary m ² Remove all loose and peeling paint from ceiling, where necessary m ²	3		NO	1			
Porcelain floor tiles including grouting 5 Remove existing wall tiles, supply and fit 600 ^{mm} x 200 ^{mm} Grade A m ² 32	Porcelain floor tiles including grouting	Porcelain floor tiles including grouting Remove existing wall tiles, supply and fit 600 ^{mm} x 200 ^{mm} Grade A Porcelain wall tiles 2200 ^{mm} high up to door height Supply and fit aluminium toilet sign on entrance door Supply and fit aluminium male and female sign to the internal doors Remove existing toilets, supply and fit new Ceramic toilet including cistern, enamel coated wooden toilet seat, connect to existing water supply and drain Supply and fit steel lockable toilet paper holder to accommodate 3 rolls at a time Supply and fit new vacant/engaged lockset to each door Supply and fit new vacant/engaged lockset to each door Supply and fit new hollow core wooden doors to each toilet Prepare and paint door and door frames 2 coats Plascon Enamel as per specification Supply and fit 5ft double LED tube light fitting complete with tubes and clip on cover Remove all loose and peeling paint from walls, where necessary rhinolite walls to smooth finish, Prepare and paint walls, 2 coats, Plascon Double Velvet, as per specification above tiles up to ceiling Remove all loose and peeling paint from ceiling, where necessary m² 14	1		2	1.4			
5 Remove existing wall tiles, supply and fit 600 ^{mm} x 200 ^{mm} Grade A m ² 32		Remove existing wall tiles, supply and fit 600 ^{mm} x 200 ^{mm} Grade A Porcelain wall tiles 2200 ^{mm} high up to door height	4		111	14			
	Permana existing well tiles supply and fit 600mm v 200mm Grade A m ² 22	Porcelain wall tiles 2200 ^{mm} high up to door height Supply and fit aluminium toilet sign on entrance door No 1 Supply and fit aluminium male and female sign to the internal doors Remove existing toilets, supply and fit new Ceramic toilet including cistern, enamel coated wooden toilet seat, connect to existing water supply and drain Supply and fit steel lockable toilet paper holder to accommodate 3 No 2 rolls at a time Supply and fit new vacant/engaged lockset to each door No 2 Supply and fit new hollow core wooden doors to each toilet No 2 Prepare and paint door and door frames 2 coats Plascon Enamel as per specification Supply and fit 5ft double LED tube light fitting complete with tubes and clip on cover hinolite walls to smooth finish, Prepare and paint walls, 2 coats, Plascon Double Velvet, as per specification above tiles up to ceiling Remove all loose and peeling paint from ceiling, where necessary m ² 14 Remove all loose and peeling paint from ceiling, where necessary m ² 14	5		m ²	22			
		6 Supply and fit aluminium toilet sign on entrance door 7 Supply and fit aluminium male and female sign to the internal doors 8 Remove existing toilets, supply and fit new Ceramic toilet including cistern, enamel coated wooden toilet seat, connect to existing water supply and drain 9 Supply and fit steel lockable toilet paper holder to accommodate 3 rolls at a time 10 Supply and fit new vacant/engaged lockset to each door 11 Supply and fit new hollow core wooden doors to each toilet 12 Prepare and paint door and door frames 2 coats Plascon Enamel as per specification 13 Supply and fit 5ft double LED tube light fitting complete with tubes and clip on cover 14 Remove all loose and peeling paint from walls, where necessary rhinolite walls to smooth finish, Prepare and paint walls, 2 coats, Plascon Double Velvet, as per specification above tiles up to ceiling 15 Remove all loose and peeling paint from ceiling, where necessary m ² 14	3		111	32			
	1 decian wan thes 2200 mgn up to door neight	7 Supply and fit aluminium male and female sign to the internal doors No 1 8 Remove existing toilets, supply and fit new Ceramic toilet including cistern, enamel coated wooden toilet seat, connect to existing water supply and drain No 2 9 Supply and fit steel lockable toilet paper holder to accommodate 3 rolls at a time No 2 10 Supply and fit new vacant/engaged lockset to each door No 2 11 Supply and fit new hollow core wooden doors to each toilet No 2 12 Prepare and paint door and door frames 2 coats Plascon Enamel as per specification No 2 13 Supply and fit 5ft double LED tube light fitting complete with tubes and clip on cover No 1 14 Remove all loose and peeling paint from walls, where necessary rhinolite walls to smooth finish, Prepare and paint walls, 2 coats, Plascon Double Velvet, as per specification above tiles up to ceiling m² 25 15 Remove all loose and peeling paint from ceiling, where necessary m² 14	6		No	1			
		Remove existing toilets, supply and fit new Ceramic toilet including cistern, enamel coated wooden toilet seat, connect to existing water supply and drain Supply and fit steel lockable toilet paper holder to accommodate 3 No 2 rolls at a time Supply and fit new vacant/engaged lockset to each door No 2 Supply and fit new hollow core wooden doors to each toilet No 2 Prepare and paint door and door frames 2 coats Plascon Enamel as per specification Supply and fit 5ft double LED tube light fitting complete with tubes and clip on cover Remove all loose and peeling paint from walls, where necessary rhinolite walls to smooth finish, Prepare and paint walls, 2 coats, Plascon Double Velvet, as per specification above tiles up to ceiling Remove all loose and peeling paint from ceiling, where necessary m ² 14							
	Supply and fit aluminium toilet sign on entrance door No 1	cistern, enamel coated wooden toilet seat, connect to existing water supply and drain 9 Supply and fit steel lockable toilet paper holder to accommodate 3 No 2 rolls at a time 10 Supply and fit new vacant/engaged lockset to each door No 2 11 Supply and fit new hollow core wooden doors to each toilet No 2 12 Prepare and paint door and door frames 2 coats Plascon Enamel as per specification 13 Supply and fit 5ft double LED tube light fitting complete with tubes and clip on cover 14 Remove all loose and peeling paint from walls, where necessary rhinolite walls to smooth finish, Prepare and paint walls, 2 coats, Plascon Double Velvet, as per specification above tiles up to ceiling 15 Remove all loose and peeling paint from ceiling, where necessary m² 14		:					
	Supply and fit aluminium toilet sign on entrance door No 1 Supply and fit aluminium male and female sign to the internal doors No 1	supply and drain Supply and fit steel lockable toilet paper holder to accommodate 3 No 2 rolls at a time Supply and fit new vacant/engaged lockset to each door No 2 Supply and fit new hollow core wooden doors to each toilet No 2 Prepare and paint door and door frames 2 coats Plascon Enamel as per specification Supply and fit 5ft double LED tube light fitting complete with tubes and clip on cover Remove all loose and peeling paint from walls, where necessary rhinolite walls to smooth finish, Prepare and paint walls, 2 coats, Plascon Double Velvet, as per specification above tiles up to ceiling Remove all loose and peeling paint from ceiling, where necessary m² 14		kemove existing toilets, supply and fit new Ceramic toilet including	No	2			
	Supply and fit aluminium toilet sign on entrance door No 1 Supply and fit aluminium male and female sign to the internal doors No 1 Remove existing toilets, supply and fit new Ceramic toilet including No 2	Supply and fit steel lockable toilet paper holder to accommodate 3 rolls at a time 10 Supply and fit new vacant/engaged lockset to each door No 2 11 Supply and fit new hollow core wooden doors to each toilet No 2 12 Prepare and paint door and door frames 2 coats Plascon Enamel as per specification 13 Supply and fit 5ft double LED tube light fitting complete with tubes and clip on cover 14 Remove all loose and peeling paint from walls, where necessary rhinolite walls to smooth finish, Prepare and paint walls, 2 coats, Plascon Double Velvet, as per specification above tiles up to ceiling 15 Remove all loose and peeling paint from ceiling, where necessary m² 14	8						
	Supply and fit aluminium toilet sign on entrance door Supply and fit aluminium male and female sign to the internal doors No Remove existing toilets, supply and fit new Ceramic toilet including cistern, enamel coated wooden toilet seat, connect to existing water	rolls at a time 10 Supply and fit new vacant/engaged lockset to each door 11 Supply and fit new hollow core wooden doors to each toilet 12 Prepare and paint door and door frames 2 coats Plascon Enamel as per specification 13 Supply and fit 5ft double LED tube light fitting complete with tubes and clip on cover 14 Remove all loose and peeling paint from walls, where necessary rhinolite walls to smooth finish, Prepare and paint walls, 2 coats, Plascon Double Velvet, as per specification above tiles up to ceiling 15 Remove all loose and peeling paint from ceiling, where necessary m ² 14 Remove all loose and peeling paint from ceiling, where necessary m ² 15 Remove all loose and peeling paint from ceiling, where necessary m ² 16 Plascon Double Velvet, as per specification above tiles up to ceiling	8						
	Supply and fit aluminium toilet sign on entrance door Supply and fit aluminium male and female sign to the internal doors No Remove existing toilets, supply and fit new Ceramic toilet including cistern, enamel coated wooden toilet seat, connect to existing water supply and drain	Supply and fit new vacant/engaged lockset to each door Supply and fit new hollow core wooden doors to each toilet Prepare and paint door and door frames 2 coats Plascon Enamel as per specification Supply and fit 5ft double LED tube light fitting complete with tubes and clip on cover Remove all loose and peeling paint from walls, where necessary rhinolite walls to smooth finish, Prepare and paint walls, 2 coats, Plascon Double Velvet, as per specification above tiles up to ceiling Remove all loose and peeling paint from ceiling, where necessary Remove all loose and peeling paint from ceiling, where necessary Remove all loose and peeling paint from ceiling, where necessary		supply and drain	NT	2			
	Supply and fit aluminium toilet sign on entrance door Supply and fit aluminium male and female sign to the internal doors No Remove existing toilets, supply and fit new Ceramic toilet including cistern, enamel coated wooden toilet seat, connect to existing water supply and drain Supply and fit steel lockable toilet paper holder to accommodate 3 No 2	11 Supply and fit new hollow core wooden doors to each toilet 12 Prepare and paint door and door frames 2 coats Plascon Enamel as per specification 13 Supply and fit 5ft double LED tube light fitting complete with tubes and clip on cover 14 Remove all loose and peeling paint from walls, where necessary rhinolite walls to smooth finish, Prepare and paint walls, 2 coats, Plascon Double Velvet, as per specification above tiles up to ceiling 15 Remove all loose and peeling paint from ceiling, where necessary m ² 14		supply and drain Supply and fit steel lockable toilet paper holder to accommodate 3	No	2			
rolls at a time	Supply and fit aluminium toilet sign on entrance door Supply and fit aluminium male and female sign to the internal doors No Remove existing toilets, supply and fit new Ceramic toilet including cistern, enamel coated wooden toilet seat, connect to existing water supply and drain Supply and fit steel lockable toilet paper holder to accommodate 3 No 2 7 8 8 8 8 8 8 8 8 8 8 8 8	Prepare and paint door and door frames 2 coats Plascon Enamel as per specification Supply and fit 5ft double LED tube light fitting complete with tubes and clip on cover Remove all loose and peeling paint from walls, where necessary rhinolite walls to smooth finish, Prepare and paint walls, 2 coats, Plascon Double Velvet, as per specification above tiles up to ceiling Remove all loose and peeling paint from ceiling, where necessary m ² Remove all loose and peeling paint from ceiling, where necessary m ² 14	9	supply and drain Supply and fit steel lockable toilet paper holder to accommodate 3 rolls at a time					
rolls at a time 10 Supply and fit new vacant/engaged lockset to each door No 2	Supply and fit aluminium toilet sign on entrance door Supply and fit aluminium male and female sign to the internal doors Remove existing toilets, supply and fit new Ceramic toilet including cistern, enamel coated wooden toilet seat, connect to existing water supply and drain Supply and fit steel lockable toilet paper holder to accommodate 3 rolls at a time Supply and fit new vacant/engaged lockset to each door No 2	per specification Supply and fit 5ft double LED tube light fitting complete with tubes and clip on cover Remove all loose and peeling paint from walls, where necessary rhinolite walls to smooth finish, Prepare and paint walls, 2 coats, Plascon Double Velvet, as per specification above tiles up to ceiling Remove all loose and peeling paint from ceiling, where necessary m ² Remove all loose and peeling paint from ceiling, where necessary m ² 14	9	supply and drain Supply and fit steel lockable toilet paper holder to accommodate 3 rolls at a time Supply and fit new vacant/engaged lockset to each door	No	2			
rolls at a time 10 Supply and fit new vacant/engaged lockset to each door No 2 11 Supply and fit new hollow core wooden doors to each toilet No 2	Supply and fit aluminium toilet sign on entrance door Supply and fit aluminium male and female sign to the internal doors Remove existing toilets, supply and fit new Ceramic toilet including cistern, enamel coated wooden toilet seat, connect to existing water supply and drain Supply and fit steel lockable toilet paper holder to accommodate 3 rolls at a time Supply and fit new vacant/engaged lockset to each door Supply and fit new hollow core wooden doors to each toilet No 2 Supply and fit new hollow core wooden doors to each toilet No 2	Supply and fit 5ft double LED tube light fitting complete with tubes and clip on cover Remove all loose and peeling paint from walls, where necessary rhinolite walls to smooth finish, Prepare and paint walls, 2 coats, Plascon Double Velvet, as per specification above tiles up to ceiling Remove all loose and peeling paint from ceiling, where necessary m ² Remove all loose and peeling paint from ceiling, where necessary m ² 14	9 10 11	supply and drain Supply and fit steel lockable toilet paper holder to accommodate 3 rolls at a time Supply and fit new vacant/engaged lockset to each door Supply and fit new hollow core wooden doors to each toilet	No No	2 2			
rolls at a time 10 Supply and fit new vacant/engaged lockset to each door 11 Supply and fit new hollow core wooden doors to each toilet 12 Prepare and paint door and door frames 2 coats Plascon Enamel as 13 No 2 No 2 No 2 No 2 No 2 No 3 No 4 No 5 No 6 No 7 No 8	Supply and fit aluminium toilet sign on entrance door Supply and fit aluminium male and female sign to the internal doors Remove existing toilets, supply and fit new Ceramic toilet including cistern, enamel coated wooden toilet seat, connect to existing water supply and drain Supply and fit steel lockable toilet paper holder to accommodate 3 rolls at a time Supply and fit new vacant/engaged lockset to each door Supply and fit new hollow core wooden doors to each toilet Prepare and paint door and door frames 2 coats Plascon Enamel as	and clip on cover Remove all loose and peeling paint from walls, where necessary rhinolite walls to smooth finish, Prepare and paint walls, 2 coats, Plascon Double Velvet, as per specification above tiles up to ceiling Remove all loose and peeling paint from ceiling, where necessary m ² 14	9 10 11	supply and drain Supply and fit steel lockable toilet paper holder to accommodate 3 rolls at a time Supply and fit new vacant/engaged lockset to each door Supply and fit new hollow core wooden doors to each toilet Prepare and paint door and door frames 2 coats Plascon Enamel as	No No	2 2			
rolls at a time 10 Supply and fit new vacant/engaged lockset to each door 11 Supply and fit new hollow core wooden doors to each toilet 12 Prepare and paint door and door frames 2 coats Plascon Enamel as per specification No 2 Propare and paint door and door frames 2 coats Plascon Enamel as per specification	Supply and fit aluminium toilet sign on entrance door Supply and fit aluminium male and female sign to the internal doors Remove existing toilets, supply and fit new Ceramic toilet including cistern, enamel coated wooden toilet seat, connect to existing water supply and drain Supply and fit steel lockable toilet paper holder to accommodate 3 rolls at a time Supply and fit new vacant/engaged lockset to each door Supply and fit new hollow core wooden doors to each toilet Prepare and paint door and door frames 2 coats Plascon Enamel as per specification	Remove all loose and peeling paint from walls, where necessary rhinolite walls to smooth finish, Prepare and paint walls, 2 coats, Plascon Double Velvet, as per specification above tiles up to ceiling Remove all loose and peeling paint from ceiling, where necessary m ² 14	9 10 11 12	supply and drain Supply and fit steel lockable toilet paper holder to accommodate 3 rolls at a time Supply and fit new vacant/engaged lockset to each door Supply and fit new hollow core wooden doors to each toilet Prepare and paint door and door frames 2 coats Plascon Enamel as per specification	No No No	2 2 2			
rolls at a time 10 Supply and fit new vacant/engaged lockset to each door 11 Supply and fit new hollow core wooden doors to each toilet 12 Prepare and paint door and door frames 2 coats Plascon Enamel as per specification 13 Supply and fit 5ft double LED tube light fitting complete with tubes 10 No 2 Double LED tube light fitting complete with tubes 2 No 1 Double LED tube light fitting complete with tubes 3 No 4 Double LED tube light fitting complete with tubes 4 Double LED tube light fitting complete with tubes 5 No 6 Double LED tube light fitting complete with tubes 6 Double LED tube light fitting complete with tubes 7 Double LED tube light fitting complete with tubes 7 Double LED tube light fitting complete with tubes 8 Double LED tube light fitting complete with tubes 9 Double LED tube light fitting complete with tubes 9 Double LED tube light fitting complete with tubes 9 Double LED tube light fitting complete with tubes 9 Double LED tube light fitting complete with tubes 9 Double LED tube light fitting complete with tubes 9 Double LED tube light fitting complete with tubes 9 Double LED tube light fitting complete with tubes 9 Double LED tube light fitting complete with tubes 9 Double LED tube light fitting complete with tubes 9 Double LED tube light fitting complete with tubes 9 Double LED tube light fitting complete with tubes 9 Double LED tube light fitting complete with tubes	Supply and fit aluminium toilet sign on entrance door Supply and fit aluminium male and female sign to the internal doors Remove existing toilets, supply and fit new Ceramic toilet including cistern, enamel coated wooden toilet seat, connect to existing water supply and drain Supply and fit steel lockable toilet paper holder to accommodate 3 rolls at a time Supply and fit new vacant/engaged lockset to each door Supply and fit new hollow core wooden doors to each toilet Prepare and paint door and door frames 2 coats Plascon Enamel as per specification Supply and fit 5ft double LED tube light fitting complete with tubes No 1 No 2 2 3 4 5 5 6 7 7 8 8 8 9 1 1 8 8 9 1 8 9 1 8 9 1 8 9 1 8 9 1 8 9 1 8 9 1 8 9 1 9 1 9 1 1 1 1 1 1 1 1	rhinolite walls to smooth finish, Prepare and paint walls, 2 coats, Plascon Double Velvet, as per specification above tiles up to ceiling 15 Remove all loose and peeling paint from ceiling, where necessary m ² 14	9 10 11 12	supply and drain Supply and fit steel lockable toilet paper holder to accommodate 3 rolls at a time Supply and fit new vacant/engaged lockset to each door Supply and fit new hollow core wooden doors to each toilet Prepare and paint door and door frames 2 coats Plascon Enamel as per specification Supply and fit 5ft double LED tube light fitting complete with tubes	No No No	2 2 2			
rolls at a time 10 Supply and fit new vacant/engaged lockset to each door 11 Supply and fit new hollow core wooden doors to each toilet 12 Prepare and paint door and door frames 2 coats Plascon Enamel as per specification 13 Supply and fit 5ft double LED tube light fitting complete with tubes and clip on cover	Supply and fit aluminium toilet sign on entrance door Supply and fit aluminium male and female sign to the internal doors Remove existing toilets, supply and fit new Ceramic toilet including cistern, enamel coated wooden toilet seat, connect to existing water supply and drain Supply and fit steel lockable toilet paper holder to accommodate 3 rolls at a time Supply and fit new vacant/engaged lockset to each door Supply and fit new hollow core wooden doors to each toilet Prepare and paint door and door frames 2 coats Plascon Enamel as per specification Supply and fit 5ft double LED tube light fitting complete with tubes and clip on cover	Plascon Double Velvet, as per specification above tiles up to ceiling 15 Remove all loose and peeling paint from ceiling, where necessary m ² 14	9 10 11 12	supply and drain Supply and fit steel lockable toilet paper holder to accommodate 3 rolls at a time Supply and fit new vacant/engaged lockset to each door Supply and fit new hollow core wooden doors to each toilet Prepare and paint door and door frames 2 coats Plascon Enamel as per specification Supply and fit 5ft double LED tube light fitting complete with tubes and clip on cover	No No No	2 2 2 1			
rolls at a time 10 Supply and fit new vacant/engaged lockset to each door 11 Supply and fit new hollow core wooden doors to each toilet 12 Prepare and paint door and door frames 2 coats Plascon Enamel as per specification 13 Supply and fit 5ft double LED tube light fitting complete with tubes and clip on cover 14 Remove all loose and peeling paint from walls, where necessary 15 No 16 No 17 No 18 No 19 No 10 No 10 No 11 No 11 No 11 No 12 No 13 Supply and fit 5ft double LED tube light fitting complete with tubes and clip on cover	Supply and fit aluminium toilet sign on entrance door Supply and fit aluminium male and female sign to the internal doors Remove existing toilets, supply and fit new Ceramic toilet including cistern, enamel coated wooden toilet seat, connect to existing water supply and drain Supply and fit steel lockable toilet paper holder to accommodate 3 rolls at a time Supply and fit new vacant/engaged lockset to each door Supply and fit new hollow core wooden doors to each toilet Prepare and paint door and door frames 2 coats Plascon Enamel as per specification Supply and fit 5ft double LED tube light fitting complete with tubes and clip on cover Remove all loose and peeling paint from walls, where necessary No 1 No 2 2 1 1 1 1 1 1 1 1 1 1 1	Remove all loose and peeling paint from ceiling, where necessary m ² 14	9 10 11 12	supply and drain Supply and fit steel lockable toilet paper holder to accommodate 3 rolls at a time Supply and fit new vacant/engaged lockset to each door Supply and fit new hollow core wooden doors to each toilet Prepare and paint door and door frames 2 coats Plascon Enamel as per specification Supply and fit 5ft double LED tube light fitting complete with tubes and clip on cover Remove all loose and peeling paint from walls, where necessary	No No No	2 2 2 1			
rolls at a time 10 Supply and fit new vacant/engaged lockset to each door 11 Supply and fit new hollow core wooden doors to each toilet 12 Prepare and paint door and door frames 2 coats Plascon Enamel as per specification 13 Supply and fit 5ft double LED tube light fitting complete with tubes and clip on cover 14 Remove all loose and peeling paint from walls, where necessary rhinolite walls to smooth finish, Prepare and paint walls, 2 coats,	Supply and fit aluminium toilet sign on entrance door Supply and fit aluminium male and female sign to the internal doors Remove existing toilets, supply and fit new Ceramic toilet including cistern, enamel coated wooden toilet seat, connect to existing water supply and drain Supply and fit steel lockable toilet paper holder to accommodate 3 rolls at a time Supply and fit new vacant/engaged lockset to each door Supply and fit new hollow core wooden doors to each toilet Prepare and paint door and door frames 2 coats Plascon Enamel as per specification Supply and fit 5ft double LED tube light fitting complete with tubes and clip on cover Remove all loose and peeling paint from walls, where necessary rhinolite walls to smooth finish, Prepare and paint walls, 2 coats,		9 10 11 12	supply and drain Supply and fit steel lockable toilet paper holder to accommodate 3 rolls at a time Supply and fit new vacant/engaged lockset to each door Supply and fit new hollow core wooden doors to each toilet Prepare and paint door and door frames 2 coats Plascon Enamel as per specification Supply and fit 5ft double LED tube light fitting complete with tubes and clip on cover Remove all loose and peeling paint from walls, where necessary rhinolite walls to smooth finish, Prepare and paint walls, 2 coats,	No No No	2 2 2 1			
rolls at a time 10 Supply and fit new vacant/engaged lockset to each door 11 Supply and fit new hollow core wooden doors to each toilet 12 Prepare and paint door and door frames 2 coats Plascon Enamel as per specification 13 Supply and fit 5ft double LED tube light fitting complete with tubes and clip on cover 14 Remove all loose and peeling paint from walls, where necessary rhinolite walls to smooth finish, Prepare and paint walls, 2 coats, Plascon Double Velvet, as per specification above tiles up to ceiling	Supply and fit aluminium toilet sign on entrance door Supply and fit aluminium male and female sign to the internal doors Remove existing toilets, supply and fit new Ceramic toilet including cistern, enamel coated wooden toilet seat, connect to existing water supply and drain Supply and fit steel lockable toilet paper holder to accommodate 3 rolls at a time Supply and fit new vacant/engaged lockset to each door Supply and fit new hollow core wooden doors to each toilet Prepare and paint door and door frames 2 coats Plascon Enamel as per specification Supply and fit 5ft double LED tube light fitting complete with tubes and clip on cover Remove all loose and peeling paint from walls, where necessary rhinolite walls to smooth finish, Prepare and paint walls, 2 coats, Plascon Double Velvet, as per specification above tiles up to ceiling	Tunnome centry to smooth tinish Prenare and nami centro / coars	9 10 11 12 13	supply and drain Supply and fit steel lockable toilet paper holder to accommodate 3 rolls at a time Supply and fit new vacant/engaged lockset to each door Supply and fit new hollow core wooden doors to each toilet Prepare and paint door and door frames 2 coats Plascon Enamel as per specification Supply and fit 5ft double LED tube light fitting complete with tubes and clip on cover Remove all loose and peeling paint from walls, where necessary rhinolite walls to smooth finish, Prepare and paint walls, 2 coats, Plascon Double Velvet, as per specification above tiles up to ceiling	No No No no m²	2 2 2 1 25			
rolls at a time 10 Supply and fit new vacant/engaged lockset to each door 11 Supply and fit new hollow core wooden doors to each toilet 12 Prepare and paint door and door frames 2 coats Plascon Enamel as per specification 13 Supply and fit 5ft double LED tube light fitting complete with tubes and clip on cover 14 Remove all loose and peeling paint from walls, where necessary rhinolite walls to smooth finish, Prepare and paint walls, 2 coats, Plascon Double Velvet, as per specification above tiles up to ceiling 15 Remove all loose and peeling paint from ceiling, where necessary m ² 14 Remove all loose and peeling paint from ceiling, where necessary m ² 15 Remove all loose and peeling paint from ceiling, where necessary m ² 16 Plascon Double Velvet, as per specification above tiles up to ceiling	Supply and fit aluminium toilet sign on entrance door Supply and fit aluminium male and female sign to the internal doors Remove existing toilets, supply and fit new Ceramic toilet including cistern, enamel coated wooden toilet seat, connect to existing water supply and drain Supply and fit steel lockable toilet paper holder to accommodate 3 rolls at a time Supply and fit new vacant/engaged lockset to each door Supply and fit new hollow core wooden doors to each toilet Prepare and paint door and door frames 2 coats Plascon Enamel as per specification Supply and fit 5ft double LED tube light fitting complete with tubes and clip on cover Remove all loose and peeling paint from walls, where necessary rhinolite walls to smooth finish, Prepare and paint walls, 2 coats, Plascon Double Velvet, as per specification above tiles up to ceiling Remove all loose and peeling paint from ceiling, where necessary m² 14	Innotice coming to smooth rimon, respute and paint coming, 2 coats,	9 10 11 12 13	supply and drain Supply and fit steel lockable toilet paper holder to accommodate 3 rolls at a time Supply and fit new vacant/engaged lockset to each door Supply and fit new hollow core wooden doors to each toilet Prepare and paint door and door frames 2 coats Plascon Enamel as per specification Supply and fit 5ft double LED tube light fitting complete with tubes and clip on cover Remove all loose and peeling paint from walls, where necessary rhinolite walls to smooth finish, Prepare and paint walls, 2 coats, Plascon Double Velvet, as per specification above tiles up to ceiling Remove all loose and peeling paint from ceiling, where necessary	No No No no m²	2 2 2 1 25			
1 O CCIAIN WAN THE 4400 MEN UD TO GOU HEISHE		6 Supply and fit aluminium toilet sign on entrance door No 1 7 Supply and fit aluminium male and female sign to the internal doors No 1 8 Remove existing toilets, supply and fit new Ceramic toilet including cistern, enamel coated wooden toilet seat, connect to existing water supply and drain No 2 9 Supply and fit steel lockable toilet paper holder to accommodate 3 rolls at a time No 2 10 Supply and fit new vacant/engaged lockset to each door No 2 11 Supply and fit new hollow core wooden doors to each toilet No 2 12 Prepare and paint door and door frames 2 coats Plascon Enamel as per specification No 2 13 Supply and fit 5ft double LED tube light fitting complete with tubes and clip on cover No 1 14 Remove all loose and peeling paint from walls, where necessary rhinolite walls to smooth finish, Prepare and paint walls, 2 coats, Plascon Double Velvet, as per specification above tiles up to ceiling m² 25 15 Remove all loose and peeling paint from ceiling, where necessary m² 14	5		111	32			
	1 ofeciani wan thes 2200 High up to door neight	7 Supply and fit aluminium male and female sign to the internal doors No 1 8 Remove existing toilets, supply and fit new Ceramic toilet including cistern, enamel coated wooden toilet seat, connect to existing water supply and drain No 2 9 Supply and fit steel lockable toilet paper holder to accommodate 3 rolls at a time No 2 10 Supply and fit new vacant/engaged lockset to each door No 2 11 Supply and fit new hollow core wooden doors to each toilet No 2 12 Prepare and paint door and door frames 2 coats Plascon Enamel as per specification No 2 13 Supply and fit 5ft double LED tube light fitting complete with tubes and clip on cover No 1 14 Remove all loose and peeling paint from walls, where necessary rhinolite walls to smooth finish, Prepare and paint walls, 2 coats, Plascon Double Velvet, as per specification above tiles up to ceiling m² 25 15 Remove all loose and peeling paint from ceiling, where necessary m² 14	6		No	1	+		
		Remove existing toilets, supply and fit new Ceramic toilet including cistern, enamel coated wooden toilet seat, connect to existing water supply and drain Supply and fit steel lockable toilet paper holder to accommodate 3 No 2 rolls at a time Supply and fit new vacant/engaged lockset to each door No 2 Supply and fit new hollow core wooden doors to each toilet No 2 Prepare and paint door and door frames 2 coats Plascon Enamel as per specification Supply and fit 5ft double LED tube light fitting complete with tubes and clip on cover Remove all loose and peeling paint from walls, where necessary rhinolite walls to smooth finish, Prepare and paint walls, 2 coats, Plascon Double Velvet, as per specification above tiles up to ceiling Remove all loose and peeling paint from ceiling, where necessary m ² 14							
7 Supply and fit aluminium male and female sign to the internal doors No 1	Supply and fit aluminium toilet sign on entrance door No 1	Remove existing toilets, supply and fit new Ceramic toilet including cistern, enamel coated wooden toilet seat, connect to existing water supply and drain Supply and fit steel lockable toilet paper holder to accommodate 3 No 2 rolls at a time Supply and fit new vacant/engaged lockset to each door No 2 Supply and fit new hollow core wooden doors to each toilet No 2 Prepare and paint door and door frames 2 coats Plascon Enamel as per specification Supply and fit 5ft double LED tube light fitting complete with tubes and clip on cover Remove all loose and peeling paint from walls, where necessary rhinolite walls to smooth finish, Prepare and paint walls, 2 coats, Plascon Double Velvet, as per specification above tiles up to ceiling Remove all loose and peeling paint from ceiling, where necessary m ² 14	7	Supply and fit aluminium male and female sign to the internal doors	No	1			
	Supply and fit aluminium toilet sign on entrance door No 1	cistern, enamel coated wooden toilet seat, connect to existing water supply and drain 9 Supply and fit steel lockable toilet paper holder to accommodate 3 No 2 rolls at a time 10 Supply and fit new vacant/engaged lockset to each door No 2 11 Supply and fit new hollow core wooden doors to each toilet No 2 12 Prepare and paint door and door frames 2 coats Plascon Enamel as per specification 13 Supply and fit 5ft double LED tube light fitting complete with tubes and clip on cover 14 Remove all loose and peeling paint from walls, where necessary rhinolite walls to smooth finish, Prepare and paint walls, 2 coats, Plascon Double Velvet, as per specification above tiles up to ceiling 15 Remove all loose and peeling paint from ceiling, where necessary m² 14		:					
	Supply and fit aluminium toilet sign on entrance door No 1 Supply and fit aluminium male and female sign to the internal doors No 1	supply and drain Supply and fit steel lockable toilet paper holder to accommodate 3 No 2 rolls at a time Supply and fit new vacant/engaged lockset to each door No 2 Supply and fit new hollow core wooden doors to each toilet No 2 Prepare and paint door and door frames 2 coats Plascon Enamel as per specification Supply and fit 5ft double LED tube light fitting complete with tubes and clip on cover Remove all loose and peeling paint from walls, where necessary rhinolite walls to smooth finish, Prepare and paint walls, 2 coats, Plascon Double Velvet, as per specification above tiles up to ceiling Remove all loose and peeling paint from ceiling, where necessary m² 14	×	Remove existing tonets, supply and fit new Ceramic tonet including	INO				
	Supply and fit aluminium toilet sign on entrance door No 1 Supply and fit aluminium male and female sign to the internal doors No 1 Remove existing toilets, supply and fit new Ceramic toilet including No 2	Supply and fit steel lockable toilet paper holder to accommodate 3 rolls at a time 10 Supply and fit new vacant/engaged lockset to each door No 2 11 Supply and fit new hollow core wooden doors to each toilet No 2 12 Prepare and paint door and door frames 2 coats Plascon Enamel as per specification 13 Supply and fit 5ft double LED tube light fitting complete with tubes and clip on cover 14 Remove all loose and peeling paint from walls, where necessary rhinolite walls to smooth finish, Prepare and paint walls, 2 coats, Plascon Double Velvet, as per specification above tiles up to ceiling 15 Remove all loose and peeling paint from ceiling, where necessary m² 14	8				1	1	
	Supply and fit aluminium toilet sign on entrance door Supply and fit aluminium male and female sign to the internal doors No Remove existing toilets, supply and fit new Ceramic toilet including cistern, enamel coated wooden toilet seat, connect to existing water	rolls at a time 10 Supply and fit new vacant/engaged lockset to each door 11 Supply and fit new hollow core wooden doors to each toilet 12 Prepare and paint door and door frames 2 coats Plascon Enamel as per specification 13 Supply and fit 5ft double LED tube light fitting complete with tubes and clip on cover 14 Remove all loose and peeling paint from walls, where necessary rhinolite walls to smooth finish, Prepare and paint walls, 2 coats, Plascon Double Velvet, as per specification above tiles up to ceiling 15 Remove all loose and peeling paint from ceiling, where necessary m ² 14 Remove all loose and peeling paint from ceiling, where necessary m ² 15 Remove all loose and peeling paint from ceiling, where necessary m ² 16 Plascon Double Velvet, as per specification above tiles up to ceiling	8						
O Symply and fit steel legisphe toilet monarie 11-11-11-11-11-11-11-11-11-11-11-11-11-	Supply and fit aluminium toilet sign on entrance door Supply and fit aluminium male and female sign to the internal doors No Remove existing toilets, supply and fit new Ceramic toilet including cistern, enamel coated wooden toilet seat, connect to existing water supply and drain	Supply and fit new vacant/engaged lockset to each door Supply and fit new hollow core wooden doors to each toilet Prepare and paint door and door frames 2 coats Plascon Enamel as per specification Supply and fit 5ft double LED tube light fitting complete with tubes and clip on cover Remove all loose and peeling paint from walls, where necessary rhinolite walls to smooth finish, Prepare and paint walls, 2 coats, Plascon Double Velvet, as per specification above tiles up to ceiling Remove all loose and peeling paint from ceiling, where necessary Remove all loose and peeling paint from ceiling, where necessary Remove all loose and peeling paint from ceiling, where necessary	8	supply and drain					
5 Supply and III steel lockable tollet paper holder to accommodate 3 No 2	Supply and fit aluminium toilet sign on entrance door Supply and fit aluminium male and female sign to the internal doors No Remove existing toilets, supply and fit new Ceramic toilet including cistern, enamel coated wooden toilet seat, connect to existing water supply and drain	Supply and fit new vacant/engaged lockset to each door Supply and fit new hollow core wooden doors to each toilet Prepare and paint door and door frames 2 coats Plascon Enamel as per specification Supply and fit 5ft double LED tube light fitting complete with tubes and clip on cover Remove all loose and peeling paint from walls, where necessary rhinolite walls to smooth finish, Prepare and paint walls, 2 coats, Plascon Double Velvet, as per specification above tiles up to ceiling Remove all loose and peeling paint from ceiling, where necessary Remove all loose and peeling paint from ceiling, where necessary Remove all loose and peeling paint from ceiling, where necessary		supply and drain	No	2			
	Supply and fit aluminium toilet sign on entrance door Supply and fit aluminium male and female sign to the internal doors No Remove existing toilets, supply and fit new Ceramic toilet including cistern, enamel coated wooden toilet seat, connect to existing water supply and drain Supply and fit steel lockable toilet paper holder to accommodate 3 No 2	11 Supply and fit new hollow core wooden doors to each toilet 12 Prepare and paint door and door frames 2 coats Plascon Enamel as per specification 13 Supply and fit 5ft double LED tube light fitting complete with tubes and clip on cover 14 Remove all loose and peeling paint from walls, where necessary rhinolite walls to smooth finish, Prepare and paint walls, 2 coats, Plascon Double Velvet, as per specification above tiles up to ceiling 15 Remove all loose and peeling paint from ceiling, where necessary m ² 14		supply and drain Supply and fit steel lockable toilet paper holder to accommodate 3	No	2			
rolls at a time	Supply and fit aluminium toilet sign on entrance door Supply and fit aluminium male and female sign to the internal doors No Remove existing toilets, supply and fit new Ceramic toilet including cistern, enamel coated wooden toilet seat, connect to existing water supply and drain Supply and fit steel lockable toilet paper holder to accommodate 3 No 2 7 8 8 8 8 8 8 8 8 8 8 8 8	Prepare and paint door and door frames 2 coats Plascon Enamel as per specification Supply and fit 5ft double LED tube light fitting complete with tubes and clip on cover Remove all loose and peeling paint from walls, where necessary rhinolite walls to smooth finish, Prepare and paint walls, 2 coats, Plascon Double Velvet, as per specification above tiles up to ceiling Remove all loose and peeling paint from ceiling, where necessary m ² Remove all loose and peeling paint from ceiling, where necessary m ² 14	9	supply and drain Supply and fit steel lockable toilet paper holder to accommodate 3 rolls at a time					
rolls at a time 10 Supply and fit new vacant/engaged lockset to each door No 2	Supply and fit aluminium toilet sign on entrance door Supply and fit aluminium male and female sign to the internal doors Remove existing toilets, supply and fit new Ceramic toilet including cistern, enamel coated wooden toilet seat, connect to existing water supply and drain Supply and fit steel lockable toilet paper holder to accommodate 3 rolls at a time Supply and fit new vacant/engaged lockset to each door No 2	per specification Supply and fit 5ft double LED tube light fitting complete with tubes and clip on cover Remove all loose and peeling paint from walls, where necessary rhinolite walls to smooth finish, Prepare and paint walls, 2 coats, Plascon Double Velvet, as per specification above tiles up to ceiling Remove all loose and peeling paint from ceiling, where necessary m ² Remove all loose and peeling paint from ceiling, where necessary m ² 14	9	supply and drain Supply and fit steel lockable toilet paper holder to accommodate 3 rolls at a time Supply and fit new vacant/engaged lockset to each door	No	2			
rolls at a time 10 Supply and fit new vacant/engaged lockset to each door No 2 11 Supply and fit new hollow core wooden doors to each toilet No 2	Supply and fit aluminium toilet sign on entrance door Supply and fit aluminium male and female sign to the internal doors Remove existing toilets, supply and fit new Ceramic toilet including cistern, enamel coated wooden toilet seat, connect to existing water supply and drain Supply and fit steel lockable toilet paper holder to accommodate 3 rolls at a time Supply and fit new vacant/engaged lockset to each door Supply and fit new hollow core wooden doors to each toilet No 2 Supply and fit new hollow core wooden doors to each toilet No 2	Supply and fit 5ft double LED tube light fitting complete with tubes and clip on cover Remove all loose and peeling paint from walls, where necessary rhinolite walls to smooth finish, Prepare and paint walls, 2 coats, Plascon Double Velvet, as per specification above tiles up to ceiling Remove all loose and peeling paint from ceiling, where necessary m ² Remove all loose and peeling paint from ceiling, where necessary m ² 14	9 10 11	supply and drain Supply and fit steel lockable toilet paper holder to accommodate 3 rolls at a time Supply and fit new vacant/engaged lockset to each door Supply and fit new hollow core wooden doors to each toilet	No No	2 2			
rolls at a time 10 Supply and fit new vacant/engaged lockset to each door No 2 11 Supply and fit new hollow core wooden doors to each toilet No 2 12 Prepare and paint door and door frames 2 coats Plascon Enamel as No 2	Supply and fit aluminium toilet sign on entrance door Supply and fit aluminium male and female sign to the internal doors Remove existing toilets, supply and fit new Ceramic toilet including cistern, enamel coated wooden toilet seat, connect to existing water supply and drain Supply and fit steel lockable toilet paper holder to accommodate 3 rolls at a time Supply and fit new vacant/engaged lockset to each door Supply and fit new hollow core wooden doors to each toilet Prepare and paint door and door frames 2 coats Plascon Enamel as	and clip on cover 14 Remove all loose and peeling paint from walls, where necessary m ² 25 rhinolite walls to smooth finish, Prepare and paint walls, 2 coats, Plascon Double Velvet, as per specification above tiles up to ceiling 15 Remove all loose and peeling paint from ceiling, where necessary m ² 14	9 10 11	supply and drain Supply and fit steel lockable toilet paper holder to accommodate 3 rolls at a time Supply and fit new vacant/engaged lockset to each door Supply and fit new hollow core wooden doors to each toilet Prepare and paint door and door frames 2 coats Plascon Enamel as	No No	2 2			
rolls at a time 10 Supply and fit new vacant/engaged lockset to each door 11 Supply and fit new hollow core wooden doors to each toilet 12 Prepare and paint door and door frames 2 coats Plascon Enamel as per specification No 2 Propare and paint door and door frames 2 coats Plascon Enamel as per specification	Supply and fit aluminium toilet sign on entrance door Supply and fit aluminium male and female sign to the internal doors Remove existing toilets, supply and fit new Ceramic toilet including cistern, enamel coated wooden toilet seat, connect to existing water supply and drain Supply and fit steel lockable toilet paper holder to accommodate 3 rolls at a time Supply and fit new vacant/engaged lockset to each door Supply and fit new hollow core wooden doors to each toilet Prepare and paint door and door frames 2 coats Plascon Enamel as per specification	Remove all loose and peeling paint from walls, where necessary rhinolite walls to smooth finish, Prepare and paint walls, 2 coats, Plascon Double Velvet, as per specification above tiles up to ceiling Remove all loose and peeling paint from ceiling, where necessary m ² 14	9 10 11 12	supply and drain Supply and fit steel lockable toilet paper holder to accommodate 3 rolls at a time Supply and fit new vacant/engaged lockset to each door Supply and fit new hollow core wooden doors to each toilet Prepare and paint door and door frames 2 coats Plascon Enamel as per specification	No No No	2 2 2			
rolls at a time 10 Supply and fit new vacant/engaged lockset to each door 11 Supply and fit new hollow core wooden doors to each toilet 12 Prepare and paint door and door frames 2 coats Plascon Enamel as per specification No 2 Propare and paint door and door frames 2 coats Plascon Enamel as per specification	Supply and fit aluminium toilet sign on entrance door Supply and fit aluminium male and female sign to the internal doors Remove existing toilets, supply and fit new Ceramic toilet including cistern, enamel coated wooden toilet seat, connect to existing water supply and drain Supply and fit steel lockable toilet paper holder to accommodate 3 rolls at a time Supply and fit new vacant/engaged lockset to each door Supply and fit new hollow core wooden doors to each toilet Prepare and paint door and door frames 2 coats Plascon Enamel as per specification	Remove all loose and peeling paint from walls, where necessary rhinolite walls to smooth finish, Prepare and paint walls, 2 coats, Plascon Double Velvet, as per specification above tiles up to ceiling Remove all loose and peeling paint from ceiling, where necessary m ² 14	9 10 11 12	supply and drain Supply and fit steel lockable toilet paper holder to accommodate 3 rolls at a time Supply and fit new vacant/engaged lockset to each door Supply and fit new hollow core wooden doors to each toilet Prepare and paint door and door frames 2 coats Plascon Enamel as per specification	No No No	2 2 2			
rolls at a time 10 Supply and fit new vacant/engaged lockset to each door 11 Supply and fit new hollow core wooden doors to each toilet 12 Prepare and paint door and door frames 2 coats Plascon Enamel as per specification 13 Supply and fit 5ft double LED tube light fitting complete with tubes 10 No 2 Double LED tube light fitting complete with tubes 2 No 1 Double LED tube light fitting complete with tubes 1 Double LED tube light fitting complete with tubes 1 Double LED tube light fitting complete with tubes 1 Double LED tube light fitting complete with tubes 1 Double LED tube light fitting complete with tubes 1 Double LED tube light fitting complete with tubes	Supply and fit aluminium toilet sign on entrance door Supply and fit aluminium male and female sign to the internal doors Remove existing toilets, supply and fit new Ceramic toilet including cistern, enamel coated wooden toilet seat, connect to existing water supply and drain Supply and fit steel lockable toilet paper holder to accommodate 3 rolls at a time Supply and fit new vacant/engaged lockset to each door Supply and fit new hollow core wooden doors to each toilet Prepare and paint door and door frames 2 coats Plascon Enamel as per specification Supply and fit 5ft double LED tube light fitting complete with tubes No 1 No 2 2 3 4 5 5 6 7 7 8 8 8 9 1 1 8 8 9 1 8 9 1 8 9 1 8 9 1 8 9 1 8 9 1 8 9 1 8 9 1 9 1 9 1 1 1 1 1 1 1 1	rhinolite walls to smooth finish, Prepare and paint walls, 2 coats, Plascon Double Velvet, as per specification above tiles up to ceiling 15 Remove all loose and peeling paint from ceiling, where necessary m ² 14	9 10 11 12	supply and drain Supply and fit steel lockable toilet paper holder to accommodate 3 rolls at a time Supply and fit new vacant/engaged lockset to each door Supply and fit new hollow core wooden doors to each toilet Prepare and paint door and door frames 2 coats Plascon Enamel as per specification Supply and fit 5ft double LED tube light fitting complete with tubes	No No No	2 2 2			
rolls at a time 10 Supply and fit new vacant/engaged lockset to each door 11 Supply and fit new hollow core wooden doors to each toilet 12 Prepare and paint door and door frames 2 coats Plascon Enamel as per specification 13 Supply and fit 5ft double LED tube light fitting complete with tubes and clip on cover	Supply and fit aluminium toilet sign on entrance door Supply and fit aluminium male and female sign to the internal doors Remove existing toilets, supply and fit new Ceramic toilet including cistern, enamel coated wooden toilet seat, connect to existing water supply and drain Supply and fit steel lockable toilet paper holder to accommodate 3 rolls at a time Supply and fit new vacant/engaged lockset to each door Supply and fit new hollow core wooden doors to each toilet Prepare and paint door and door frames 2 coats Plascon Enamel as per specification Supply and fit 5ft double LED tube light fitting complete with tubes and clip on cover	Plascon Double Velvet, as per specification above tiles up to ceiling 15 Remove all loose and peeling paint from ceiling, where necessary m ² 14	9 10 11 12	supply and drain Supply and fit steel lockable toilet paper holder to accommodate 3 rolls at a time Supply and fit new vacant/engaged lockset to each door Supply and fit new hollow core wooden doors to each toilet Prepare and paint door and door frames 2 coats Plascon Enamel as per specification Supply and fit 5ft double LED tube light fitting complete with tubes and clip on cover	No No No	2 2 2 1			
rolls at a time 10 Supply and fit new vacant/engaged lockset to each door 11 Supply and fit new hollow core wooden doors to each toilet 12 Prepare and paint door and door frames 2 coats Plascon Enamel as per specification 13 Supply and fit 5ft double LED tube light fitting complete with tubes and clip on cover 14 Remove all loose and peeling paint from walls, where necessary 15 No 16 No 17 No 18 No 19 No 10 No 10 No 11 No 11 No 11 No 12 No 13 Supply and fit 5ft double LED tube light fitting complete with tubes and clip on cover	Supply and fit aluminium toilet sign on entrance door Supply and fit aluminium male and female sign to the internal doors Remove existing toilets, supply and fit new Ceramic toilet including cistern, enamel coated wooden toilet seat, connect to existing water supply and drain Supply and fit steel lockable toilet paper holder to accommodate 3 rolls at a time Supply and fit new vacant/engaged lockset to each door Supply and fit new hollow core wooden doors to each toilet Prepare and paint door and door frames 2 coats Plascon Enamel as per specification Supply and fit 5ft double LED tube light fitting complete with tubes and clip on cover Remove all loose and peeling paint from walls, where necessary No 1 No 2 2 1 1 1 1 1 1 1 1 1 1 1	Remove all loose and peeling paint from ceiling, where necessary m ² 14	9 10 11 12	supply and drain Supply and fit steel lockable toilet paper holder to accommodate 3 rolls at a time Supply and fit new vacant/engaged lockset to each door Supply and fit new hollow core wooden doors to each toilet Prepare and paint door and door frames 2 coats Plascon Enamel as per specification Supply and fit 5ft double LED tube light fitting complete with tubes and clip on cover Remove all loose and peeling paint from walls, where necessary	No No No	2 2 2 1			
rolls at a time 10 Supply and fit new vacant/engaged lockset to each door 11 Supply and fit new hollow core wooden doors to each toilet 12 Prepare and paint door and door frames 2 coats Plascon Enamel as per specification 13 Supply and fit 5ft double LED tube light fitting complete with tubes and clip on cover 14 Remove all loose and peeling paint from walls, where necessary rhinolite walls to smooth finish, Prepare and paint walls, 2 coats,	Supply and fit aluminium toilet sign on entrance door Supply and fit aluminium male and female sign to the internal doors Remove existing toilets, supply and fit new Ceramic toilet including cistern, enamel coated wooden toilet seat, connect to existing water supply and drain Supply and fit steel lockable toilet paper holder to accommodate 3 rolls at a time Supply and fit new vacant/engaged lockset to each door Supply and fit new hollow core wooden doors to each toilet Prepare and paint door and door frames 2 coats Plascon Enamel as per specification Supply and fit 5ft double LED tube light fitting complete with tubes and clip on cover Remove all loose and peeling paint from walls, where necessary rhinolite walls to smooth finish, Prepare and paint walls, 2 coats,	Remove all loose and peeling paint from ceiling, where necessary m ² 14	9 10 11 12	supply and drain Supply and fit steel lockable toilet paper holder to accommodate 3 rolls at a time Supply and fit new vacant/engaged lockset to each door Supply and fit new hollow core wooden doors to each toilet Prepare and paint door and door frames 2 coats Plascon Enamel as per specification Supply and fit 5ft double LED tube light fitting complete with tubes and clip on cover Remove all loose and peeling paint from walls, where necessary rhinolite walls to smooth finish, Prepare and paint walls, 2 coats,	No No No	2 2 2 1			
rolls at a time 10 Supply and fit new vacant/engaged lockset to each door 11 Supply and fit new hollow core wooden doors to each toilet 12 Prepare and paint door and door frames 2 coats Plascon Enamel as per specification 13 Supply and fit 5ft double LED tube light fitting complete with tubes and clip on cover 14 Remove all loose and peeling paint from walls, where necessary rhinolite walls to smooth finish, Prepare and paint walls, 2 coats,	Supply and fit aluminium toilet sign on entrance door Supply and fit aluminium male and female sign to the internal doors Remove existing toilets, supply and fit new Ceramic toilet including cistern, enamel coated wooden toilet seat, connect to existing water supply and drain Supply and fit steel lockable toilet paper holder to accommodate 3 rolls at a time Supply and fit new vacant/engaged lockset to each door Supply and fit new hollow core wooden doors to each toilet Prepare and paint door and door frames 2 coats Plascon Enamel as per specification Supply and fit 5ft double LED tube light fitting complete with tubes and clip on cover Remove all loose and peeling paint from walls, where necessary rhinolite walls to smooth finish, Prepare and paint walls, 2 coats,		9 10 11 12	supply and drain Supply and fit steel lockable toilet paper holder to accommodate 3 rolls at a time Supply and fit new vacant/engaged lockset to each door Supply and fit new hollow core wooden doors to each toilet Prepare and paint door and door frames 2 coats Plascon Enamel as per specification Supply and fit 5ft double LED tube light fitting complete with tubes and clip on cover Remove all loose and peeling paint from walls, where necessary rhinolite walls to smooth finish, Prepare and paint walls, 2 coats,	No No No	2 2 2 1			
rolls at a time 10 Supply and fit new vacant/engaged lockset to each door 11 Supply and fit new hollow core wooden doors to each toilet 12 Prepare and paint door and door frames 2 coats Plascon Enamel as per specification 13 Supply and fit 5ft double LED tube light fitting complete with tubes and clip on cover 14 Remove all loose and peeling paint from walls, where necessary rhinolite walls to smooth finish, Prepare and paint walls, 2 coats, Plascon Double Velvet, as per specification above tiles up to ceiling	Supply and fit aluminium toilet sign on entrance door Supply and fit aluminium male and female sign to the internal doors Remove existing toilets, supply and fit new Ceramic toilet including cistern, enamel coated wooden toilet seat, connect to existing water supply and drain Supply and fit steel lockable toilet paper holder to accommodate 3 rolls at a time Supply and fit new vacant/engaged lockset to each door Supply and fit new hollow core wooden doors to each toilet Prepare and paint door and door frames 2 coats Plascon Enamel as per specification Supply and fit 5ft double LED tube light fitting complete with tubes and clip on cover Remove all loose and peeling paint from walls, where necessary rhinolite walls to smooth finish, Prepare and paint walls, 2 coats, Plascon Double Velvet, as per specification above tiles up to ceiling		9 10 11 12 13	supply and drain Supply and fit steel lockable toilet paper holder to accommodate 3 rolls at a time Supply and fit new vacant/engaged lockset to each door Supply and fit new hollow core wooden doors to each toilet Prepare and paint door and door frames 2 coats Plascon Enamel as per specification Supply and fit 5ft double LED tube light fitting complete with tubes and clip on cover Remove all loose and peeling paint from walls, where necessary rhinolite walls to smooth finish, Prepare and paint walls, 2 coats, Plascon Double Velvet, as per specification above tiles up to ceiling	No No No no m²	2 2 2 1 25			

	Placean Double Volvet as non-anaification		1	1	
16	Plascon Double Velvet, as per specification Supply and fit new Yale Puch Button door lock	No	1		
	7.7.		1		
17	Supply and fit one L automatic battery-operated Motion sensor soap dispenser stainless steel mounted against the wall	No	1		
18	Supply and fit Paper towel dispenser Auto cut/motion sensor stainless steel mounted against the wall	No	1		
19	Supply and fit 18L stainless steel bin mounted against the wall	No	1		
			1		
	Manager Office:		1		
1	Remove all wooden tables, shelves, cupboards and benches and make		Item		
•	good		100111		
2	Supply and fit 5ft double LED tube light fitting complete with tubes	No	1		
	and clip on cover				
3	Remove all loose and peeling paint from walls, where necessary	m^2	35		
	rhinolite walls to smooth finish, Prepare and paint walls, 2 coats,				
	Plascon Double Velvet, as per specification above tiles up to ceiling				
4	Remove all loose and peeling paint from ceiling, where necessary	m^2	12		
	rhinolite ceiling to smooth finish, Prepare and paint ceiling, 2 coats,				
	Plascon Double Velvet, as per specification				
5	Remove existing vinyl sheeting and skirting, prepare floor to smooth	m^2	12		
	finish using self-levelling screed, supply and install 2 ^{mm} Eclipse PUR				
	or Classic Mystique PUR vinyl sheeting with welded joints, vinyl				
	must go up the wall 120 ^{mm} high include cove fillet and capping as per				
	specification				
6	Supply and fit Mahogany 90 Degree link 750 ^{mm} x 600 ^{mm}	No	1		
7	Supply and fit Mahogany lockable sliding door Credenza 1000 ^{mm} x	No	1		
0	600 with shelve	NT_	1		
8	Supply and fit Mobile pedestal top draw locking with 4 drawers and	No	1		
9	pen/pencil tray Supply and deliver Lush Highback Chairs-Forward knee Tilt	No	1		
7	Mechanism-Nylon Base	NU	1		
10	Supply and deliver filling cupboard 1800 ^{mm} high with 4 shelves each	No	2		
10	lockable	110			
11	Remove existing door and door frame, plaster reveals and rhinolite to	No	1		
	smooth finish	1.0			
12	Supply and fit Aluminium window (PT 99) top half opening	No	1		
	outwards, 900 x 900, brick up double brick wall to match existing,				
	plaster and rhinolite on the inside and match brickwork on the outside				
	Complete Lab Building:				
1	Remove existing blinds, supply and fit 50 ^{mm} Polyvinyl Chloride PVC	No	5		
	blinds to windows including rails, 1800 ^{mm} x 1200 ^{mm}				
2	Remove existing blinds, supply and fit 50 ^{mm} Polyvinyl Chloride PVC	No	3		
	blinds to windows including rails, 620 ^{mm} x 1200 ^{mm}				
3	Remove existing blinds, supply and fit 50mm Polyvinyl Chloride PVC	No	2		
	blinds to windows including rails, 1400mm x 1300mm		<u> </u>		
4	Remove existing blinds, supply and fit 50mm Polyvinyl Chloride PVC	No	2		
	blinds to windows including rails, 1900mm x 1200mm				
5	Remove existing blinds, supply and fit 50 ^{mm} Polyvinyl Chloride PVC	No	1		
	blinds to windows including rails, 2500mm x 1200mm		1		
6	Remove exiting doors, supply and fit aluminium frame with 6 ^{mm}	No	6		
	safety laminated single glass doors, fit industrial door handle with				
	separate lockset, supply and fit 4 heavy duty hinges to door, bottom				
	half of door must be solid aluminium and top half must be clear/				
7	frosted glass	N.T.	-		
7	Remove exiting doors, supply and fit aluminium frame with 6 ^{mm}	No	5		
	safety laminated double glass doors, fit industrial door handle with		1		

	separate lockset, supply and fit 4 heavy duty hinges to door, bottom			
	half of door must be solid aluminium and top half must be clear/			
	frosted glass			
8	Remove exiting doors, supply and fit aluminium frame with 6 ^{mm}	No	2	
	safety laminated door and half glass doors, fit industrial door handle			
	with separate lockset, supply and fit 4 heavy duty hinges to door,			
	bottom half of door must be solid aluminium and top half must be			
	clear/ frosted glass			
	Plumbing certificate on completion.		Item	
	Remove all ruble from site		Item	
	Electrical COC to be issued on completion		Item	
	Allow the amount of R 50 000-00 (Fifty Thousand Rand) for			R50, 000-00
	contingency to be used at the discretion of the Principal Agent and			
	deducted in whole or in part if not required			
	NOTE: Contractor should always have project supervisor on			R0-00
	site in order to maintain NHLS standard and specification			
	TOTAL			
	PLUS 15% VAT			
	GRAND TOTAL			
	Estimated time to complete work			

NOTE:

Important Note:

- Always read specification in conjunction with Bill of Quantities and Plan (if plan is applicable and supplied).
- All Quantities measured are indicative and will be re-measured on completion.
- Specific products to be used, to be confirmed in Bill of Quantities.
- All materials and products to be used, to be ISO 9001 accredited.
- Due to the nature of our labs (operation 24 hours) the contractor will be expected to work after hours and over the weekend.
- Variation orders can only be approved in writing (via the email) by the NHLS Project Manager
- No additional or extra work done will be paid for unless the project manager has issued a variation order.
- NHLS Project Manager will conduct all inspections.
- The contractor should be required to move the equipment (furniture, benches, etc.) and put them back requested.
- Only material installed will be paid and not for any wastage (no material on site will be paid).
- NHLS delegates can also and contact the client or visit the work done as referred on the completion certificate.
- Contractor will be requested to **provide comprehensive safety file**; work will be only allowed to commence after the file has been formally approve by NHLS.
- A contractor is expected to sign a 37(2) Agreement (Form FMI 0008) before commencing with the project.
- No progress payment will be made less than R200,000.00.

[&]quot;Provide details and registration confirmation with CIDB in terms of the CIDB Act 38 of 2000. Provide proof of grading level 2 GB

References:

- NHLS delegates can also and contact the client or visit the work done as referred on the reference or completion certificate.
- All the contractors will be requested to provides NHLS with the following signed of stamped references or completion certificates of similar work done on company or departments letter head, not more than five years (5) old as per the table below

If QUOTE	REQUIRED REFERENCE OR COMPLETION	CONTRACT VALUE OF
VALUE	CERTIFICATES	PROJECT PREVIOUSLY
		DONE
	One(1) copy of contactable reference or completion certificate, on	
	client's letterhead, with contact details, valid e-mail address,	
R0-R50,000.00	office telephone, cell phone and business address	N/A
	Two(2) copies of contactable reference or completion certificate, ,	
R50,000.00 -	on client's letterhead, with contact details, valid e-mail address,	
R100.000.00	office telephone, cell phone and business address	N/A
	Three(3) copies of contactable reference or completion certificate,	
R100,000.00 -	, on client's letterhead, with contact details, valid e-mail address,	At least 1x R100,000.00 and
R200.000.00	office telephone, cell phone and business address	above
	Three(3) copies of contactable reference or completion certificate,	
R200,000.00	, on client's letterhead, with contact details, valid e-mail address,	At least 3x R200,000.00 and
and above	office telephone, cell phone and business address	above

GUARANTEE, MAINTENANCE, PENALTY AND RETENTION PERIOD

The Guarantee and Maintenance period shall be for 12 months commencing on the date of Practical completion and acceptance of the Installation. During the Guarantee period the Contractor shall repair all defects in the Installation which may arise as a result of inferior quality materials or faulty workmanship. 5% retention of the contract price will be held back for a period of 3 months after date of Practical completion and acceptance of the installation

The fact that the Installation will be used and occupied by the Employer during the guarantee period shall in no way exempt the Contractor from his responsibility under this clause

Should a non-urgent fault occur during the guarantee period the Contractor will be advised and he shall repair the fault in good time

Should a fault occur during the guarantee period, that is in the opinion of the Project Manager of an urgent nature, then the Contractor will be advised and shall proceed immediately to rectify the fault

Should a fault occur during the guarantee period, that is in the opinion of the Project Manager of an urgent nature, and the Contractor is not available, the Employer shall reserve the right to obtain the services of any available Contractor to repair the fault. The cost of such repair work shall be borne by the Contractor in accordance with the escalated rates. In such a case the faulty equipment shall be kept for scrutiny by the Contractor. If this occurs during the retention period and retention money is still due to the Contractor, such claim from the Alternative Contractor, will be deducted from the Retention fund

Should the frequency and breakdown/s, in the opinion of the Project Manager, become so regular as to constitute and unacceptable state of affairs or should the installation or portions thereof prove to be unacceptable, the Contractor shall upon receipt of a written instruction from the Project Manager, replace portions/components or even the entire installation if need be, at his own cost as prescribed by the Project Manager

Where the practical completion is not reached by the date stated in the Tender/RFQ document or by the revised date granted by the Project Manager, the Contractor shall be liable to a Penalty determent by the Project Manager, which is in this instance .1% (point 1 percent) of the Tender/RFQ Total value, Per Day

PRELIMINARIES

Tenderer's attention is drawn to the fact that the Hospital and Laboratory will be fully operational during the building process. The work will have to be carried out in phases and at times that must be liaised and agreed to with the Business Manager and Hospital Management. This might result in certain work being carried out at certain times only, even after hours of weekends. Also note that sensitive electronic equipment are in use and no work that cause a vibration can be carried out when these equipment are in operation. Operating theaters in the vicinity of the building work will also be in use during the building program and the Contractor must liaise closely with the Hospital Management and obtain their written consent and permission, before removing and/or servicing equipment/structures, that might interfere with the running of the theaters or any other service/s. The use of certain lifts for moving of material will also have to be agreed to with the Hospital Management. The tenderer must allow for this in his prices since no additional claim will be entertained in this regard

TENDERS SHOULD BE BASED ON THE FOLLOWING SPECIFICATIONS

SITE APPLICATION

Repair to cracks

Repairs to cracks 0.2^{mm} to 2^{mm}

Rake out with a scraped blade.

Remove dust and debris.

Fill with pure acrylic, paintable, flexible crack filler.

Cracks over 2mm

Open out with a carborundum disk into a V shape minimum 3^{mm} wide.

Remove dust and debris.

Wet the crack and fill with damp 1:4 cement/sand mortar properly compacted into the cracks.

Repairs to Mortar Joints

Scrape out unsound mortar

Point solidly with 1:3 cement/sand mortar properly compacted into the joints

Repairs to Painted Wall Surface Coating

Remove loose paint with a sharp paint a scraper or hand-held pneumatic engraving tools fitted with flat chisel heads Feather edges of tightly bonded paint with a rough to medium grit paper

Built up paint covering flush with general surface area

Preparation - Generally

Materials used in preparation to be types recommended by their manufacturers and the coating manufacturer for the situation and surfaces being prepared.

Apply in strict accordance with the manufacturers specification.

Apply oil based stoppers/fillers after priming. Apply water based stoppers/fillers before priming unless recommended otherwise by manufacturer. Patch prime water based stoppers/fillers when applied after priming.

Ensure that doors and opening windows, etc, are "eased" as necessary before coating. Prime any resulting bare areas.

Plastered surfaces and fibre cement boards to be washed down and allowed to dry completely.

Unfinished concrete surfaces clean with 1:4 solution of spirit of salts: water.

All floors where painting is to be carried out to be swept clean, walls dusted down and unpainted surfaces protected.

Efflorescence

Remove surface salts and other loose material with a stiff brush or coarse dry cloth.

Leave for 48 hours and repeat process if further efflorescence occurs.

Sand glossy surfaces to provide a key for finish.

Ironmongery

Remove from surfaces to be coated and re-fit on completion. Do not remove hinges unless instructed to do so

Previously Uncoated Timber

Ensure that large and loose knots are removed and made good with sound timber of the same species. Sand down flush Ensure that surfaces are clean and remove all oil, grease and excessive natural oils with suitable solvents Sand to a smooth, even finish with arrises rounded or eased

Remove resinous bleeding by heat, apply two coats of knotting to resinous areas and all knots and allow to dry Ensure that head of fasteners is countersunk sufficiently to hold stopping/filling. Fill nail and screw holes, joints, cracks, holes, depressions, open or coarse grain with matching coloured stopper/filler worked well in and finished off flush with surface. Sand smooth and remove dust

Sand down to remove all plaster stains pencil marks and other blemishes from timber that is to be oiled or stained

Previously Coated Timber

Strip any existing cracked or flaking varnish back to fresh wood

Sand down any discoloured areas to fresh wood

Ensure that surfaces are clean and remove all oil, grease and excessive natural oils with suitable solvents

Sound varnish to be sanded with 360 grit paper

Uncoated Masonry/Render

Remove dirt, surface deposits, loose and faking material with a stiff brush

Fill holes and cracks flush with surface, rub down

Unpainted Plaster

Remove dirt and surface deposits with a stiff brush

Rub down to remove nibs, trowel marks and plaster splashes

Lightly rub over trowelled glossy plaster with worn abrasive paper

Fill depressions, holes and cracks and lightly rub down flush with surface

Steel Generally

Remove all loose and faking paint

Feather edges of tightly bonding paint

Rusted Areas

Clean disk sand and wire brush to remove rust

Clean bare steel patches with a solvent wash

Rust convertor only to be used on small areas where hand cleaning is ineffective

Apply with a stiff brush ensuring penetration into any pitting

Inspect after two hours and recoat areas showing unconverted red rust

Prime surfaces as soon as possible after cleaning, and in any case within four hours

Coating

Painting Generally

Operatives must be appropriately skilled and experienced in the use of specified materials and methods of application Do not use materials that show any bittiness when applied. Do not thin or intermix unless specified or recommended otherwise. If materials are found to have been thinned without authorization, the Project Manager may require an additional application of additional coats

Any priming as soon as possible on the same day as preparation is completed, ensure that coats are of adequate thickness and suit surface porosity

Adjacent coats of the same material must be of a different tint to ensure that each coat provides complete coverage

Apply coatings to clean, dust free, suitable dry surfaces in dry atmospheric conditions and after any previous coats have hardened. Lightly abrade between coats as necessary

Apply coatings evenly to give a smooth finish of uniform colour, free from brush marks, nibs, sags, runs and other defects. Cut in neatly and cleanly. Do not splash or mark adjacent surfaces

Keep all surfaces clean and free from dust during coating and drying. Adequately protect completed work from damage

Painted Joinery/woodwork

Before priming preservative treated timber, any cut surfaces to be retreated and all end grain to be liberally coated allowing it to soak in before recoating it

Pre-primed woodwork to be lightly rubbed down and patch prime to match existing

Prime: One coat primer, two coats to end grain which will be painted

Finish: Two coats Alkyd gloss, sanded down between coats

Staining

Check with stain manufacturer if primer is required for the species of timber and type of previously applied treatment. Apply stain in flowing coats. Redistribute excess material by brushing before stain has set. Allow not less than 12 hours between coats

Varnishing

Thin first coat with white spirits according to manufacturer's recommendations

Brush well in avoiding aeration and lay off

Apply further coats of varnish, rubbing down lightly between coats along the grain

Bead Glazing to Coated Timber

Before Glazing: Apply first two coats to rebates and beads

Concealed Joinery Surfaces

Inaccessible parts of joinery constructions are to be primed and/or coated before assembly

Where one or more additional coats are specified to be applied, they must be applied to all surfaces, including those that will be concealed when incorporated into the building

Wooden Doors

Varnish or paint bottom edges before hanging

Completion

Ensure that opening lights/windows/hinges and other moving parts move freely. Remove all masking tape and temporary coverings afterwards

Protection

Adequately protect all surfaces that are not to be coated

Protect all surfaces from dust and damp

Where doors are delivered to site in a finished condition, provide all necessary protection to the doors when applying coatings to the frames

Air-conditioners

Contractor to provide adequate power supply to air con unit

12-month warrantee to be included

Contractor is liable for any damages to structure

All work must be SABS approved

Each air con to be separately wired via isolator from the DB board and connected with a circuit breaker (see size and Phase requirements as stipulated in Bill)

D/P Isolator to be installed and connected adjacent to air-con unit internally (see size and Phase requirements as stipulated in Bill)

Electrical Certificate of Compliance to be issued on completion

Allow for drilling through wall and plaster/ patch and paint afterwards. Piping to installed through walls only, never glass panes

All piping/cabling to be in PVC trunking / ducting. Allow for correct lengths

Units always to be heating and cooling (unless otherwise stipulated in Bill)

All piping, brackets, gas up to commissioning to be included in pricing

Supply units of the following Manufacturers: Samsung, LG, Carrier, Daiken, York or similar (in warrantee and guarantee)

All Air-cons to be Inverter type, unless specified of the BOQ

Plumbing

Only registered Plumbers to be employed for any plumbing & drainage work

Allow for $\pm 2m^2$ tiling above each basin and sink

Allow for A Grade Glazed white tiles, 152 x 152mm, 5 – 6.5mm thick

Sinks size: 1350^{mm} x 535^{mm} unless otherwise specified in bill of quantities

Sink mixer for tea room sink to be 15mm chrome plated brass cobra mixer type tap

All basins to be white glazed, each fitted with an approved 32mm chrome plated brass waste fitting with screwed outlet, and a 15mm chrome plated brass elbow action tap connected to water supply

All sinks to be standalone stainless steel sink, work area, splash back on Pre-manufactured 40 x 32^{mm} stainless steel square tubing frames, 4 legs on adjustable pedestals. Exposed surfaces having a smooth finish, each fitted with an approved 32mm chrome plated brass waste fitting with screwed outlet, and a 15mm chrome plated brass Hospital goose neck tap

Stainless steel grade 316 or Type 304 to be used for stainless steel sinks

All material to be SABS approved

Make sure all existing water pipes and waste is in good working condition

All existing basins and sinks to be washed and cleaned

On each water supply line, a ball valve need to be installed as close as possible to outlet, this includes basins, sinks, toilets

Each tap to be visibly marked with "H" or a "Red" mark for Hot water and "C" or a "Blue" mark for Cold water

Geysers: Install makes such as Franky, Kwikhot or similar. Install on a drip tray with drain pipe to outside, pressure valve, safety valve, shut off valve, overflow pipe. Isolator to be installed at least 1m from Geyser, hot and cold water supply lines to be bonded and earthed. Isolator to be wired to DB with dedicated double pole circuit breaker.


Toilets: these shall be deemed to include the following: WC Pan, flush valve or 11-liter cistern with flushing apparatus, float valve and flush pipe and all finishing's to pipes and cistern. To be the wash down type, approximately 400 high manufactured of white glazed fireclay or vitreous china, each provided with the compatible "P" or "S" –Traps, jointed to Pan. Pans and traps to be set on and encased in Class B concrete not less than 100mm thick at any point or position

Wall mounted bowl urinals: to be of white glazed fireclay or vitreous china, approximately 700 x 380mm in size with back flush entry, secured to wall with at least 2 concealed hanger brackets. Each urinal to be fitted with 38mm chrome plated domical grating, urinal complete with push button assembly, exposed type flush valve with ball-o-stop and wall

flange. • Chrome plate finish. • Additional toilet piston screw • Non-hold open feature, spreader and all other necessary chrome plated brass fittings as well as a chrome plated brass bottle trap

Hydro boil installations: Install always above sink (see bill of quantities for size)

Emergency shower: complete body shower with eye station. Flow rate to be 60 liters per minute. At floor level, 700mm below shower head, the radius of water reaching the floor should be 200mm. At the eye station flow rate should be 6 liters per minute at a flow pressure safe enough not to injure the User. This unit to be 1 meter from floor level. Make use of emergency showers as supplied by Broen, Bull Maurice Trading or similar



Water tanks Pumps



Electrical

Only registered Electricians to be employed for any electrical work

Wires to be used for sockets outlets; 2.5mm² PVC

Colour for 2- compartment steel/PVC power skirting unless differently specified in bill of quantities (colour to be confirmed)

Normal plugs to be white and dedicated plugs to be red

Electrician to consult with Lab Manager regarding lab equipment when circuit are installed to prevent overloading, new plug points to be wired from distribution board and marked properly

Legend card in DB to be up to date

Electrical Certificate of Completion to be issued on completion

All material to be SABS approved

All installations to comply with SANS10142 installation rules

All additional /replaced plugs, isolators and light switches must be labelled on the cover and Distribution Board Circuit breakers to be SABS approved and type and size to be confirmed with Project Manager before installation Hydroboils: wire from DB Board with 30Amp double pole isolator next to Unit (at least 1m away) and 20Amp circuit breaker in DB board

Shade ports

Item	Single	Double	Triple
Pitch Height	900	1350	1350
Clearance	2100	2100	2100
Width	3000	5000	7500
Length of span	5500	5500	5500
Cross	50 x 2	50 x 2	57 x 2
Cable	6mm galvanized	in all cases	
Hoops	42 x 2	42 x 2	50 x 2
Cantilever (bottom)	50 x 2		
Cantilever (top arm)	42 x 2		
Cantilever (brace)	34 x 2		
Columns	165 x 3.5 x 4000		
Columns	50 x 2	76 x 2	76 x 2
Foundations	500 x 600 x 900		

The hanging braces must be braced
The hanging brace must have a 12.5-degree angle
The hoops must be rolled on a rolling machine and not cranked/ bend
Colour green
The cotton used for sewing the nets must be UV resistant

Workbenches & Tops

Worktops to be 32^{mm} thick, either 600mm, 900mm or 1200mm, Formica brand post form - white (unless otherwise stipulated in Bill)

Where necessary 75mm holes must be drilled in worktops to accommodate computer cables and power supply to machinery and be made good with a plastic grommet

Pre-manufacture 30^{mm} x 30^{mm} steel square tubing frames as supplied by SA Lab or similar, sections of 1 000mm wide and 500mm deep or 1000mm wide and 800mm deep, for post form tops. All 4 legs to be on lockable castors or adjustable inserts as per BOQ wheel diameter 100mm. Bench Units to be equipped with water, basins, sinks, to be om adjustable pedestals. Benches could be 730mm or 900mm high (see bill of quantities) Sections to be bolted together, not welded. All steelwork to be epoxy powder coated in dove grey colour.

Cupboards

steel laboratory cupboards

Steel epoxy powder coated white cupboards to be manufactured and assembled as follows. Units specified in bill will be either a 4 drawer (450mm wide) or 2 doors with 1 shelve unit (750mm wide). Exterior and Interior to be White powder coated. Doors to be affixed with 2 brass heavy duty piano hinges each and drawers to be mounted on runners. Each drawer and door to be equipped with a PVC recessed handle. All floor cupboards to be on 4 castors each, front wheels to be lockable. All doors to be double paneled for stability and no wobbly door and cupboards will be accepted. See bill of quantities for sizes and combinations.

wooden cupboards

In kitchens timber cupboards to be manufactured and installed with 16mm melamine covered pressed wood. All cupboards to be on 100mm pedestals. Exterior to be Oak finish and Interior to be white finish. All visible exterior edges to be finished in Oak and internally white. Each drawer faces and door to have wrap around finish. Doors to be affixed on 2 hinges each and drawers on runners. Each drawer and door to be equipped with an aluminium handle

Doors

All doors to be hung in such a way that the clearance gap between door and frame after hanging shall not exceed 2mm at sides and head. The floor clearance to be preferably 2mm but may be increased to accommodate an uneven floor finish. Exterior doors shall be hung on brass hinges. Aluminium frame glass doors to have 6mm safety laminated glass fitted, to be hung on aluminium hinges, not less than 4 hinges on a 2 100mm high door. On higher doors at least 5 hinges should be fitted. The glass door must have a mid-rail with bottom half either glass or solid aluminium, the aluminium door profile must be 90mm all-round All exterior doors to be fitted with an aluminium and rubber weather strip at the bottom. Each door to be equipped with 2 door handles. Type to be confirmed by Project Manager. Behind every door a door stop should be installed on top of the floor to prevent the door handle making contact with the wall – clearance between wall and door handle to be approximately 20mm.

Paint

Two final coats of White paint to all surfaces, ceiling and walls. Door colours to be confirmed by Project Manager, if not varnished

Existing pipes against wall must be colour coded painted, for example gas, water, oxygen Rhino board surface to receive Rhinolite to a smooth finish on dry walls

Before painting can commence, every defect/uneven surface must be repaired

Patch prime new and exposed plaster areas with 1 coat and allow drying. Coat 1 may be thinned up to 10% with mineral turpentine to aid absorption. Allow 4 hours drying time at 23° c . Three (3) coats of paint to dry wall. Paint texture and type to match existing, Colour for walls and steel frames to be white unless otherwise confirmed by Project Manager One coat metal primer to steel work and two coats final oil based enamel

Paint to be Plascon double velvet, Dulux, Prominent or similar

VINYL Floors

Only use Heavy duty safety Vinyl flooring which should be slip resistant and factory sealed with Polyurethane as supplied by Marley or Polyfloor. Roll to be at least 2 metres wide and vinyl 2 - 2.5 mm thick. Colour to be confirmed by Project Manager. Sample to be signed off by Project Manager before installation commences

Ensure that the sub-floor is completely smooth, level, hard, dry and clean before laying commences

Joints to be butted, grooved and heat welded ensuring that the welding rod bonds to more than 70% of the sheet thickness. It is essential that on completion the installation be rolled, in both directions with an articulated 68kg three sectional metal floor roller.

Skirting; install coving where wall meets floor and continue with vinyl floor 100mm high. Finish off with Vinyl/PVC Ribbon

Installation to be done by an approved Installer in accordance with the Manufacturers specifications

TILE Floors

Ensure that the sub-floor is completely smooth, level, hard, dry and clean before laying commences

Only use A Grade Acid resisting Ceramic/ porcelain tiles, 10mm thick, 600^{mm} x 600^{mm} for floors and 600^{mm} x 200^{mm} for walls in size or as per BOQ

All tiles need to have "Aluminium Tile Edge Trim" where necessary. Bull nose or square one may be used

Use SABS approved tile cement and apply as per Manufacturers instructions (colour to be confirmed by Project Manager)

Use SABS approved water proof Acid resistant grout. Gaps 5 – 10mm (colour grey)

Skirtings to be 100mm high where required, coved at junction with floor and rounded on top edge

CARPET Floors

Ensure that the sub-floor is completely smooth, level, hard, dry and clean before laying commences. Installation to be done by an approved Installer in accordance with the Manufacturer's specifications

TILE Walls

Ensure that the wall is completely smooth, level, hard, dry and clean before laying commences

Only use A Grade Acid resisting Ceramic tiles, 10mm thick, 600 x 200mm in size

Use SABS approved tile cement and apply as per Manufacturers instructions (colour to be confirmed by Project Manager)

All tiles need to have "Aluminium Tile Edge Trim" where necessary. Bull nose or square one may be used

Use SABS approved water proof Acid resistant grout. Gaps 5 – 10mm (colour grey)

All edges and corners to be finished off with PVC edging strips. Colour to be confirmed per job depending on tile colour.

Glazing

All Internal glass in panes not exceeding 1.5m² of surface area shall be 4mm clear float glass

All Internal glass in panes exceeding 1.5m² of surface area shall be 6mm laminated safety glass with a Manufacturer's warranty against defects and discoloration

All Exterior glass up to a height of 10m in panes not exceeding 2.9m²of surface area shall be 6.38mm PVB Laminated annealed safety glass. Above 10m the Project Manager should appoint a Glazing Competent Person

Mirrors to comply with SABS requirements. Unframed mirrors to have polished edges

All glass in aluminium doors and frames to be fitted with 6mm laminated safety glass

All exterior facing windows to be tinted with Klingshield or similar product, unless otherwise stipulated. Colour to be confirmed by Project Manager

Blinds

Vertical Group 3 blinds to be installed (colour to be confirmed by Project Manager)

Blinds to be re-measured on site before manufacturing and installation

Vertical blinds to be 127mm

Horizontal blinds 50mm

Horizontal blinds to be either Aluminium/ Wood Venetian conformation on the BOQ

Measurements given is only for tendering purpose

Suspended ceilings

Install suspended ceilings as per Manufacturers instructions such as Donn Products or similar. Panels to be vinyl cladded smooth white panels, 1200 x 600 x 12.5mm on suspended pre-painted exposed tee trusses, including main and cross tees, hangers, grids, etc., all level and properly secured. At edges use 25mm pre-painted shadow line aluminium cornices

Partitioning

Drywall partitioning construction and support frame system including finishes to be as per Manufacturer's specifications

Minimum requirement GPG Gypsum Gyproe Standard 40 Db, ½ hour fire rating with a stud (63.5mm) and track system. Positioning at 600mm cc fixed to 63.5mm top & bottom track clad on both sides with 12.5mm taper edged rhino board affixed with 25mm drywall screws at 220mm cc

All corners to be finished off with drywall corner strips. All joints to be taped, jointed and smoothed before painting Aluminium skirtings to be affixed to all drywall partitioning unless otherwise specified

Door and window frames fitted in drywall partitioning to be installed as per Manufacturer's specifications

Lockers (Timber)

Timber lockers to be manufactured and assembled with 16mm melamine covered pressed wood. Exterior to be Oak melamine finish, including all visible edges. Interior to be White melamine finish, including all visible edges and backing. If the back side of any cupboard will be visible after installation, those exposed areas or entire area should be cladded with white melamine. Inside dimensions of each cubicle to be 300mm². Units to be assembled 3 on top of each other. Each locker to have a wrap around Oak melamine finished door, affixed with piano hinges. Each locker to be equipped with a lock and 2 keys as well as an aluminium handle (no plastic handles). Each stack of 3 to be assembled as 1 unit and 100mm adjustable chrome plated legs to be affixed underneath bottom locker.

Lab Coat Hooks

Lab coat hooks must be aluminium base and hooks with a minimum of three per set

Lockers (Steel)

Solid steel lockers which should be epoxy powder coated to be supplied. Sets to be single 4 tier lockers. Colour to Ivory/Beige/Karoo. Each door to be lockable and correct size padlocks with 2 keys each, per locker, to be provided

Locks

All exterior door locks to have 4 lever mortice locks with 2 keys each fitted (unless otherwise specified in bill)

All interior door locks to have 2 lever mortice locks with 2 keys each fitted (unless otherwise specified in bill)

All security type gates to have 7 lever locks with 2 keys each fitted

All timber lockers to have normal cupboard locks with 2 keys each fitted

All steel lockers to have padlocks with 2 keys each fitted

Steel shelving

Only powder coated grey steel shelving to be installed in storage areas, archives & wash up areas (no wood allowed). Shelving to be of an adjustable type with each shelve at least 500mm wide and 450mm deep. Bottom shelve to be at least 200mm from the floor and top shelve not higher than 2 100mm. In between top and bottom another 3 shelves, evenly spaced, to be fitted (in total 5 tier shelving). Each vertical steel supports to be affixed to the wall at, at least 2 positions in the top half. As supplied by Krost shelving or similar

Signage

All interior signs to be White Perspex with smooth edges, with vinyl (7 year) applied onto the Perspex All exterior signs to be White Chromadek, with vinyl (7 year) applied onto the metal

Pantone: Coated - 383C / Uncoated - 397 U

CMYK – C:40 M:0 Y:100 K0 RGB – R:166 G:206 B:54

Artwork to be signed off by Project Manager before sign is manufactured

PLEASE TAKE NOTE THAT THE ABOVE SPECIFICATIONS AND MEASUREMENTS ARE SUBJECT TO CHANGE AS MAY BE DETERMINED BY THE FINAL APPROVED DRAWINGS OR COMPULSARY SITE MEETING FOR THE JOB IN QUESTION

WORKS AGREEMENT

Contractor: The contactor shall:

- Provide adequate supervision and management of the works at all times.
- Provide toilet facilities for use by his workers except where provided by the client (NHLS).
- Storage space is not always available for material and sufficient arrangements should be catered for and included in pricing.
- Submit all local authority notices by the works.
- Comply with all statutes, regulations and bylaws of local or other authorities having jurisdiction regarding the execution of the works and obtain all certificates and other documents required by such authorities.
- Notify the Project Manager where compliance with any statute, regulation or bylaw requires a change or variation to the works upon which such change shall be deemed to be a contract instruction.
- Immediately begin the works and continue at a rate of progress satisfactory to the Project Manager in terms of the agreement.
- Comply with all contract instructions in good time.
- Bring the works, within the constructed period, to practical completion in terms of completion.
- Bring the works to final completion.
- Surplus material and waste to be carted away to a suitable dumping site to be found by the Contractor, outside the boundary of the site

Completion

Practical Completion

- The Project Manager shall inspect the works from time to time to give the contractor interpretations and guidance
 on the standard and state of completion of the works which he will require the contractor to achieve for practical
 completion
- The contractor shall inform the Project Manager of the date on which he expects to achieve practical completion
- The Project Manager shall inspect the works on or before the date requested by the contractor

Where the works:

- Has reached practical completion the Project Manager shall at once issue a certificate of practical completion to the contractor
- Has not reached practical completion the Project Manager shall issue a practical completion list to the contractor detailing the outstanding work to be done and defects to be rectified to achieve practical completion
- Is not ready for practical completion inspection the Project Manager shall issue a list as a general guide to the contractor of the outstanding areas of work and defects to be attended to before he can request a further inspection

Final Completion

- Within seven calendar days of practical completion the Project Manager shall prepare and issue to the contractor a final completion list detailing the incomplete work and defects to be rectified within a reasonable period
- The defects liability period of fourteen calendar days shall start on the date of practical completion
- On the expiry of the defects liability period the Project Manager shall immediately inspect the works for final completion. Where the works:
- Has reached final completion the Project Manager shall at once issue a certificate of final completion to the contractor
- Has not reached final completion the Project Manager shall issue a defects list to the contractor detailing any incomplete work and defects to be rectified before the Project Manager will undertake a further inspection
- Where the contractor has achieved final completion the latent defects liability period shall end three years from the date of final completion

Employer: The employer shall:

- Hand over the site to the contractor by the date stated in the schedule. The construction period and latent defects liability period shall commence with the handover of the site.
- Arrange for water, sewer and electrical connections as required and pay all fees concerning this
- Provide water and electricity as required for the execution of the works free of charge.
- Not issue instructions to, interfere with, hinder or obstruct any of the contractor's workers or any other persons employed or acting on behalf of the contractor.

Risk and Insurance

- The Contractor indemnifies the NHLS against any loss in respect of claims from other parties arising out of or due to the execution of the works or occupation of the site by the contractor consequent upon:
 - o Death or bodily injury or illness of any person.
 - o Physical loss and damage to any property other than the works.

- o Removal of or interference with lateral support of an adjoining property.
- The contractor shall take out insurances in respect of his employees as are required by law.
- Where, in the opinion of the Project Manager, loss and damage to the works due to the contractor's negligence the contractor shall be liable for such loss and damage.
- The contractor shall in all circumstances be at risk for loss of, or damage to his construction plant or vehicles.
- The contractor shall enclose the site along the facades where work is being done. He shall furthermore allow for all the required scaffolding, gantries, hoarding, etc. to safeguard pedestrian traffic on the sidewalks or paths as well as vehicular traffic in the streets
- The form of scaffolding, gantries, hoardings, etc., must be fully detailed in his "method statement" as previously required. It is not the intention to prohibit or deviate pedestrians or traffic during construction and Tenderers are to account for this when pricing the Tender
- Adequate warning signs/ lights/ etc. are to be employed where required. If the Tenderer requires the full pavement
 width and even part of the adjacent street, then he must make all the necessary arrangements with local authorities
 for the pavement and street closure as well as pay for all fees in connection therewith including the loss of income
 due to parking meters
- The existing premises will be occupied at all times and the Contractor will be required to keep all noise to a minimum

Safety

- From the date of site handover to the Contractor until the completed work is handed back to the Employer, the Contractor shall be responsible for maintaining safe working conditions on site
- The Contractor shall be responsible in terms of the Occupational Health and Safety Act, 1993 (Act No 85 of 1993)
 and the regulations promulgated in terms of the Act or Factories, Machinery and Buildings Work Act, whichever is
 applicable
- The Contractor shall be responsible for supplying and installing the required safety signs as determined by the Occupational Health and Safety Act, 1993 (Act No 85 of 1993) All safety signs shall comply with the requirements of the latest edition of SANS 11861 as Applicable

Programme

•	The Contractor shall submit his programme of work to the Project Manager not later than 14 days after the
	Contractor has been notified of the acceptance of his tender. If necessary, the Project Manager may instruct the
	Contractor to adjust his programme to suit other activities