



NATIONAL HEALTH
LABORATORY SERVICE

RFQ NO: 0007227/ 1948569/ 0007042

INVITATION TO QUOTE ON:

DESCRIPTION: SUPPLY AND INSTALL AIR CONDITIONERS TO VARIOUS DEPARTMENTS AT NELSON MANDELA LABORATORY

COMPULSORY SITE MEETING: It is strongly recommended that the Bidders visit the Labs to familiarize themselves with the installation requirements

ADDRESS:

CLOSING DATE;
ADDRESS:

FORM OF QUOTATION

SUPPLIER: _____

RFQ NO: 0007227/ 1948569/ 0007042

DESCRIPTION:**SUPPLY AND INSTALL AIR CONDITIONERS TO VARIOUS DEPARTMENTS AT NELSON MANDELA LABORATORY**

Description	Unit	Quantity	Rate	Cost excl vat
Haematology:				
Remove existing air conditioner and remove from site	No	1		
Supply and install 48 000 BTU Ceiling Cassette Unit, heating and cooling air conditioner, must be inverter type using R410A refrigerant, install as per specification , air con type must be: LG, Carrier, York, Samsung, or Daiken or similar	No	1		
Re-connect to existing power supply	No	1		
Microbiology:				
Supply and install 48 000 BTU Ceiling Cassette Unit, heating and cooling air conditioner, must be inverter type using R410A refrigerant, install as per specification , air con type must be: LG, Carrier, York, Samsung, or Daiken or similar	No	1		
Supply and install 30 amp three phase isolator at air con wired from distribution board including 1 x 30 amp three phase circuit breaker, allow for cabling, trunking, bends and end caps	No	1		
Supply electrical COC certificate		Item		
Histology:				
Supply and install 12 000 BTU Midwall split Unit, heating and cooling air conditioner, must be inverter type using R410A refrigerant, install as per specification , air con type must be: LG, Carrier, York, Samsung, or Daiken or similar	No	1		
Supply and install 30 amp single phase isolator at air con wired from distribution board including 1 x 20 amp single phase circuit breaker, allow for cabling, trunking, bends and end caps	No	1		
Supply electrical COC certificate				
NOTE: Contractor should always have project supervisor on site in order to maintain NHLS standard and specification				
TOTAL				
PLUS 15% VAT				
GRAND TOTAL				
Estimated time to complete work above				

NOTE:

“Provide details and registration confirmation with CIDB in terms of the CIDB Act 38 of 2000.

Provide proof of grading level 1ME

Technical mandatory documents which should be included on submission

no	Certificate and or license	comply	Do not comply
1	Air conditioners trade test certificate(wher air conditioners included)		
2	Electrical Wire man 's license		
3	Specify air conditioner brand		
4	Plumbing Trade test certificate	N/A	
5	Provide copy of CV and Certificate of experienced project manager to manage the project		

Important Note:

- Always read specification in conjunction with Bill of Quantities and Plan (if plan is applicable and supplied).
- All Quantities measured are indicative and will be re-measured on completion.
- Specific products to be used, to be confirmed in Bill of Quantities.
- All materials and products to be used, to be ISO 9001 accredited.
- Due to the nature of our labs (operation 24 hours) **the contractor will be expected to work after hours and over the weekend.**
- Variation orders can only be approved in writing (via the email) by the NHLS Project Manager
- No additional or extra work done will be paid for unless the project manager has issued a variation order.
- NHLS Project Manager will conduct all inspections.
- The contractor should be required to move the equipment (furniture, benches, etc.) and put them back requested.
- Only material installed will be paid and not for any wastage (no material on site will be paid).
- NHLS delegates can also and contact the client or visit the work done as referred on the completion certificate.
- Contractor will be requested to **provide comprehensive safety file**; work will be only allowed to commence after the file has been formally approve by NHLS.
- A contractor is expected to **sign a 37(2) Agreement** (Form – FMI 0008) before commencing with the project.
- No progress payment will be made less than R200,000.00.

References:

- NHLS delegates can also and contact the client or visit the work done as referred on the reference or completion certificate.