1 **1 LOWER GROUND FLOOR LAYOUT**
1 : 50



5 **Section 24**
1 : 20



TYPE 1



TYPE 2

4 **SLAB CONSTRUCTION JOINTS**
1 : 10



FILL COMPACTED IN LAYERS N/E 150mm TO 95% MOD AASHTO & SUBGRADE TO BE SCARIFIED & COMPACTED TO 90% MOD AASHTO, ALL@OMC

2 **DETAIL TYPICAL LAYERWORKS**
1 : 10



3 **DETAIL TYPICAL SAW-CUT JOINT**
1 : 10

GENERAL NOTES

1. ALL WORK TO BE CONSTRUCTED IN ACCORDANCE WITH NATIONAL BUILDING REGULATIONS, SABS 0100, SABS 1200 GB,GE,GF & THE PROJECT SPECIFICATIONS.
2. DO NOT SCALE ANY DRAWINGS.
3. WORK TO FIGURED DIMENSIONS ONLY.
4. ANY DISCREPANCIES ON THIS DRAWING TO BE BROUGHT TO THE ENGINEER'S ATTENTION PRIOR TO THE IMPLEMENTATION OF ANY WORK.
5. ALL COLUMNS ARE ON CENTRE LINES UNLESS SHOWN OTHERWISE.
6. ALL LOAD BEARING BRICKWORK IS TO BE CONSTRUCTED USING 14MPa BRICKS.
7. THE CONTRACTOR IS TO MAINTAIN A FULL SET OF WORKING DRAWINGS ON SITE.
8. THE CONTRACTOR IS TO VERIFY ALL DIMENSIONS ON SITE.
9. ALL CONCRETE SIZES DO NOT I NCLUDE FINISHES UNLESS NOTED OTHERWISE.
10. THIS DRAWING IS TO BE READ IN CONJUNCTION WITH ALL CONTRACT SPECIFICATIONS.
11. FOR RAINWATER DRIPS, CHAMFERS AND CONSTRUCTION JOINTS REFER TO ARCHITECT'S DRAWINGS UNLESS OTHERWISE SHOWN ON THIS DRAWING.
12. THE ENGINEER SHOULD BE GIVEN 48 HOURS NOTICE PRIOR TO ANY NECESSARY SITE INSPECTION.

CONCRETE NOTES

13. ALL REINFORCED CONCRETE WORK TO COMPLY WITH THE LATEST REQUIREMENTS OF SABS 1200 OR AMENDMENTS THEREOF.
14. ALL CONCRETE TO BE ADEQUATELY VIBRATED.
15. A SET OF THREE CUBES TO BE MADE PER MAJOR POUR AND TESTED AT 28 DAYS.
16. CONCRETE FINISHES AS SPECIFIED BY ARCHITECT.
17. ALL REINFORCEMENT IS TO BE INSPECTED BY THE ENGINEER PRIOR TO CASTING OF ANY CONCRETE.
18. ERECTION AND STRIPPING OF FORMWORK AND CURING OF CONCRETE TO BE STRICTLY TO SABS 1200 OR LATEST AMENDMENTS THEREOF.
19. THE CONTRACTOR IS RESPONSIBLE FOR MAINTAINING THE REINFORCEMENT IN THE CORRECT POSITION AT ALL TIMES.
20. T.O.C. DENOTES TOP OF CONCRETE LEVEL.
21. COVER TO CONCRETE REINFORCEMENT:
    a) FOUNDATIONS 40mm
    b) COLUMNS 25mm
    c) BEAMS 25mm
    d) SLABS 25mm
22. CONCRETE STRENGTH AT 28 DAYS
    COLUMNS - 30MPa
    WALLS - 25MPa
    BEAMS - 25MPa
    SLABS - 25MPa
    STAIRS - 25MPa
    BASES - 25MPa
    BLINDING - 10MPa

PROJECT MANAGER

HAPPRE GROUP

CLIENT

NATIONAL HEALTH LABORATORY SERVICE

NATIONAL HEALTH LABORATORY SERVICE

● CONCEPT DRAWING	NAME		
	SIGNATURE		DATE
○ TENDER DRAWING	NAME		
	SIGNATURE		DATE
○ APPROVED FOR CONSTRUCTION	NAME		
	SIGNATURE		DATE
○ AS-BUILT DRAWING	NAME		
	SIGNATURE		DATE

DATE:	DRAWN:	DESIGNED:	CHECKED:
19.09.2023	G. MACHIPISA	R.G. MUSWERE	R.G. MUSWERE

Rev.	Date	Description	BY	DRAWN	CHCKD

LHE. Africa
You imagine it, we engineer it
Consulting Structural & Civil Engineers
19 TENDELE ROAD, DOUGLASDALE
engineer@lheafrica.co.za
+27617681270

DRAWING TITLE: LOWER GROUND FLOOR LAYOUT

PROJECT TITLE: **NHLS NEW LABORATORY AND OFFICE**

SCALE AT A0: As indicated

DRAWING STATUS: **INFORMATION**

DISCIPLINE: STRUCTURAL

JOB No.: **BR_LHE0224**

DRAWING No.: **01**

ISSUE No.: A